

**P-07-99**

## **Oskarshamn site investigation**

### **Hydraulic injection tests in borehole KLX13A**

#### **Subarea Laxemar**

Cristian Enachescu, Stephan Rohs  
Golder Associates GmbH

September 2007

**Svensk Kärnbränslehantering AB**

Swedish Nuclear Fuel  
and Waste Management Co  
Box 5864  
SE-102 40 Stockholm Sweden  
Tel 08-459 84 00  
+46 8 459 84 00  
Fax 08-661 57 19  
+46 8 661 57 19



## **Oskarshamn site investigation**

### **Hydraulic injection tests in borehole KLX13A**

#### **Subarea Laxemar**

Cristian Enachescu, Stephan Rohs  
Golder Associates GmbH

September 2007

*Keywords:* Site/project, Hydrogeology, Hydraulic tests, Injection test, Hydraulic parameters, Transmissivity, Constant head.

This report concerns a study which was conducted for SKB. The conclusions and viewpoints presented in the report are those of the authors and do not necessarily coincide with those of the client.

Data in SKB's database can be changed for different reasons. Minor changes in SKB's database will not necessarily result in a revised report. Data revisions may also be presented as supplements, available at [www.skb.se](http://www.skb.se).

A pdf version of this document can be downloaded from [www.skb.se](http://www.skb.se).

## Abstract

Hydraulic injection tests have been performed in Borehole KLX13A at the Laxemar area, Oskarshamn. The tests are part of the general program for site investigations and specifically for the Laxemar subarea. The hydraulic testing programme has the aim to characterise the rock with respect to its hydraulic properties of the fractured zones and rock mass between them. Data is subsequently delivered for the site descriptive model.

This report describes the results and primary data evaluation of the hydraulic injection tests in borehole KLX13A performed between 12<sup>th</sup> and 23<sup>rd</sup> of February 2007.


The objective of the hydrotests was to describe the rock around the borehole with respect of hydraulic parameters, mainly transmissivity (T) and hydraulic conductivity (K) at different measurement scales of 100 m and 20 m sections. Transient evaluation during flow and recovery period provided additional information such as flow regimes, hydraulic boundaries and cross-over flows. Constant pressure injection tests were conducted between 102.50–582.50 m below ToC. The results of the test interpretation are presented as transmissivity, hydraulic conductivity and hydraulic freshwater head.

# Sammanfattning

Injektionstester har utförts i borrhål KLX13A i delområde Laxemar, Oskarshamn. Testerna är en del av SKB:s platsundersökningar. Hydraultestprogrammet där injektionstesterna ingår har som mål att karakterisera berget med avseende på dess hydrauliska egenskaper av sprickzoner och mellanliggande bergmassa. Data från testerna används vid den platsbeskrivande modelleringen av området.

Denna rapport redovisar resultaten och utvärderingar av primärdata de hydrauliska injektionstesterna i borrhål KLX13A. Testerna utfördes mellan den 12 till den 23 Februari 2007.

Syftet med hydraultesterna var framförallt att beskriva bergets hydrauliska egenskaper runt borrhålet med avseende på hydrauliska parametrar, i huvudsak transmissivitet (T) och hydraulisk konduktivitet (K) vid olika mätskalor av 100 m och 20 m sektioner. Transient utvärdering under injektions- och återhämtningsfasen gav ytterligare information avseende flödesgeometri, hydrauliska gränser och sprickläckage. Injektionstester utfördes mellan 102,50–582,50 m borrhålslängd. Resultaten av testutvärderingen presenteras som transmissivitet, hydraulisk konduktivitet och grundvattennivå uttryckt i ekvivalent sötwaterpelare (fresh-water head).



Borehole KLX13 A – Summary of results.

# Innehåll

<b>1</b>	<b>Introduction</b>	9
<b>2</b>	<b>Objective and scope</b>	11
2.1	Borehole	11
2.2	Injection tests	13
2.3	Control of equipment	14
<b>3</b>	<b>Equipment</b>	15
3.1	Description of equipment	15
3.2	Sensors	19
3.3	Data acquisition system	20
<b>4</b>	<b>Execution</b>	21
4.1	Preparations	21
4.2	Length correction	21
4.3	Execution of field work	21
4.3.1	Test principle	21
4.3.2	Test procedure	22
4.4	Data handling/post processing	23
4.5	Analyses and interpretations	24
4.5.1	Analysis software	24
4.5.2	Analysis approach	24
4.5.3	Analysis methodology	24
4.5.4	Correlation between storativity and skin factor	26
4.5.5	Determination of the ri-index and calculation of the radius of influence (ri)	26
4.5.6	Steady state analysis	27
4.5.7	Flow models used for analysis	27
4.5.8	Calculation of the static formation pressure and equivalent freshwater head	28
4.5.9	Derivation of the recommended transmissivity and the confidence range	28
4.6	Nonconformities	29
<b>5</b>	<b>Results</b>	31
5.1	100 m single-hole injection tests	31
5.1.1	Section 102.50–205.50 m, test no. 1, injection	31
5.1.2	Section 202.50–302.50 m, test no. 1, injection	32
5.1.3	Section 302.50–402.50 m, test no. 1, injection	32
5.1.4	Section 395.50–495.50 m, test no. 1, injection	33
5.1.5	Section 482.50–582.50 m, test no. 1, injection	34
5.2	20 m single-hole injection tests	35
5.2.1	Section 102.50–122.50 m, test no. 1, injection	35
5.2.2	Section 122.50–142.50 m, test no. 1, injection	35
5.2.3	Section 142.50–162.50 m, test no. 1, injection	36
5.2.4	Section 162.50–182.50 m, test no. 1, injection	37
5.2.5	Section 182.50–202.50 m, test no. 1, injection	37
5.2.6	Section 202.50–222.50 m, test no. 1, injection	38
5.2.7	Section 222.50–242.50 m, test no. 1, injection	39
5.2.8	Section 242.50–262.50 m, test no. 1, injection	39
5.2.9	Section 262.50–282.50 m, test no. 1, injection	40
5.2.10	Section 282.50–302.50 m, test no. 1, injection	41
5.2.11	Section 302.50–322.50 m, test no. 1, injection	41

5.2.12	Section 322.50–342.50 m, test no. 1, injection	42
5.2.13	Section 342.50–362.50 m, test no. 1, injection	43
5.2.14	Section 355.50–375.50 m, test no. 1, injection	43
5.2.15	Section 375.50–395.50 m, test no. 1, injection	44
5.2.16	Section 395.50–415.50 m, test no. 1, injection	45
5.2.17	Section 415.50–435.50 m, test no. 1, injection	45
5.2.18	Section 435.50–455.50 m, test no. 1, injection	46
5.2.19	Section 455.50–475.50 m, test no. 1, injection	47
5.2.20	Section 475.50–495.50 m, test no. 1, injection	47
5.2.21	Section 493.00–513.00 m, test no. 1, injection	48
5.2.22	Section 507.00–527.00 m, test no. 1, injection	49
5.2.23	Section 527.00–547.00 m, test no. 1, injection	49
5.2.24	Section 547.00–567.00 m, test no. 1, injection	50
5.2.25	Section 562.50–582.50 m, test no. 1, injection	51
5.2.26	Section 583.50–595.85 m (bottom zone), test no. 1	51
<b>6</b>	<b>Summary of results</b>	<b>53</b>
6.1	General test data and results	54
6.2	Correlation analysis	62
6.2.1	Comparison of steady state and transient analysis results	62
6.2.2	Comparison between the matched and theoretical wellbore storage coefficient	63
<b>7</b>	<b>Conclusions</b>	<b>65</b>
7.1	Transmissivity	65
7.2	Equivalent freshwater head	65
7.3	Flow regimes encountered	65
<b>8</b>	<b>References</b>	<b>67</b>
<b>Appendices attached on CD</b>		
<b>Appendix 1</b> File Description Table		
<b>Appendix 2</b> Test Analyses Diagrams		
<b>Appendix 3</b> Test Summary Sheets		
<b>Appendix 4</b> Nomenclature		
<b>Appendix 5</b> SICADA Data Tables		

# 1 Introduction

A general program for site investigations presenting survey methods has been prepared /SKB 2001/, as well as a site-specific program for the investigations in the Simpevarp area /SKB 2006/. The hydraulic injection tests form part of the site characterization program under item 1.1.5.8 in the work breakdown structure of the execution programme, /SKB 2002/.

Measurements were carried out according in borehole KLX13A between 12<sup>th</sup> and 23<sup>rd</sup> of February 2007 following the methodology described in SKB MD 323.001 and in the Activity Plan AP PS 400-07-006 (SKB controlling documents). Data and results were delivered to the SKB site characterization database SICADA and are traceable by the Activity Plan number.

The hydraulic testing programme has the aim to characterise the rock with respect to its hydraulic properties of the fractured zones and rock mass between them. This report describes the results and primary data evaluation of the hydraulic injection tests in borehole KLX13A. The commission was conducted by Golder Associates AB and Golder Associates GmbH.


Borehole KLX13A is situated in the Laxemar area approximately 3 km northwest of the nuclear power plant of Simpevarp, Figure 1-1. The borehole was drilled from March 2006 to August 2006 at 595.85 m length with an inner diameter between 341 mm and 160 mm to a depth of 99.9 m and further on of 76 mm to the bottom of the borehole. The inclination of the borehole is  $-82.25^\circ$ . The upper 11.75 m is cased with large diameter telescopic casing ranging from diameter (outer diameter) 208–323 mm. A cone casing is placed from 96.11 m to 101.21 m ranging from diameter (outer diameter) 100–104 mm.

The work was carried out in accordance with Activity Plan AP PS 400-07-006. In Table 1-1 controlling documents for performing this activity are listed. Activity plan and Method Descriptions are SKB's internal controlling documents. Measurements were conducted utilising SKB's custom made testing equipment PSS2.

**Table 1-1. Controlling documents for the performance of the activity.**

<b>Activity Plan</b>	<b>Number</b>	<b>Version</b>
Hydraulic pumping and injection tests in borehole KLX13A.	AP PS 400-07-006	1.0
<b>Method Descriptions</b>	<b>Number</b>	<b>Version</b>
Analysis of injection and single-hole pumping tests.	SKB MD 320.004e	1.0
Hydraulic injection tests.	SKB MD 323.001e	1.0
Instruktion för rengöring av borrhålsutrustning och viss markbaserad utrustning.	SKB MD 600.004	1.0
Instruktion för längdkalibrering vid undersökningar i kärnborrhål.	SKB MD 620.010	1.0
Allmänna ordning-, skydds- och miljöregler för platsundersökningar Oskarshamn.	SKB SDPO-003	1.0
Miljökontrollprogram Platsundersökningar.	SKB SDP-301	1.0
Hantering av primärdata vid platsundersökningar.	SKB SDP-508	1.0





*Figure 1-1. The investigation area Laxemar, Oskarshamn with location of borehole KLX13A.*

## 2 Objective and scope

The objective of the hydrotests in borehole KLX13A is to describe the rock around the borehole with respect to hydraulic parameters, mainly transmissivity (T) and hydraulic conductivity (K). This is done at different measurement scales of 100 m and 20 m sections. Among these parameters transient evaluation during the flow and recovery period provides additional information such as flow regimes, hydraulic boundaries and cross-over flows.

The scope of work consisted of preparation of the PSS2 tool which included cleaning of the down-hole tools, calibration and functional checks, injection tests of 100 m and 20 m test sections, analyses and reporting.

Preparation for testing was done according to the Quality plan. This step mainly consists of functions checks of the equipment to be used, the PSS2 tool. Calibration checks and function checks were documented in the daily log and/or relevant documents.

The following hydraulic injection tests were performed between 12<sup>th</sup> and 23<sup>rd</sup> February 2007.

Furthermore, the response in the bottom zone during the last 20 m test (562.50–582.50) was analysed.

### 2.1 Borehole

The borehole is telescope drilled with specifications on its construction according to Table 2-2. The reference point of the borehole is the centre of top of casing (ToC), given as elevation in the table below. The Swedish National coordinate system (RT90) is used in the x-y direction and RHB70 in the z-direction. Northing and Easting refer to the top of the boreholes at the ground surface. The borehole diameter in Table 2-2 refers to the final diameter of the drill bit after drilling to full depth.

**Table 2-1. Performed injection tests at borehole KLX13A.**

No. of injection tests*	Interval	Positions	Time/test	Total test time
5	100 m	102.50–582.50 m	125 min	10.4 hrs
25	20 m	102.50–582.50 m	90 min	37.5 hrs
			Total:	47.9 hrs

\* excluding repeated tests

**Table 2-2. Information about KLX13A (from SICADA 2007-01-17).**

Title	Value				
Comment:	No comment exists				
Borehole length (m):	595.85				
Reference level:	TOC				
Drilling Period (s):	From date	To date	Secup (m)	Seclow (m)	Drilling type
	2006-03-23	2006-06-30	0.15	99.86	Percussion drilling
	2006-05-19	2006-08-16	99.86	595.85	Core drilling
Starting point coordinate: (centerpoint of TOC)	Length (m)	Northing (m)	Easting (m)	Elevation (m.a.s.l.)	Coord system
	0.00	6,367,547.14	1,546,787.36	24.15	RT90-RHB70
	3.00	6,367,546.89	1,546,787.08	21.18	RT90-RHB70
Angles:	Length (m)	Bearing	Inclination (– = down)		
	0.00	224.48	–82.25	RT90-RHB70	
Borehole diameter:	Secup (m)	Seclow (m)	Hole diam (m)		
	0.15	6.15	0.341		
	6.15	11.75	0.252		
	11.75	99.76	0.197		
	99.76	99.86	0.160		
	99.86	101.21	0.086		
	101.21	595.85	0.076		
Core diameter:	Secup (m)	Seclow (m)	Core diam (m)		
	99.86	100.36	0.072		
	100.36	595.85	0.050		
Casing diameter:	Secup (m)	Seclow (m)	Case in (m)	Case out (m)	
	0.00	11.75	0.200	0.208	
	0.15	6.15	0.301	0.323	
Cone dimensions:	Secup (m)	Seclow (m)	Cone in (m)	Cone out (m)	
	96.11	101.21	0.100	0.104	
Grove milling:	Length (m)	Trace detectable			
	110.000	YES			
	150.000	YES			
	200.000	YES			
	250.000	YES			
	300.000	YES			
	350.000	YES			
	400.000	YES			
	450.000	YES			
	500.000	YES			
	550.000	YES			
	581.000	YES			

## 2.2 Injection tests


Injection tests were conducted according to the Activity Plan AP PS 400-07-006 and the Method Description for hydraulic injection tests, SKB MD 323.001 (SKB internal documents). Tests were done in 100 m and 20 m test sections between 102.50–582.50 m below ToC (see Table 2-3). The initial criteria for performing injection tests in 20 m sections was a measurable flow of  $Q > 0.001$  L/min in the previous measured 100 m covering the smaller test sections (see Figure 2-1). The measurements were performed with SKB's custom made equipment for hydraulic testing called PSS2.

No other additional measurements except the actual hydraulic tests and related measurements of packer position and water level in annulus of borehole KLX13A were conducted.

**Table 2-3. Tests performed.**

Bh ID	Test section (m bToC)	Test type <sup>1</sup>	Test no	Test start date, time	Test stop date, time
KLX13A	102.50–202.50	3	1	2007-02-15 09:48	2007-02-15 14:06
KLX13A	202.50–302.50	3	1	2007-02-15 15:34	2007-02-15 17:30
KLX13A	302.50–402.50	3	2	2007-02-16 07:58	2007-02-16 10:27
KLX13A	395.50–495.50	3	3	2007-02-16 11:52	2007-02-16 13:43
KLX13A	482.50–582.50	3	1	2007-02-16 15:44	2007-02-16 17:35
KLX13A	102.50–122.50	3	1	2007-02-17 18:25	2007-02-17 20:28
KLX13A	122.50–142.50	3	2	2007-02-18 08:25	2007-02-18 10:31
KLX13A	142.50–162.50	4B	1	2007-02-18 11:07	2007-02-18 12:53
KLX13A	162.50–182.50	3	2	2007-02-18 13:24	2007-02-18 14:46
KLX13A	182.50–202.50	3	1	2007-02-18 16:10	2007-02-18 17:42
KLX13A	202.50–222.50	3	2	2007-02-18 18:12	2007-02-18 19:32
KLX13A	222.50–242.50	3	1	2007-02-19 09:02	2007-02-19 10:27
KLX13A	242.50–262.50	3	2	2007-02-19 11:04	2007-02-19 12:53
KLX13A	262.50–282.50	3	1	2007-02-19 14:13	2007-02-19 15:40
KLX13A	282.50–302.50	3	1	2007-02-19 16:17	2007-02-19 17:40
KLX13A	302.50–322.50	3	1	2007-02-19 18:12	2007-02-19 19:37
KLX13A	322.50–342.50	3	1	2007-02-20 08:18	2007-02-20 09:42
KLX13A	342.50–362.50	3	1	2007-02-20 10:20	2007-02-20 11:43
KLX13A	355.50–375.50	3	1	2007-02-20 12:56	2007-02-20 14:18
KLX13A	375.50–395.50	3	1	2007-02-20 15:00	2007-02-20 16:26
KLX13A	395.50–415.50	3	1	2007-02-20 17:07	2007-02-20 18:30
KLX13A	415.50–435.50	3	1	2007-02-21 08:38	2007-02-21 10:02
KLX13A	435.50–455.50	3	1	2007-02-21 10:41	2007-02-21 12:03
KLX13A	455.50–475.50	3	1	2007-02-21 13:02	2007-02-21 14:30
KLX13A	475.50–495.50	3	1	2007-02-21 15:28	2007-02-21 16:54
KLX13A	493.00–513.00	3	1	2007-02-21 17:33	2007-02-21 18:58
KLX13A	507.00–527.00	3	1	2007-02-22 08:14	2007-02-22 09:36
KLX13A	527.00–547.00	3	1	2007-02-22 10:14	2007-02-22 11:38
KLX13A	547.00–567.00	3	1	2007-02-22 13:02	2007-02-22 14:22
KLX13A	562.50–582.50	3	1	2007-02-22 15:00	2007-02-22 17:15
KLX13A	583.50–595.85	2	1	2007-02-22 15:00	2007-02-22 17:15

1) 2: Interference test; 3: Injection test; 4B Pulse injection test



\* eventually tests performed after specific discussion with SKB

**Figure 2-1.** Flow chart for test sections.

## 2.3 Control of equipment

Control of equipment was mainly performed according to the Quality plan. The basis for equipment handling is described in the “Mätssystembeskrivning” SKB MD 345.101-123 which is composed of two parts 1) management description, 2) drawings and technical documents of the modified PSS2 tool.

Function checks were performed before and during the tests. Among these pressure sensors were checked at ground level and while running in the hole calculated to the static head. Temperature was checked at ground level and while running in. Leakage checks at joints in the pipe string were done at least every 100 m of running in.

Any malfunction was recorded, and measures were taken accordingly for proper operation. Approval was made according to SKB site manager, or Quality plan and the “Mätssystembeskrivning”.


## 3 Equipment

### 3.1 Description of equipment

The equipment called PSS2 (Pipe String System 2) is a highly integrated tool for testing boreholes at great depth (see conceptual drawing in the next Figure). The system is built inside a container suitable for testing at any weather. Briefly, the components consists of a hydraulic rig, down-hole equipment including packers, pressure gauges, shut-in tool and level indicator, racks for pump, gauge carriers, breakpins, etc shelves and drawers for tools and spare parts.

There are three spools for a multi-signal cable, a test valve hose and a packer inflation hose. There is a water tank for injection purposes, pressure vessels for injection of packers, to open test valve and for low flow injection. The PSS2 has been upgraded with a computerized flow regulation system. The office part of the container consists of a computer, regulation valves for the nitrogen system, a 24 V back-up system in case of power shut-offs and a flow regulation board.

PSS2 is documented in photographs 1–6.



*Figure 3-1. A view of the layout and equipment of PSS2.*






*Photo 1. Hydraulic rig.*




*Photo 2. Rack for pump, down-hole equipment, workbench and drawers for tools.*



*Photo 3. Computer room, displays and gas regulators.*



*Photo 4. Pressure vessels for test valve, packers and injection.*



*Photo 5. Positioner, bottom end of down-in-hole string*



*Photo 6. Packer and gauge carrier.*

The down-hole equipment consists from bottom to top of the following equipment:

- Level indicator – SS 630 mm pipe with OD 73 mm with 3 plastic wheels connected to a Hallswitch.
- Gauge carrier – SS 1.5 m carrying bottom section pressure transducer and connections from positioner.
- Lower packer – SS and PUR 1.5 m with OD 72 mm, stiff ends, tightening length 1.0 m, maximum pressure 6.5 MPa, working pressure 1.6 MPa.
- Gauge carrier with breakpin – SS 1.75 m carrying test section pressure transducer, temperature sensor and connections for sensors below. Breakpin with maximum load of 47.3 ( $\pm$  1.0) kN. The gauge carrier is covered by split pipes and connected to a stone catcher on the top.
- Pop joint – SS 1.0 or 0.5 m with OD 33 mm and ID 21 mm, double O-ring fittings, trapezoid thread, friction loss of 3kPa/m at 50 L/min.
- Pipe string – SS 3.0 m with OD 33 mm and ID 21 mm, double O-ring fittings, trapezoid thread, friction loss of 3kPa/m at 50 L/min.
- Contact carrier – SS 1.0 m carrying connections for sensors below.
- Upper packer – SS and PUR 1.5 m with OD 72 mm, fixed ends, seal length 1.0 m, maximum pressure 6.5 MPa, working pressure 1.6 MPa.
- Breakpin – SS 250 mm with OD 33.7 mm. Maximum load of 47.3 ( $\pm$  1.0) kN.
- Gauge carrier – SS 1.5 m carrying top section pressure transducer, connections from sensors below. Flow pipe is double bent at both ends to give room for sensor equipment. The pipe gauge carrier is covered by split pipes.
- Shut-in tool (test valve) – SS 1.0 m with a OD of 48 mm, Teflon coated valve piston, friction loss of 11 kPa at 10 L/min (260 kPa–50L/min). Working pressure 2.8–4.0 MPa. Breakpipe with maximum load of 47.3 ( $\pm$  1.0) kN. The shut-in tool is covered by split pipes and connected to a stone catcher on the top.

The tool scheme is presented in Figure 3-2.






Figure 3-2. Schematic drawing of the down-hole equipment in the PSS2 system.

## 3.2 Sensors

**Table 3-1. Technical specifications of sensors.**

Keyword	Sensor	Name	Value/range	Unit	Comments
P <sub>sec,a,b</sub>	Pressure	Druck PTX 162-1464abs	9–30	VDC	
			4–20	mA	
			0–13.5	MPa	
			± 0.1	% of FS	
T <sub>sec,surf,air</sub>	Temperature	BGI	18–24	VDC	
			4–20	mA	
			0–32	°C	
			± 0.1	°C	
Q <sub>big</sub>	Flow	Micro motion	0–100	kg/min	Massflow
		Elite sensor	± 0.1	%	
Q <sub>small</sub>	Flow	Micro motion	0–1.8	kg/min	Massflow
		Elite sensor	± 0.1	%	
p <sub>air</sub>	Pressure	Druck PTX 630	9–30	VDC	
			4–20	mA	
			0–120	KPa	
			± 0.1	% of FS	
p <sub>pack</sub>	Pressure	Druck PTX 630	9–30	VDC	
			4–20	mA	
			0–4	MPa	
			± 0.1	% of FS	
p <sub>in,out</sub>	Pressure	Druck PTX 1400	9–28	VDC	
			4–20	mA	
			0–2.5	MPa	
			± 0.15	% of FS	
L	Level Indicator				Length correction

**Table 3-2. Sensor positions and wellbore storage (WBS) controlling factors.**

Borehole information			Sensors		Equipment affecting WBS coefficient		
ID	Test section (m)	Volume in test section (m <sup>3</sup> )	Type	Position (m fr ToC)	Position	Function	Outer diameter (mm)
KLX13A	102.50–202.50	0.454	p <sub>a</sub>	100.50	Test section	Signal cable	9.1
			p	201.60		Pump string	33
			T	201.35		Packer line	6
			p <sub>b</sub>	203.20			
			L	205.75			
KLX13A	102.50–122.50	0.091	p <sub>a</sub>	100.50	Test section	Signal cable	9.1
			p	121.60		Pump string	33
			T	121.35		Packer line	6
			p <sub>b</sub>	123.20			
			L	125.75			



## 4 Execution

### 4.1 Preparations

Following preparation work and functional checks were conducted prior to starting test activities:

- Place pallets and container, lifting rig up, installing fence on top of container, lifting tent on container.
- Clean and disinfect of Multikabel and hoses for packer and test valve. Clean the tubings with hot steam.
- Filling injection tank with water (water provided by SKB).
- Filling buffer tank with water and tracer it with Uranin; take water sample.
- Filling vessels.
- Filling the hoses for test valve and packer.
- Entering calibration constants to system and regulation unit.
- Synchronize clocks on all computers.
- Function check of shut-in tool both ends, overpressure by 900 kPa for 5 min (OK).
- Check pressure gauges against atmospheric pressure and than on test depth against column of water.
- Translate all protocols into English (where necessary).
- Filling packers with water and de-air.
- Measure and assemble test tool.


### 4.2 Length correction

By running in with the test tool, a level indicator is incorporated at the bottom of the tool. The level indicator is able to record grooves milled into the borehole wall. The depths of these grooves are given by SKB in the Activity Plan (see Table 2-2) and the measured depth is counter checked against the number/length of the tubes build in. The achieved correction value, based on linear interpolation between the reference marks, is used to adjust the location of the packers for the test sections to avoid wrong placements and minimize elongation effects of the test string.

### 4.3 Execution of field work

#### 4.3.1 Test principle

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a shut-in pressure recovery (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.



*Figure 4-1. Flow chart for test performance.*

### 4.3.2 Test procedure

A typical test cycle includes the following phases: 1) Transfer of down-hole equipment to the next section. 2) Packer inflation. 3) Pressure stabilisation. 4) Preliminary Pulse injection. 5) Constant head injection. 6) Pressure recovery. 7) Packer deflation.

The preliminary pulse injection (Step 4) derives the first estimations of the formation transmissivity. It is conducted by applying a pressure difference of approx. 200 kPa to the static formation pressure. If the pulse recovery indicates a very low transmissivity (flow probably below 1 mL/min) the pulse recovery is prolonged and no constant head injection test is performed. The decision to continue the pulse or to conduct an injection tests is based on the pressure response of the pulse recovery. A pressure recovery less than 50% during the first ten minutes of the pulse indicates a low transmissivity. In such a case no injection test will be conducted.

The pressure static recovery (PSR) after packer inflation and before the pulse gives a direct measure of the magnitude of the packer compliance. A steep PSR indicates extremely low test section transmissivity. In such a case the packer compliance would influence the subsequent pulse test too much and introduce very large uncertainties. Therefore tests with this behaviour would be stopped after PSR phase.

If the preliminary pulse injection test indicates a formation transmissivity with a flow above 1 mL/min a constant head injection test (Step 5 and 6) is carried out. It is applied with a constant injection pressure of approx. 200 kPa (20 m water column) above the static formation pressure in the test section. Before start of the injection tests, approximately stable pressure conditions prevailed in the test section. After the injection period, the pressure recovery in the section is measured. In cases, where small flow rates were expected, the automatic regulation unit was switched off and the test was performed manually (determined by the preliminary pulse injection). In those cases, the constant difference pressure was usually unequal to 200 kPa.

In cases when the derived transmissivity of a test section influences the subsequent test program the constant head injection was conducted even if the preliminary pulse indicates a very tight section (e.g. flow below 1 mL/min). The injection phase is then performed to verify the results of the pulse and a flow below 1 mL/min.

The duration for each phase is presented in Table 4-1.

## 4.4 Data handling/post processing

The data handling followed several stages. The data acquisition software (Orchestrator) produced an ASCII raw data file (\*.ht2) which contains the data in voltage and milliampere format plus calibration coefficients. The \*.ht2 files were processed to \*.dat files using the SKB program called IPPlot. These files contain the time, pressure, flow rate and temperature data. The \*.dat files were synthesised in Excel to a \*.xls file for plotting purposes. Finally, the test data to be delivered to SKB were exported from Excel in \*.csv format. These files were also used for the subsequent analysis (field and final) of the injection phase (CHi). The synthesised data of the recovery phase (CHir) was used for the field analysis and to receive preliminary results for consistency reviews.

**Table 4-1. Durations for packer inflation, pressure stabilisation, injection and recovery phase and packer deflation.**

Step	Phase	Time
1	Position test tool to new test section (correct position using the borehole markers)	Approx. 30 min.
2	Inflate packers with appr. 1,900 kPa	25 min.
3	Close test valve	10 min.
	Check tubing integrity with appr. 800 kPa	5 min.
	De-air system	2 min.
4	Pretest, pulse injection (duration depends on the formation transmissivity)	...
5*	Set automatic flow control parameters or setting for manual test	5 min.
	Start injection	20 to 45 min.
6*	Close test valve, start recovery	20 min. or more
	Open test valve	10 min.
7	Deflate packers	25 min.
	Move to next test depth	...

\* Step 5 and 6 conducted if the preliminary pulse indicates a formation transmissivity with a sufficient flow

## 4.5 Analyses and interpretations

### 4.5.1 Analysis software

The tests were analysed using a type curve matching method. The analysis was performed using Golder's test analysis program FlowDim. FlowDim is an interactive analysis environment allowing the user to interpret constant pressure, constant rate and slug/pulse tests in source as well as observation boreholes. The program allows the calculation of type-curves for homogeneous, dual porosity and composite flow models in variable flow geometries from linear to spherical.

### 4.5.2 Analysis approach

Constant pressure tests are analysed using a rate inverse approach. The method initially known as the /Jacob and Lohman 1952/ method was further improved for the use of type curve derivatives and for different flow models.

Constant pressure recovery tests are analysed using the method described by /Gringarten 1986, Bourdet et al. 1989/ by using type curve derivatives calculated for different flow models.

Pulse tests are analysed by using the pressure deconvolution method described by /Peres et al. 1989/ with improvements introduced by /Chakabarty and Enachescu 1997/.

The response in the bottom zone during the injection in test section 562.50–582.50 m was analysed using cylindrical source type curves calculated for different flow models as identified from the log-log derivative of the pressure response. This type curves are based on /Theis 1935/.

### 4.5.3 Analysis methodology

Each of the relevant test phases is subsequently analyzed using the following steps:

- **Injection Tests**

- Identification of the flow model by evaluation of the derivative on the log-log diagnostic plot. Initial estimates of the model parameters are obtained by conventional straight-line analysis.
- Superposition type curve matching in log-log coordinates. A non-linear regression algorithm is used to provide optimized model parameters in the latter stages.
- Non-linear regression in semi-log coordinates (superposition HORNER plot; /Horner 1951/. In this stage of the analysis, the static formation pressure is selected for regression.

The test analysis methodology is best explained in /Horne 1990/.

- **Pre-test for the Injection Tests**

The test cycle always starts with a pulse injection phase with the aim of deriving a first estimation of the formation transmissivity. In cases when the pulse recovery is slow (indicating low transmissivity) the pulse phase is extended and analysed as the main phase of the test.

The transmissivity derived from a pulse test is strongly influenced by the wellbore storage coefficient used as an input in the analysis. The wellbore storage coefficient is calculated as  $C = dV/dP$  where  $dV$  is the volume difference injected during the brief flow period of the pulse and  $dP$  is the initial pressure difference of the pulse.  $dV$  is directly measured either by using the flowmeter readings or water level measurements in the injection vessel.

It should be noted though that there is large uncertainty connected with the determination of the wellbore storage coefficient (probably one order of magnitude), which will implicitly translate into uncertainty in the derived transmissivity. Figure 4-2 below show an example of a typical pressure versus time evolution for such a tight section.

- Flow model identification and type curve analysis in the deconvolution Peres Plot /Peres et al. 1989, Chakrabarty and Enachescu 1997/. A non-linear regression algorithm is used to provide optimized model parameters in the later stages. An example of type curves is presented in Figure 4-3.




Figure 4-2. Typical pressure versus time plot of a Pulse injection test.




Figure 4-3. Deconvolution type curve set for pulse test analysis.

#### • Response Analysis

The test phases are subsequently analyzed using the following steps:

- Identification of the flow model by evaluation of the derivative on the log-log diagnostic plot. Initial estimates of the model parameters are obtained by conventional straight-line analysis.
- Superposition type curve matching in log-log coordinates. The type curves are based on /This 1935/ calculated for a cylindrical source (i.e. finite wellbore radius).

The distance used for the analysis is the shortest way between the source and the observation hole and no pathway tortuosity was considered. This assumption influences the storativity derived from the transient analysis.



#### 4.5.4 Correlation between storativity and skin factor

For the analysis of the conducted hydraulic tests below 100 m depth a storativity of  $1 \cdot 10^{-6}$  is assumed (SKB MD 320.004e). Based on this assumption the skin will be calculated. In the following the correlation between storativity and skin for the relevant test phases will be explained in greater detail.

- **Injection phase (CHi) / Pulse tests (Pi)**

Due to the fact that the early time data of the CHi and Pi phases, respectively, is not available or too noisy (attributed to the automatic regulation system) the storativity and the skin factor become correlated. Consequently they cannot be solved independently any more. In this case as a result of the analysis one determines the correlation group  $e^{2\xi}/S$ . This means that in such cases the skin factor can only be calculated when assuming the storativity as known.

- **Recovery phase (CHir)**

The wellbore storage coefficient (C) is determined by matching the early time data with the corresponding type curve. The derived C-value is introduced in the equation of the type curve parameter:

$$(C_D e^{2\xi})_M = \frac{C \rho g}{2\pi r_w^2 S} e^{2\xi}$$

The equation above has two unknowns, the storativity (S) and the skin factor ( $\xi$ ) which expresses the fact that for the case of constant rate and pressure recovery tests the storativity and the skin factor are 100% correlated. Therefore, the equation can only be either solved for skin by assuming that the storativity is known or solved for storativity by assuming the skin as known.

#### 4.5.5 Determination of the ri-index and calculation of the radius of influence (ri)

The analysis provides also the radius of influence and the ri-index, which describes the late time behaviour of the derivative.

##### **RI-Index**

The determination of the ri-Index is based on the shape of the derivative plotted in log-log coordinates and describes the behaviour of the derivative after the time  $t_2$ , representing the end of the near wellbore response. The ri-index also describes the flow regime at the end of the test. Following ri-indices can be assigned:

- ri-index = 0: The middle and late time derivative shows a horizontal stabilization. This pressure response indicates that the size of the hydraulic feature is greater than the radius of influence. The calculated radius of influence is based on the entire test time  $t_p$ .
- ri-index = 1: The derivative shows an upward trend at late times, indicating a decrease of transmissivity or a barrier boundary at some distance from the borehole. The size of the hydraulic feature near the borehole is estimated as the radius of influence based on  $t_2$ .
- ri-index = -1: The derivative shows a downward trend at late times, indicating an increase of transmissivity or a constant head boundary at some distance from the borehole. The size of the hydraulic feature near the borehole is estimated as the radius of influence based on  $t_2$ .

Figure 4-4 presents the relationship between the shape of derivative and the ri-index.

If no radial flow stabilization can be observed the ri-index is based on the flow regime at the end of the test: i.e. ri-index = 1 for tests with a derivative showing an upward trend at the end and a ri-index = -1 for tests with a derivative showing a downward trend. In such cases the calculated radius of influence is based on the entire test time  $t_p$ .

The assignment of the ri-index is based on /Rhen 2005/.




Figure 4-4. Schematic plot of the assignments for the  $ri$ -indices.

#### Calculation of the radius of influence

The radius of influence ( $ri$ ) is calculated as follows:

$$ri = 1.89 \times \sqrt{\frac{T_T}{S_T}} \times t_2 \quad [\text{m}]$$

$T_T$  recommended inner zone transmissivity [ $\text{m}^2/\text{s}$ ].

$t_2$  time when hydraulic formation properties changes (see previous chapter) [s].

$S_T$  for the calculation of the  $ri$  the storage coefficient ( $S$ ) is estimated from the transmissivity /Rhen et al. 2006/:

$$S_T = 0.0007 \times T_T^{0.5} \quad [-]$$

#### 4.5.6 Steady state analysis

In addition to the type curve analysis, an interpretation based on the assumption of stationary conditions was performed as described by /Moye 1967/.

#### 4.5.7 Flow models used for analysis

The flow models used in analysis were derived from the shape of the pressure derivative calculated with respect to log time and plotted in log-log coordinates.

In several cases the pressure derivative suggests a change of transmissivity with the distance from the borehole. In such cases a composite flow model was used in the analysis.

If there were different flow models matching the data in comparable quality, the simplest model was preferred.

The flow dimension displayed by the test can be diagnosed from the slope of the pressure derivative. A slope of 0.5 indicates linear flow, a slope of 0 (horizontal derivative) indicates radial flow and a slope of  $-0.5$  indicates spherical flow. The flow dimension diagnosis was

commented for each of the tests. At tests where a flow regime could not clearly identified from the test data, we assume in general a radial flow regime as the most simple flow model available. The value of  $p^*$  was then calculated according to this assumption.

In cases when the infinite acting radial flow (IARF) phase was not supported by the data the derivative was extrapolated using the most conservative assumption, which is that the derivative would stabilise short time after test end. In such cases the additional uncertainty was accounted for in the estimation of the transmissivity confidence ranges.

#### 4.5.8 Calculation of the static formation pressure and equivalent freshwater head

The static formation pressure ( $p^*$ ) measured at transducer depth, was derived from the pressure recovery (CHir) following the constant pressure injection phase by using:

- (1) straight line extrapolation in cases infinite acting radial flow (IARF) occurred.
- (2) type curve extrapolation in cases infinite acting radial flow (IARF) is unclear or was not reached.

The equivalent freshwater head (expressed in meters above sea level) was calculated from the extrapolated static formation pressure ( $p^*$ ), corrected for atmospheric pressure measured by the surface gauge and corrected for the vertical depth considering the inclination of the drill hole, by assuming a water density of 1,000 kg/m<sup>3</sup> (freshwater). The equivalent freshwater head is the static water level an individual test interval would show if isolated and connected to the surface by tubing full of freshwater. Figure 4-4 shows the methodology schematically.

The freshwater head in meters above sea level is calculated as following:

$$head = \frac{(p^* - p_{atm})}{\rho \times g}$$

which is the  $p^*$  value expressed in a water column of freshwater.


With consideration of the elevation of the reference point (RP) and the gauge depth (Gd), the freshwater head  $h_{iwf}$  is:

$$h_{iwf} = RP_{elev} - Gd + \frac{(p^* - p_{atm})}{\rho \times g}$$

#### 4.5.9 Derivation of the recommended transmissivity and the confidence range

In most of the cases more than one analysis was conducted on a specific test. Typically both test phases were analysed (CHi and CHir) and in some cases the CHi or the CHir phase was analysed using two different flow models. The parameter sets (i.e. transmissivities) derived from the individual analyses of a specific test usually differ. In the case when the differences are small (which is typically the case) the recommended transmissivity value is chosen from the test phase that shows the best data and derivative quality.

In cases when the difference in results of the individual analyses was large (more than half order of magnitude) the test phases were compared and the phase showing the best derivative quality was selected.



**Figure 4-5.** Schematic methodologies for calculation of the freshwater head.

The confidence range of the transmissivity was derived using expert judgement. Factors considered were the range of transmissivities derived from the individual analyses of the test as well as additional sources of uncertainty such as noise in the flow rate measurement, numeric effects in the calculation of the derivative or possible errors in the measurement of the wellbore storage coefficient. No statistical calculations were performed to derive the confidence range of transmissivity.

In cases when changing transmissivity with distance from the borehole (composite model) was diagnosed, the transmissivity of the zone, which was showing the better derivative quality, was recommended.

In cases when the infinite acting radial flow (IARF) phase was not supported by the data the additional uncertainty was accounted for in the estimation of the transmissivity confidence ranges.

## 4.6 Nonconformities

No nonconformities occurred during the performance of the hydraulics tests in KLX13A.

## 5 Results

In the following, results of all tests are presented and analysed. Chapters 5.1 and 5.2 present the 100 m and 20 m tests, respectively. The results are given as general comments to test performance, the identified flow regimes and calculated parameters and finally the parameters which are considered as most representative are chosen and justification is given. All results are also summarised in Table 6-1 and 6-2 of the Summary chapter. In addition, the results are presented in appendices 3 and 5.

The results are stored in the primary data base (SICADA). The SICADA data base contains data that will be used for further interpretation (modelling). The data are traceable in SICADA by the Activity plan number (AP PS 400-07-006; SKB controlling document).

### 5.1 100 m single-hole injection tests

In the following, the 100 m section tests conducted in borehole KLX13A are presented and analysed.

#### 5.1.1 Section 102.50–205.50 m, test no. 1, injection

##### *Comments to test*

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium to high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 199 kPa. No hydraulic connection between the test interval and adjacent sections was observed. The injection rate decreased from 6.5 L/min at start of the CHi phase to 3.9 L/min at the end, indicating a medium to high interval transmissivity (consistent with the pulse recovery). The CHi data are noisy during the entire phase. However, both phases are adequate for quantitative analysis.

##### *Flow regime and calculated parameters*

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase is noisy, but it shows a flat derivative at middle and late times. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilization at middle times with a downward slope at late times. This is indicative for the transition to a zone of higher transmissivity at some distance to the borehole. A two shell composite model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-1.

##### *Selected representative parameters*

The recommended transmissivity of  $2.6 \cdot 10^{-6} \text{ m}^2/\text{s}$  was derived from the analysis of the CHir phase (inner zone), which shows the best data and derivative quality and a clear horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-6} \text{ m}^2/\text{s}$  to  $8.0 \cdot 10^{-6} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 1,978.7 kPa.

The analyses of the CHi and CHir phases show some inconsistency. As the CHi phase was analysed using a homogeneous model, a two shell composite model was chosen for the CHir phase. Probably this is related to the poor data quality of the CHi phase. No further analysis is recommended.

### **5.1.2 Section 202.50–302.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response and the recovery of the pulse test indicated a medium to high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted manually using a pressure difference of 200 kPa. No hydraulic connection to the adjacent zones was observed. The injection rate decreased from 3.5 L/min at start of the CHi phase to 2.2 L/min at the end, indicating a medium to high interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test, the CHi phase shows a flat derivative at middle to late times indicating radial flow. A infinite acting homogeneous flow model was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal part at middle times followed by an upward trend and a horizontal stabilisation at late times afterwards. A two shell composite model with wellbore storage and skin was used for the analysis of the CHir phase. The analysis is presented in Appendix 2-2.

#### ***Selected representative parameters***

The recommended transmissivity of  $1.5 \cdot 10^{-6} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which shows the clearest horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be  $8.0 \cdot 10^{-7} \text{ m}^2/\text{s}$  to  $6.0 \cdot 10^{-6} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,941.2 kPa.

The analyses of the CHi and CHir phases show consistency. No further analysis is recommended.

### **5.1.3 Section 302.50–402.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. Due to the very high transmissivity of the formation no pressure response was observed during the pulse injection. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted.

The CHi phase was conducted using a pressure difference of 11 kPa. The bottom zone increased by approx. 5 kPa, indicating a connection to the test interval. The injection rate decreased from 44 L/min at start of the CHi phase to 15 L/min at the end, indicating a relatively high interval transmissivity. Because of the high flow and the increasing pressure in the regulation system the recorded flow rate is not suitable for analysis at early and middle times. Therefore only the

late time data of the CHi phase was analysed. Due to the small pressure difference during the perturbation phase the CHir phase was not analysed. Because of the mentioned problems the result of the analysis should be regarded as order of magnitude only.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase was matched using a two shell composite radial flow model with decreasing transmissivity at some distance from the borehole. The analysis is presented in Appendix 2-3.

#### ***Selected representative parameters***

The recommended transmissivity of  $4.1 \cdot 10^{-4}$  m<sup>2</sup>/s was derived from the analysis of the CHi phase (inner zone). The confidence range for the interval transmissivity is estimated to be  $7.0 \cdot 10^{-5}$  m<sup>2</sup>/s to  $8.0 \cdot 10^{-4}$  m<sup>2</sup>/s (this range encompasses the outer zone transmissivity). The flow dimension during the test is assumed to be 2. The static pressure could not be analysed based on solely the CHi phase.

No further analysis is recommended.

### **5.1.4 Section 395.50–495.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 42 kPa. The pressure in the section below increased by 10 kPa during injection and decreased by 6 kPa during recovery. The pressure in the section above increased by 3 kPa during injection and decreased by 1 kPa during recovery. The injection rate decreased from 29.2 L/min at start of the CHi phase to 24.3 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). The regulation unit did not work very well during the first part of the CHi phase. However, the late time data of the CHi phase and the CHir phase are adequate for quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a flat derivative at middle and late times, indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilization at middle and late times, indicating radial flow. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-4.

#### ***Selected representative parameters***

The recommended transmissivity of  $9.2 \cdot 10^{-5}$  m<sup>2</sup>/s was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. Due to the hydraulic connection to the bottom zone, the derived transmissivity should be regarded to be at the upper limit of the confidence range. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-5}$  m<sup>2</sup>/s to  $2.0 \cdot 10^{-4}$  m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow).



The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,837.2 kPa.

The analyses of the CHi and CHir phases show some inconsistency due to the fast recovery. No further analysis is recommended.

### **5.1.5 Section 482.50–582.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 198 kPa. The pressure in the section below increased by 92 kPa during injection and decreased by 86 kPa during recovery. No hydraulic connection was observed between the section above and the test section. The injection rate decreased from 14.2 L/min at start of the CHi phase to 6.3 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a flat derivative at middle times, indicating radial flow. At late times the derivative shows an upward trend which is characteristic for a change in flow dimension or in transmissivity. A radial two shell composite flow model was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilization at middle and late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-4.

#### ***Selected representative parameters***

The recommended transmissivity of  $5.7 \cdot 10^{-6} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase (inner zone), which shows a good derivative stabilisation. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-6} \text{ m}^2/\text{s}$  to  $7.0 \cdot 10^{-6} \text{ m}^2/\text{s}$  due to the hydraulic connection. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,684.4 kPa.

The analyses of the CHi and CHir phases show some inconsistency regarding the derived transmissivities. This can be attributed to the hydraulic communication to the bottom zone. The impact of this communication is related to the pressure difference between the zones. No further analysis is recommended.



## 5.2 20 m single-hole injection tests

In the following, the 20 m section tests conducted in borehole KLX13A are presented and analysed.

### 5.2.1 Section 102.50–122.50 m, test no. 1, injection

#### **Comments to test**

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response and the recovery of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted manually using a pressure difference of 198 kPa. No hydraulic connection to the adjacent zones was observed. The injection rate decreased from 5.4 L/min at start of the CHi phase to 3.4 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). The regulation unit could not keep the pressure very stable. The flow rate and the pressure data were quite noisy during the CHi phase. However, both phases show no problems and are adequate for quantitative analysis.

#### **Flow regime and calculated parameters**

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test, the CHi phase shows a noisy but flat derivative at early times followed by an upward trend at middle times and further with a horizontal stabilisation at late times. A two shell composite flow model was chosen for analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilisation at middle times followed by an upward trend at late times indicating a two shell composite model with wellbore storage and skin was used for the analysis of the CHir phase. The analysis is presented in Appendix 2-6.

#### **Selected representative parameters**

The recommended transmissivity of  $2.3 \cdot 10^{-6} \text{ m}^2/\text{s}$  was derived from the analysis of the CHir phase (inner zone), which shows the best horizontal stabilisation of the derivative and best data and derivative quality. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-6} \text{ m}^2/\text{s}$  to  $7.0 \cdot 10^{-6} \text{ m}^2/\text{s}$ . The analysis was conducted using a flow dimension of 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 1,198.9 kPa.

The analyses of the CHi and CHir phases show a good consistency. No further analysis is recommended.

### 5.2.2 Section 122.50–142.50 m, test no. 1, injection

#### **Comments to test**

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a low formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

Prior the pulse test the pressure in the test section rose by 11 kPa within 14 min. The CHi phase was conducted using a pressure difference of 196 kPa. Due to the expected small injection rate, the CHi phase was conducted without the automatic regulation, directly from the injection vessel with  $\text{N}_2$  backpressure. The injection rate decreased from 6.8 mL/min at start of the CHi

phase to 1.0 mL/min at the end, indicating a low interval transmissivity (consistent with the pulse recovery). The CHI data are quite noisy due to the low transmissivity and the low flow rate. Both phases show no problems and are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHI phase shows a noisy derivative with an upwards trend and a horizontal stabilisation at late times, indicating the transition from wellbore storage and skin dominated flow to formation flow. The derivative of the CHir phase looks similar with an upward trend and the transition to formation flow. Both phases were analysed using an infinite acting radial flow model. The analysis is presented in Appendix 2-7.

### ***Selected representative parameters***

The recommended transmissivity of  $1.0 \cdot 10^{-10}$  m<sup>2</sup>/s was derived from the analysis of the CHir phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be  $7.0 \cdot 10^{-11}$  m<sup>2</sup>/s to  $4.0 \cdot 10^{-10}$  m<sup>2</sup>/s. The analysis was conducted using a flow dimension of 2 (radial flow). Due to the low transmissivity no fresh water head was calculated.

The analyses of the CHI and CHir phases show good consistency. No further analysis is recommended.

## **5.2.3 Section 142.50–162.50 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The very slow recovery of the pulse test indicated a very low formation transmissivity. Based on this result no constant pressure injection test was performed. Instead, the recovery of the pulse injection test was prolonged and analysed.

Prior the pulse injection the pressure in the test section rose by 19 kPa within 17 min. During the brief injection phase of the pulse injection a total volume of about 5.6 mL was injected (derived from the flow meter readings). This injected volume produced a pressure increase of 236 kPa. Using a dV/dP approach, the wellbore storage coefficient relevant for the subsequent pressure recovery can be calculated to  $2.4 \cdot 10^{-11}$  m<sup>3</sup>/Pa. It should be noted though that there is uncertainty connected with the determination of the wellbore storage coefficient, which will implicitly translate into uncertainty in the derived transmissivity.

### ***Flow regime and calculated parameters***

For the interpretation a flow dimension of 2 (radial flow) was assumed. In case of the present test the deconvolved PI pressure derivative shows an upward trend with a horizontal stabilisation at late times. The PI phase was analysed using a homogenous model with radial flow, wellbore storage and skin. The analysis is presented in Appendix 2-8.

### ***Selected representative parameters***

The recommended transmissivity of  $2.9 \cdot 10^{-11}$  m<sup>2</sup>/s was derived from the analysis of the Pi phase. The confidence range for the interval transmissivity is estimated to be  $9.0 \cdot 10^{-12}$  to  $7.0 \cdot 10^{-11}$  m<sup>2</sup>/s. The analysis was conducted using a flow dimension of 2. The static pressure could not be extrapolated due to the very low transmissivity.

No further analysis is recommended.

#### **5.2.4 Section 162.50–182.50 m, test no. 1, injection**

##### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 199 kPa. No hydraulic connection between the test interval and adjacent sections was observed during the CHi and CHir phases. The injection rate decreased from 0.38 L/min at start of the CHi phase to 0.13 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). At the start of the CHi phase, the automatic flow regulation needed some time to stabilise the injection pressure, leading to a poor data quality at the early time data. However, both phases are adequate for quantitative analysis.

##### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a flat derivative at middle and late times. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a downward slope at middle times followed by a horizontal stabilisation at late times. This is indicative for a transition to a zone of higher transmissivity at some distance to the borehole. A two shell composite model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-9.

##### ***Selected representative parameters***

The recommended transmissivity of  $1.9 \cdot 10^{-7} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which shows the clearest horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be  $9.0 \cdot 10^{-8} \text{ m}^2/\text{s}$  to  $6.0 \cdot 10^{-7} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 1,782.2 kPa.

The analyses of the CHi and CHir phases show some minor inconsistency. No further analysis is recommended.

#### **5.2.5 Section 182.50–202.50 m, test no. 1, injection**

##### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The first CHi phase was stopped due to the long time the regulation unit needed to adjust the pressure difference. The second CHi phase was conducted using a pressure difference of 199 kPa. No hydraulic connection between the test interval and adjacent sections was observed during the CHi and CHir phases. The injection rate decreased from 0.47 L/min at start of the CHi phase to 0.31 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). At the start of the CHi phase, the automatic flow regulation needed some time to stabilise the injection pressure, leading to a poor data quality at the early time data. However, both phases are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy but flat derivative at middle and late times. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a flat derivative at middle times, followed by a downward slope at late times. This behaviour is characteristic for a transition to a zone of higher transmissivity. A two shell composite model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-10.

### ***Selected representative parameters***

The recommended transmissivity of  $2.5 \cdot 10^{-7} \text{ m}^2/\text{s}$  was derived from the analysis of the CHir phase (inner zone), which shows the best data and derivative quality. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-7} \text{ m}^2/\text{s}$  to  $8.0 \cdot 10^{-7} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 1,965.1 kPa.

The analyses of the CHi and CHir phases show good consistency. No further analysis is recommended.

## **5.2.6 Section 202.50–222.50 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 215 kPa. No hydraulic connection to the test section was observed. The injection rate decreased from 0.87 mL/min at start of the CHi phase to 0.48 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a horizontal stabilisation at middle and late times, indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a downward slope with a horizontal stabilization at late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-11.

### ***Selected representative parameters***

The recommended transmissivity of  $6.4 \cdot 10^{-7} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be  $4.0 \cdot 10^{-7} \text{ m}^2/\text{s}$  to  $3.0 \cdot 10^{-6} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,166.3 kPa.

The analyses of the CHi and CHir phases show inconsistencies. Due to the fast recovery the transmissivity of the CHi phase is preferred. No further analysis is recommended.

### **5.2.7 Section 222.50–242.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response and the recovery of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 200 kPa. No hydraulic connection to the adjacent zones was observed. The injection rate decreased from 1.86 L/min at start of the CHi phase to 0.96 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test, the CHi phase shows a flat derivative at early times followed by an upward trend at middle times and further with a horizontal stabilisation at late times. A two shell composite flow model was chosen for analysis of the CHi phase. The derivative of the CHir phase shows after an early flat part an upward trend at middle times followed by a horizontal stabilisation at late times afterwards indicating a decrease in transmissivity at some distance from the borehole. A two shell composite model with wellbore storage and skin was used for the analysis of the CHir phase. The analysis is presented in Appendix 2-12.

#### ***Selected representative parameters***

The recommended transmissivity of  $5.7 \cdot 10^{-7} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase (outer zone), which shows the best horizontal stabilisation of the derivative and best data and derivative quality. The confidence range for the interval transmissivity is estimated to be  $2.0 \cdot 10^{-7} \text{ m}^2/\text{s}$  to  $1.0 \cdot 10^{-6} \text{ m}^2/\text{s}$ . The analysis displayed during the test a flow dimension of 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,360.1 kPa.

The analyses of the CHi and CHir phases show a good consistency. No further analysis is recommended.

### **5.2.8 Section 242.50–262.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a low formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 196 kPa. No hydraulic connection to the test section was observed. The regulation unit needed some time to reach stable conditions though the data quality is poor for early and middle time data. The injection rate decreased from 47.1 mL/min at start of the CHi phase to 22.4 mL/min at the end, indicating a low interval transmissivity (consistent with the pulse recovery). The late time data of the CHi phase and the entire CHir phase show no problems and are adequate for the quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy but flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase tends to show a horizontal stabilization at late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-13.

### ***Selected representative parameters***

The recommended transmissivity of  $2.5 \cdot 10^{-8} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-8} \text{ m}^2/\text{s}$  to  $9.0 \cdot 10^{-8} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,563.2 kPa.

The analyses of the CHi and CHir phases show some minor inconsistencies, mainly caused by the noisy data of the CHi phase and the non-radial flow of the CHir phase. No further analysis is recommended.

## **5.2.9 Section 262.50–282.50 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 212 kPa. No hydraulic connection between the test interval and adjacent sections was observed during the CHi and CHir phases. The injection rate decreased from 99.8 mL/min at start of the CHi phase to 81.7 mL/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). At the start of the CHi phase, the automatic flow regulation needed some time to stabilise the injection pressure, leading to a poor data quality at the early and middle time data. However, the late time data of the CHi phase and the entire CHir phase show no problems and are adequate for the quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy but flat derivative at late times. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a flat part at middle times followed by a downward trend. The analysis indicated a change in transmissivity or flow dimension at some distance to the borehole. A two shell composite model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-14.

### ***Selected representative parameters***

The recommended transmissivity of  $1.2 \cdot 10^{-7} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which is very noisy but shows a horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be  $3.0 \cdot 10^{-8} \text{ m}^2/\text{s}$  to  $3.0 \cdot 10^{-7} \text{ m}^2/\text{s}$ . The analysis was conducted using a flow dimension of 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,743.6 kPa.



The analyses of the CHi and CHir phases show minor inconsistencies regarding the flow models. This can be addressed to the poor data quality of the CHi data. No further analysis is recommended.

#### **5.2.10 Section 282.50–302.50 m, test no. 1, injection**

##### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 199 kPa. No hydraulic connection to the test section was observed. The injection rate decreased from 1.7 L/min at start of the CHi phase to 1.1 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

##### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy but flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal part at late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-15.

##### ***Selected representative parameters***

The recommended transmissivity of  $2.0 \cdot 10^{-6}$  m<sup>2</sup>/s was derived from the analysis of the CHir phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be  $9.0 \cdot 10^{-7}$  m<sup>2</sup>/s to  $5.0 \cdot 10^{-6}$  m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,939.1 kPa.

The analyses of the CHi and CHir phases show good consistency. No further analysis is recommended.

#### **5.2.11 Section 302.50–322.50 m, test no. 1, injection**

##### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response and the very fast recovery of the pulse test indicated a moderate to high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 198 kPa. The automatic regulation system worked well. No hydraulic connection to the adjacent zones was observed. The injection rate decreased from 7.8 L/min at start of the CHi phase to 4.7 L/min at the end, indicating a moderate to high interval transmissivity (consistent with the pulse recovery). The CHi phase is adequate for qualitative analysis. The CHir phase shows very fast recovery, but is still adequate for quantitative analysis, too.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy derivative with an upward trend followed by a horizontal stabilisation at late times, indicating a decrease of transmissivity at some distance to the borehole. The early time data are not representative for the formation. A two shell composite flow model was used for the analysis of the CHi phase. The CHir phase shows a flat derivative at middle and late times. The CHir phase was analysed using a homogeneous radial flow model with wellbore storage and skin. The analysis is presented in Appendix 2-16.

### ***Selected representative parameters***

The recommended transmissivity of  $2.1 \cdot 10^{-5}$  m<sup>2</sup>/s was derived from the analysis of the CHir phase, which shows the better derivative quality. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-6}$  m<sup>2</sup>/s to  $4.0 \cdot 10^{-5}$  m<sup>2</sup>/s. The flow dimension displayed during the test is 2. The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 3,137.7 kPa.

The analyses of the CHi and CHir phases show inconsistencies due to the fast recovery. No further analysis is recommended.

## **5.2.12 Section 322.50–342.50 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response and the recovery of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted manually using a pressure difference of 200 kPa. No hydraulic connection to the adjacent zones was observed. The injection rate decreased from 130.5 mL/min at start of the CHi phase to 96.8 mL/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test, the CHi phase shows a noisy but flat derivative at early times followed by an upward trend at middle times and further with a horizontal stabilisation at late times. A two shell composite flow model was chosen for analysis of the CHi phase. The derivative of the CHir phase shows an upward trend at middle times followed by a horizontal stabilisation at late times, indicating an increase in transmissivity at some distance from the borehole. A two shell composite model with wellbore storage and skin was used for the analysis of the CHir phase. The analysis is presented in Appendix 2-17.

### ***Selected representative parameters***

The recommended transmissivity of  $1.6 \cdot 10^{-7}$  m<sup>2</sup>/s was derived from the analysis of the CHi phase (inner zone), which shows a horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be  $8.0 \cdot 10^{-8}$  m<sup>2</sup>/s to  $5.0 \cdot 10^{-7}$  m<sup>2</sup>/s. The analysis was conducted using a flow dimension of 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 3,334.2 kPa.

The analyses of the CHi and CHir phases show a good consistency. No further analysis is recommended.



### **5.2.13 Section 342.50–362.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 199 kPa. The section below showed a pressure increase by 5 kPa during injection and a pressure decrease by 3 kPa. No hydraulic connection to the section above was observed. The injection rate decreased from 24.2 L/min at start of the CHi phase to 15.1 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). The regulation unit did not work well at the beginning of the CHi phase. During the second part of this phase, the system could hold constant pressure much better. The late time data of the CHi and CHir phase are adequate for quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy derivative with a flat part at late times, indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase is noisy and shows a horizontal stabilisation at late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-18.

#### ***Selected representative parameters***

The recommended transmissivity of  $4.8 \cdot 10^{-5} \text{ m}^2/\text{s}$  was derived from the analysis of the CHir phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be  $2.0 \cdot 10^{-5} \text{ m}^2/\text{s}$  to  $7.0 \cdot 10^{-5} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 3,529.9 kPa.

The analyses of the CHi and CHir phases show good consistency. No further analysis is recommended.

### **5.2.14 Section 355.50–375.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 160 kPa. The section below showed a pressure increase by 6 kPa during injection and a pressure decrease by 3 kPa during recovery. No hydraulic connection to the section below was observed. The injection rate decreased from 21.4 L/min at start of the CHi phase to 16.8 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). The CHir phase shows a fast recovery. Both phases show no problems and are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHI phase shows a noisy but flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHI phase. The derivative of the CHir phase shows a horizontal stabilization at middle and late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-19.

### ***Selected representative parameters***

The recommended transmissivity of  $4.1 \cdot 10^{-5} \text{ m}^2/\text{s}$  was derived from the analysis of the CHI phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be  $2.0 \cdot 10^{-5} \text{ m}^2/\text{s}$  to  $8.0 \cdot 10^{-5} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 3,658.5 kPa.

The analyses of the CHI and CHir phases show good consistency. No further analysis is recommended.

## **5.2.15 Section 375.50–395.50 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response and the recovery of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHI) and a recovery phase (CHir) was conducted. Only the CHI and CHir phases were analysed quantitatively.

The CHI phase was conducted using a pressure difference of 8 kPa. The section below showed a hydraulic connection to the test section with a pressure increase of 7 kPa during injection and pressure decrease by 3 kPa during recovery. The section above showed no hydraulic connectivity. The injection rate decreased from 40.0 L/min at the start of the CHI phase to 14.2 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). Because of the high flow and the increasing pressure in the regulation system the recorded flow rate is not suitable for analysis at early and middle pressure difference during the perturbation phase. The CHir phase was not analysed. Because of the mentioned problems the result of the analysis should be regarded as order of magnitude only.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test, the CHI phase shows a noisy but flat derivative at early times followed by an upward trend at middle times and further with a horizontal stabilisation at late times. This indicates a decrease in transmissivity at some distance from the borehole. A two shell composite flow model with skin was chosen for analysis of the CHI phase. The analysis is presented in Appendix 2-20.

### ***Selected representative parameters***

The recommended transmissivity of  $4.4 \cdot 10^{-4} \text{ m}^2/\text{s}$  was derived from the analysis of the CHI phase (inner zone), which shows the best horizontal stabilisation of the derivative and best data and derivative quality. The confidence range for the interval transmissivity is estimated to be  $7.0 \cdot 10^{-5} \text{ m}^2/\text{s}$  to  $8.0 \cdot 10^{-4} \text{ m}^2/\text{s}$ . The analysis was conducted using a flow dimension of 2 (radial flow). The static pressure could not be analysed based on solely the CHI phase.

No further analysis is recommended.

### **5.2.16 Section 395.50–415.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 108 kPa. No hydraulic connection to the test section was observed. The injection rate decreased from 20.0 L/min at start of the CHi phase to 14.4 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). The CHir phase shows a very fast recovery. However, both phases show no problems and are adequate for quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilization at middle and late times. The shape of the derivative is quite sensitive to the smoothing factor. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-21.

#### ***Selected representative parameters***

The recommended transmissivity of  $4.8 \cdot 10^{-5} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be  $3.0 \cdot 10^{-5} \text{ m}^2/\text{s}$  to  $7.0 \cdot 10^{-5} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,053.1 kPa.

The analyses of the CHi and CHir phases show consistency. No further analysis is recommended.

### **5.2.17 Section 415.50–435.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 199 kPa. No hydraulic connection to the test section was observed. The injection rate decreased from 12.6 L/min at start of the CHi phase to 9.3 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). The CHir phase shows a very fast recovery. However, both phases are adequate for quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase.

The derivative of the CHir phase shows a horizontal stabilization at middle and late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-22.

### ***Selected representative parameters***

The recommended transmissivity of  $1.9 \cdot 10^{-5} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase due to the fast recovery during the CHir phase. The confidence range for the interval transmissivity is estimated to be  $9.0 \cdot 10^{-6} \text{ m}^2/\text{s}$  to  $5.0 \cdot 10^{-5} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,246.6 kPa.

The analyses of the CHi and CHir phases show good consistency. No further analysis is recommended.

## **5.2.18 Section 435.50–455.50 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 92 kPa. The section below showed a pressure increase during injection by 8 kPa and a pressure decrease during recovery by 5 kPa. The section above showed no hydraulic connection to the test section. The injection rate decreased from 21.1 L/min at start of the CHi phase to 14.6 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilization at middle and late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-23.

### ***Selected representative parameters***

The recommended transmissivity of  $5.5 \cdot 10^{-5} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase which is more reliable due to the fast recovery during the CHir phase. The confidence range for the interval transmissivity is estimated to be  $3.0 \cdot 10^{-5} \text{ m}^2/\text{s}$  to  $8.0 \cdot 10^{-5} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,442.8 kPa.

The analyses of the CHi and CHir phases show good consistency. No further analysis is recommended.

### **5.2.19 Section 455.50–475.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 120 kPa. The section below showed a pressure increase during injection by 4 kPa and a pressure decrease during recovery by 4 kPa. The section above showed no hydraulic connection to the test section. The injection rate decreased from 18.8 L/min at start of the CHi phase to 11.2 L/min at the end, indicating a high interval transmissivity (consistent with the pulse recovery). The CHir phase shows fast recovery, but is still amenable for the quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy but flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilization at middle and late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-24.

#### ***Selected representative parameters***

The recommended transmissivity of  $2.9 \cdot 10^{-5} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase due to the fast recovery during the CHir phase. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-5} \text{ m}^2/\text{s}$  to  $7.0 \cdot 10^{-5} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,638.9 kPa.

The analyses of the CHi and CHir phases show good consistency. No further analysis is recommended.

### **5.2.20 Section 475.50–495.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium to high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 198 kPa. No hydraulic connection to the adjacent sections was observed. The injection rate decreased from 7.3 L/min at start of the CHi phase to 3.6 L/min at the end, indicating a medium to high interval transmissivity (consistent with the pulse recovery). The CHir phase shows a very fast recovery. The derived values of this analysis should be regarded as order of magnitude only.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy but flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi

phase. An infinite acting radial flow model with wellbore storage and skin was used to analyse the CHir phase. Due to the fast recovery the determination of the flow model is very uncertain. The analysis is presented in Appendix 2-25.

### ***Selected representative parameters***

The recommended transmissivity of  $3.5 \cdot 10^{-6} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which shows a clear horizontal stabilisation and good data quality. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-6} \text{ m}^2/\text{s}$  to  $8.0 \cdot 10^{-6} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,833.3 kPa.

The analyses of the CHi and CHir phases show some inconsistency, mainly caused by the fast recovery of the CHir phase. No further analysis is recommended.

## **5.2.21 Section 493.00–513.00 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium to high formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 198 kPa. No hydraulic connection to the adjacent sections was observed. The injection rate decreased from 7.6 L/min at start of the CHi phase to 3.5 L/min at the end, indicating a medium to high interval transmissivity (consistent with the pulse recovery). The CHir phase shows a fast recovery and the analysis should be regarded as order of magnitude only.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilization at middle and late times, although it is very sensitive to the smoothing factor of the analysis. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-26.

### ***Selected representative parameters***

The recommended transmissivity of  $3.5 \cdot 10^{-6} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which is of good quality and shows a clear horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-6} \text{ m}^2/\text{s}$  to  $6.0 \cdot 10^{-6} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,005.4 kPa.

The analyses of the CHi and CHir phases show some inconsistencies, mainly caused by the fast recovery. No further analysis is recommended.



## **5.2.22 Section 507.00–527.00 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 198 kPa. The section below showed a pressure increase by 8 kPa during injection and a pressure decrease by 6 kPa. No hydraulic connection to the section above was observed. The injection rate decreased from 1.4 L/min at start of the CHi phase to 0.9 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a noisy but flat derivative indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir phase shows a horizontal stabilization at middle and late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-27.

### ***Selected representative parameters***

The recommended transmissivity of  $9.1 \cdot 10^{-7} \text{ m}^2/\text{s}$  was derived from the analysis of the CHi phase, which shows the better derivative quality. The confidence range for the interval transmissivity is estimated to be  $7.0 \cdot 10^{-7} \text{ m}^2/\text{s}$  to  $4.0 \cdot 10^{-6} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,140.4 kPa.

The analyses of the CHi and CHir phases show some minor inconsistencies, mainly caused by the relatively fast recovery of the CHi phase and the data quality of both phases. No further analysis is recommended.

## **5.2.23 Section 527.00–547.00 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 199 kPa. The section below showed a pressure increase by 9 kPa during injection and a pressure decrease by 7 kPa. No hydraulic connection to the section above was observed. The injection rate decreased from 1.8 L/min at start of the CHi phase to 1.0 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHI phase shows a little noisy but flat derivative at middle and late times, indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHI phase. The derivative of the CHir phase shows is a little noisy, either. However it shows a horizontal stabilization at middle and late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-28.

### ***Selected representative parameters***

The recommended transmissivity of  $9.5 \cdot 10^{-7}$  m<sup>2</sup>/s was derived from the analysis of the CHI phase, which shows the better derivative and horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be  $7.0 \cdot 10^{-7}$  m<sup>2</sup>/s to  $5.0 \cdot 10^{-6}$  m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,335.5 kPa.

The analyses of the CHI and CHir phases show sufficient consistency. No further analysis is recommended.

## **5.2.24 Section 547.00–567.00 m, test no. 1, injection**

### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHI) and a recovery phase (CHir) was conducted. Only the CHI and CHir phases were analysed quantitatively.

The CHI phase was conducted using a pressure difference of 197 kPa. No hydraulic connection to the adjacent sections was observed. The injection rate decreased from 1.58 L/min at start of the CHI phase to 0.98 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). Both phases show no problems and are adequate for quantitative analysis.

### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHI phase shows a flat derivative at middle and late times indicating radial flow. A homogeneous model with radial flow was chosen for the analysis of the CHI phase. The derivative of the CHir phase is a little noisy and shows a horizontal stabilization at middle and late times. A homogeneous model with radial flow, wellbore storage and skin was chosen for the analysis. The analysis is presented in Appendix 2-29.

### ***Selected representative parameters***

The recommended transmissivity of  $1.1 \cdot 10^{-6}$  m<sup>2</sup>/s was derived from the analysis of the CHI phase, which shows the better derivative quality and horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be  $8.0 \cdot 10^{-7}$  m<sup>2</sup>/s to  $5.0 \cdot 10^{-6}$  m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,530.2 kPa.

The analyses of the CHI and CHir phases show consistency. No further analysis is recommended.



### **5.2.25 Section 562.50–582.50 m, test no. 1, injection**

#### ***Comments to test***

The test design consisted of a preliminary pulse injection test conducted with the goal of deriving a first estimate of the formation transmissivity. The pressure response of the pulse test indicated a medium formation transmissivity. Based on this result a sequence consisting of a constant pressure injection phase (CHi) and a recovery phase (CHir) was conducted. Only the CHi and CHir phases were analysed quantitatively.

The CHi phase was conducted using a pressure difference of 200 kPa. The section below showed a hydraulic connection with a pressure increase/decrease of 16 kPa during the pulse injection. During the CHi phase the pressure below increased by 86 kPa. This response was analysed as well (see next chapter; Section 583.50–595.85). The section above showed no hydraulic connection. The injection rate decreased from 0.465 L/min at start of the CHi phase to 0.087 L/min at the end, indicating a medium interval transmissivity (consistent with the pulse recovery). At the start of the CHi phase, the automatic flow regulation needed some time to stabilise the injection pressure, leading to a poor data quality at the early and middle time data. However, both phases are adequate for quantitative analysis.

#### ***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test the CHi phase shows a flat derivative at middle and late times. A homogeneous model with radial flow was chosen for the analysis of the CHi phase. The derivative of the CHir shows a horizontal part at middle times, followed by a downward slope and a beginning horizontal stabilisation at late times, indicating a change in transmissivity or in flow dimension. A two shell composite model with radial flow, wellbore storage and skin was chosen for the analysis of the CHir phase. The analysis is presented in Appendix 2-30.

#### ***Selected representative parameters***

The recommended transmissivity of  $3.7 \cdot 10^{-8} \text{ m}^2/\text{s}$  was derived from the analysis of the CHir phase (inner zone), which shows the best data and derivative quality. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-8} \text{ m}^2/\text{s}$  to  $5.0 \cdot 10^{-8} \text{ m}^2/\text{s}$ . The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,677.5 kPa.

The analyses of the CHi and CHir phases show good consistency. No further analysis is recommended.

### **5.2.26 Section 583.50–595.85 m (bottom zone), test no. 1**

#### ***Comments to test***

The injection test in Section 562.50–582.50 m showed a clear connection to the bottom zone (583.50–595.85 m). This response was used for an analysis to describe the hydraulic properties of the lowest part of the borehole. During the Chi phase in section 562.50–582.50 m the pressure increased by 86 kPa in the bottom section and a decrease during the CHir phase. The observed responses (CHi and CHir) are adequate for quantitative analysis. For the distance between both sections a distance of 5 m was assumed. This value corresponds with the distance between two fracture zones, which can be seen on the borehole pictures.

***Flow regime and calculated parameters***

The flow dimension is interpreted from the slope of the semi-log derivative plotted in log-log coordinates. In case of the present test both phases were analysed using a two shell composite flow model. The analysis is presented in Appendix 2-31.

***Selected representative parameters***

The recommended transmissivity of  $6.4 \cdot 10^{-8} \text{ m}^2/\text{s}$  was derived from the analysis of the CHir phase (inner zone), which shows the best data and derivative quality. The confidence range for the interval transmissivity is estimated to be  $1.0 \cdot 10^{-8} \text{ m}^2/\text{s}$  to  $1.0 \cdot 10^{-7} \text{ m}^2/\text{s}$ . The analysis was conducted using a flow dimension of 2 (radial flow).

The analyses of both phases show a good consistency. No further analysis is recommended.

## **6 Summary of results**

This chapter summarizes the basic test parameters and analysis results. In addition, the correlation between steady state and transient transmissivities as well as between the matched and the theoretical wellbore storage (WBS) coefficient are presented and discussed.

## 6.1 General test data and results

Table 6-1. General test data from hydraulic tests in KLX13A (for nomenclature see appendix 4 and below).

Borehole sec up [m bToC]	Borehole sec low [m bToC]	Date and Time for test start YYMMDD hh:mm	Date and Time for test stop YYMMDD hh:mm	Q <sub>p</sub> (m <sup>3</sup> /s)	Q <sub>m</sub> (m <sup>3</sup> /s)	t <sub>p</sub> (s)	t <sub>f</sub> (s)	p <sub>0</sub> (kPa)	p <sub>i</sub> (kPa)	p <sub>p</sub> (kPa)	p <sub>f</sub> (kPa)	te <sub>w</sub> (°C)	Test phases measured, Analysed test phases marked bold
102.50	202.50	070215 09:48	070215 14:06	6.50E-05	7.00E-05	1,800	1,800	1,971	1,978	2,176	1,981	9.1	CHi / CHir
202.50	302.50	070215 15:34	070215 17:30	3.67E-05	4.05E-05	1,800	1,800	2,946	2,947	3,147	2,954	10.5	CHi / CHir
302.50	402.50	070216 07:58	070216 10:27	2.63E-04	4.65E-04	1,800	1,800	3,922	3,923	3,934	3,927	12.4	CHi / CHir
395.50	495.50	070216 11:52	070216 13:43	4.05E-04	4.52E-04	1,800	1,800	4,834	4,834	4,875	4,838	14.4	CHi / CHir
482.50	582.50	070216 15:44	070216 17:35	1.05E-04	1.20E-04	1,800	1,800	5,687	5,686	5,884	5,687	15.8	CHi / CHir
102.50	122.50	070217 18:25	070217 20:28	5.67E-05	6.17E-05	1,200	3,600	1,194	1,197	1,396	1,201	7.9	CHi / CHir
122.50	142.50	070218 08:25	070218 10:31	1.67E-08	2.00E-08	600	2,400	1,387	1,401	1,627	1,435	8.3	CHi / CHir
142.50	162.50	070218 11:07	070218 12:53	#NV	#NV	10	3,600	1,581	1,599	1,833	1,674	8.5	Pi
162.50	182.50	070218 13:24	070218 14:46	2.18E-06	2.35E-06	1,200	1,200	1,776	1,782	1,981	1,783	8.8	CHi / CHir
182.50	202.50	070218 16:10	070218 17:42	5.18E-06	5.47E-06	1,200	1,200	1,971	1,973	2,172	1,971	9.0	CHi / CHir
202.50	222.50	070218 18:12	070218 19:32	8.00E-06	8.50E-06	1,200	1,200	2,166	2,168	2,382	2,168	9.3	CHi / CHir
222.50	242.50	070219 09:02	070219 10:27	1.72E-05	1.85E-05	1,200	1,200	2,362	2,367	2,567	2,377	9.6	CHi / CHir
242.50	262.50	070219 11:04	070219 12:53	3.67E-07	4.17E-07	1,200	2,400	2,556	2,565	2,764	2,565	10.0	CHi / CHir
262.50	282.50	070219 14:13	070219 15:40	1.37E-06	1.49E-06	1,200	1,200	2,751	2,751	2,963	2,752	10.3	CHi / CHir
282.50	302.50	070219 16:17	070219 17:40	1.80E-05	1.87E-05	1,200	1,200	2,949	2,943	3,143	2,943	10.6	CHi / CHir
302.50	322.50	070219 18:12	070219 19:37	8.00E-05	9.17E-05	1,200	1,200	3,141	3,138	3,336	3,138	10.9	CHi / CHir
322.50	342.50	070220 08:18	070220 09:42	1.60E-06	1.67E-06	1,200	1,200	3,338	3,336	3,534	3,335	11.1	CHi / CHir
342.50	362.50	070220 10:20	070220 11:43	2.52E-04	2.62E-04	1,200	1,200	3,531	3,529	3,647	3,531	11.0	CHi / CHir
355.50	375.50	070220 12:56	070220 14:18	2.79E-04	2.92E-04	1,200	1,200	3,658	3,657	3,817	3,659	11.2	CHi / CHir
375.50	395.50	070220 15:00	070220 16:26	2.37E-04	4.68E-04	1,200	1,200	3,854	3,853	3,861	3,857	12.3	CHi / CHir
395.50	415.50	070220 17:07	070220 18:30	2.41E-04	2.50E-04	1,200	1,200	4,052	4,052	4,160	4,053	13.0	CHi / CHir
415.50	435.50	070221 08:38	070221 10:02	1.55E-04	1.60E-04	1,200	1,200	4,247	4,246	4,442	4,247	13.5	CHi / CHir
435.50	455.50	070221 10:41	070221 12:03	2.43E-04	2.53E-04	1,200	1,200	4,443	4,444	4,534	4,444	13.8	CHi / CHir
455.50	475.50	070221 13:02	070221 14:30	1.87E-04	1.99E-04	1,200	1,200	4,639	4,638	4,758	4,639	14.1	CHi / CHir
475.50	495.50	070221 15:28	070221 16:54	6.07E-05	6.68E-05	1,200	1,200	4,834	4,833	5,031	4,833	14.4	CHi / CHir
493.00	513.00	070221 17:33	070221 18:58	5.92E-05	6.40E-05	1,200	1,200	5,005	5,005	5,203	5,005	14.7	CHi / CHir
507.00	527.00	070222 08:14	070222 09:36	1.48E-05	1.57E-05	1,200	1,200	5,142	5,140	5,339	5,141	14.9	CHi / CHir
527.00	547.00	070222 10:14	070222 11:38	1.67E-05	1.80E-05	1,200	1,200	5,338	5,336	5,536	5,339	15.2	CHi / CHir
547.00	567.00	070222 13:02	070222 14:22	1.63E-05	1.78E-05	1,200	1,200	5,533	5,532	5,731	5,533	15.5	CHi / CHir
562.50	582.50	070222 15:00	070222 17:15	1.45E-06	1.77E-06	1,200	3,600	5,686	5,685	5,883	5,691	15.8	CHi / CHir
583.50	595.85	070222 15:00	070222 17:15	1.45E-06	1.77E-06	1,200	3,600	5,711	5,712	5,798	5,717	#NV	Response Analysis

---

**Nomenclature**

---

$Q_p$	Flow in test section immediately before stop of flow [m <sup>3</sup> /s]
$Q_m$	Arithmetical mean flow during perturbation phase [m <sup>3</sup> /s]
$t_p$	Duration of perturbation phase [s]
$t_f$	Duration of recovery phase [s]
$p_0$	Pressure in borehole before packer inflation [kPa]
$p_i$	Pressure in test section before start of flowing [kPa]
$p_p$	Pressure in test section before stop of flowing [kPa]
$p_F$	Pressure in test section at the end of the recovery [kPa]
$T_{e_w}$	Temperature in test section
Test phases	CHi Constant Head injection phase CHir: Recovery phase following the constant head injection phase Pi: Pulse injection phase
#NV	not analysed/no values

---

**Table 6-2. Results from analysis of hydraulic tests in KLX13A (for nomenclature see appendix 4 and below).**

Interval position		Stationary flow parameters		Transient analysis														Static conditions	
up	low	Q/s	T <sub>M</sub>	Flow regime		Formation parameters								C	ξ	dt <sub>1</sub>	dt <sub>2</sub>	p*	h <sub>wif</sub>
m	btoc	m <sup>2</sup> /s	m <sup>2</sup> /s	Perturb. Phase	Recovery Phase	T <sub>f1</sub>	T <sub>f2</sub>	T <sub>s1</sub>	T <sub>s2</sub>	T <sub>T</sub>	T <sub>TMIN</sub>	T <sub>TMAX</sub>	m <sup>3</sup> /Pa	-	min	min	kPa	m.a.s.l.	
102.50	202.50	3.22E-06	4.19E-06	2	WBS22	4.5E-06	#NV	2.6E-06	8.2E-06	2.6E-06	1.0E-06	8.0E-06	1.1E-10	-2.4	0.07	0.98	1,978.7	15.71	
202.50	302.50	1.80E-06	2.34E-06	22	WBS22	1.5E-06	#NV	3.7E-06	1.6E-06	1.5E-06	8.0E-07	6.0E-06	4.4E-10	-2.4	2.06	26.88	2,941.2	14.75	
302.50	402.50	2.35E-04	3.06E-04	22	WBS22	4.1E-04	7.5E-05	#NV	#NV	4.1E-04	7.0E-05	8.0E-04	#NV	-0.7	#NV	#NV	#NV	#NV	
395.50	495.50	9.69E-05	1.26E-04	2	WBS2	9.2E-05	#NV	2.8E-04	#NV	9.2E-05	1.0E-05	2.0E-04	2.0E-08	-3.9	5.61	25.90	4,837.2	16.67	
482.50	582.50	5.20E-06	6.77E-06	2	WBS2	5.7E-06	2.9E-06	2.1E-05	#NV	5.7E-06	1.0E-06	7.0E-06	1.1E-09	0.4	0.28	3.06	5,684.4	16.68	
102.50	122.50	2.79E-06	2.92E-06	22	WBS22	2.5E-06	4.7E-06	2.3E-06	5.7E-06	2.3E-06	1.0E-06	7.0E-06	2.3E-10	-2.2	0.22	1.84	1,198.9	15.73	
122.50	142.50	7.23E-10	7.57E-10	2	WBS2	1.3E-10	#NV	1.0E-10	#NV	1.0E-10	7.0E-11	4.0E-10	3.3E-11	-1.2	#NV	#NV	1,362.2	#NV	
142.50	162.50	#NV	#NV	#NV	2	#NV	#NV	2.9E-11	#NV	2.9E-11	9.0E-12	7.0E-11	2.4E-11	-0.3	#NV	#NV	#NV	#NV	
162.50	182.50	1.08E-07	1.13E-07	2	WBS2	1.9E-07	#NV	1.1E-07	4.2E-07	1.9E-07	9.0E-08	6.0E-07	6.3E-11	4.2	1.52	16.68	1,782.2	15.67	
182.50	202.50	2.56E-07	2.67E-07	2	WBS22	3.2E-07	#NV	2.5E-07	6.2E-07	2.5E-07	1.0E-07	8.0E-07	5.6E-11	0.3	0.31	1.23	1,965.1	14.32	
202.50	222.50	3.67E-07	3.84E-07	2	WBS2	6.4E-07	#NV	2.4E-06	#NV	6.4E-07	4.0E-07	3.0E-06	6.7E-11	3.6	0.19	13.32	2,166.3	15.30	
222.50	242.50	8.42E-07	8.81E-07	22	WBS22	1.2E-06	5.7E-07	2.3E-06	6.3E-07	5.7E-07	2.0E-07	1.0E-06	1.5E-10	0.2	4.82	18.25	2,360.1	15.05	
242.50	262.50	1.81E-08	1.89E-08	2	WBS2	2.5E-08	#NV	8.7E-08	#NV	2.5E-08	1.0E-08	9.0E-08	1.0E-10	2.8	2.68	15.86	2,563.2	15.75	
262.50	282.50	6.32E-08	6.62E-08	2	WBS22	1.2E-07	#NV	2.3E-08	7.5E-08	1.2E-07	3.0E-08	3.0E-07	2.4E-11	-2.2	2.70	17.74	2,743.6	14.61	
282.50	302.50	8.83E-07	9.24E-07	2	WBS2	1.4E-06	#NV	2.0E-06	#NV	2.0E-06	9.0E-07	5.0E-06	2.0E-10	6.9	0.53	13.15	2,939.1	14.53	
302.50	322.50	3.96E-06	4.15E-06	22	WBS2	6.8E-06	2.0E-06	2.1E-05	#NV	2.1E-05	1.0E-06	4.0E-05	2.1E-10	20.3	0.34	7.99	3,137.7	14.77	
322.50	342.50	7.93E-08	8.29E-08	22	WBS22	1.6E-07	3.1E-07	5.9E-08	2.9E-07	1.6E-07	8.0E-08	5.0E-07	8.3E-11	6.7	1.30	16.65	3,334.2	15.27	
342.50	362.50	2.09E-05	2.19E-05	2	WBS2	4.6E-05	#NV	4.8E-05	#NV	4.8E-05	2.0E-05	7.0E-05	5.1E-09	5.2	0.91	13.78	3,529.9	15.22	
355.50	375.50	1.71E-05	1.79E-05	2	WBS2	4.1E-05	#NV	6.1E-05	#NV	4.1E-05	2.0E-05	8.0E-05	1.9E-09	6.0	0.38	19.17	3,658.5	15.58	
375.50	395.50	2.91E-04	3.04E-04	22	#NV	4.4E-04	1.3E-04	#NV	#NV	4.4E-04	7.0E-05	8.0E-04	#NV	-2.8	#NV	#NV	#NV	#NV	
395.50	415.50	2.18E-05	2.29E-05	2	WBS2	4.8E-05	#NV	5.6E-05	#NV	4.8E-05	3.0E-05	7.0E-05	1.6E-09	4.4	0.22	16.10	4,053.1	15.81	
415.50	435.50	7.73E-06	8.09E-06	2	WBS2	1.9E-05	#NV	3.4E-05	#NV	1.9E-05	9.0E-06	5.0E-05	1.1E-09	6.0	0.78	13.44	4,246.6	16.00	
435.50	455.50	2.65E-05	2.77E-05	2	WBS2	5.5E-05	#NV	5.9E-05	#NV	5.5E-05	3.0E-05	8.0E-05	3.3E-09	5.5	0.18	16.50	4,442.8	16.00	
455.50	475.50	1.53E-05	1.60E-05	2	WBS2	2.9E-05	#NV	5.4E-05	#NV	2.9E-05	1.0E-05	7.0E-05	1.5E-09	2.9	0.91	12.31	4,638.9	15.99	
475.50	495.50	3.01E-06	3.14E-06	2	WBS2	3.5E-06	#NV	1.4E-05	#NV	3.5E-06	1.0E-06	8.0E-06	3.5E-10	-0.8	0.61	18.65	4,833.3	16.27	
493.00	513.00	2.93E-06	3.07E-06	2	WBS2	3.5E-06	#NV	1.4E-05	#NV	3.5E-06	1.0E-06	6.0E-06	1.7E-10	-0.4	8.50	26.27	5,005.4	16.37	
507.00	527.00	7.31E-07	7.65E-07	2	WBS2	9.1E-07	#NV	3.5E-06	#NV	9.1E-07	7.0E-07	4.0E-06	2.9E-10	0.8	0.17	17.90	5,140.4	16.08	
527.00	547.00	8.18E-07	8.55E-07	2	WBS2	9.5E-07	#NV	3.1E-06	#NV	9.5E-07	7.0E-07	5.0E-06	1.8E-10	0.0	0.20	18.25	5,335.5	15.96	
547.00	567.00	8.05E-07	8.42E-07	2	WBS2	1.1E-06	#NV	4.1E-06	#NV	1.1E-06	8.0E-07	5.0E-06	7.1E-11	0.9	0.28	18.27	5,530.2	16.27	
562.50	582.50	7.18E-08	7.52E-08	2	WBS2	3.7E-08	#NV	3.7E-08	7.3E-08	3.7E-08	1.0E-08	5.0E-08	8.5E-12	-2.9	2.44	18.35	5,677.5	15.98	
583.50	595.85	#NV	#NV	22	22	4.0E-08	1.1E-07	6.4E-08	1.4E-07	6.4E-08	1.0E-08	1.0E-07	#NV	#NV	1.80	8.62	#NV	#NV	

---

## Nomenclature

---

Q/s	Specific capacity.
T <sub>M</sub>	Transmissivity according to /Moye 1967/.
Flow regime	The flow regime description refers to the recommended model used in the transient analysis. WBS denotes wellbore storage and skin and is followed by a set of numbers describing the flow dimension used in the analysis (1 = linear flow, 2 = radial flow, 3 = spherical flow). If only one number is used (e.g. WBS2 or 2) a homogeneous flow model (1 composite zone) was used in the analysis, if two numbers are given (WBS22 or 22) a 2 zones composite model was used.
T <sub>f</sub>	Transmissivity derived from the analysis of the perturbation phase (CHi). In case a homogeneous flow model was used only one T <sub>f</sub> value is reported, in case a two zone composite flow model was used both T <sub>f1</sub> (inner zone) and T <sub>f2</sub> (outer zone) are given.
T <sub>s</sub>	Transmissivity derived from the analysis of the recovery phase (CHir or Pi). In case a homogeneous flow model was used only one T <sub>s</sub> value is reported, in case a two zone composite flow model was used both T <sub>s1</sub> (inner zone) and T <sub>s2</sub> (outer zone) are given.
T <sub>T</sub>	Recommended transmissivity.
T <sub>TMIN</sub>	Confidence range lower limit.
T <sub>TMAX</sub>	Confidence range upper limit.
C	Wellbore storage coefficient.
ξ	Skin factor (calculated based on a Storativity of $1 \cdot 10^{-6}$ ).
dt <sub>1</sub>	Estimated start time of evaluation.
dt <sub>2</sub>	Estimated stop time of evaluation.
p*	The parameter p* denoted the static formation pressure (measured at transducer depth) and was derived from the HORNER plot of the CHir phase using straight line or type-curve extrapolation.
h <sub>wif</sub>	Fresh-water head (based on transducer depth and p*).
#NV	Not analysed/no values.

---



**Table 6-3. Results from the ri-index calculation of hydraulic tests in KLX13A  
(see Chapter 4.5.5 for details and nomenclature)**

Borehole secup [m b ToC]	Borehole seclow [m b ToC]	Recommended Transmissivity Tt [m <sup>2</sup> /s]	ri-index [-]	Time t <sub>2</sub> for radius of influence calculation [s]	Radius of Influence ri [m]
102.50	202.50	2.56E-06	-1	59	21.91
202.50	302.50	1.50E-06	0	1,800	106.06
302.50	402.50	4.12E-04	1	#NV	#NV
395.50	495.50	9.16E-05	0	1,800	296.50
482.50	582.50	5.74E-06	1	184	47.38
102.50	122.50	2.33E-06	-1	110	29.32
122.50	142.50	1.03E-10	1	2,400	11.15
142.50	162.50	2.86E-11	0	3,600	9.91
162.50	182.50	1.87E-07	0	1,200	51.46
182.50	202.50	2.54E-07	-1	74	13.78
202.50	222.50	6.41E-07	0	1,200	70.02
222.50	242.50	5.69E-07	1	289	49.26
242.50	262.50	2.49E-08	0	1,200	31.09
262.50	282.50	1.16E-07	0	1,200	45.67
282.50	302.50	2.04E-06	0	1,200	93.52
302.50	322.50	2.05E-05	0	1,200	166.51
322.50	342.50	1.58E-07	1	999	45.02
342.50	362.50	4.83E-05	0	1,200	206.30
355.50	375.50	4.10E-05	0	1,200	198.02
375.50	395.50	4.38E-04	1	#NV	#NV
395.50	415.50	4.82E-05	0	1,200	206.19
415.50	435.50	1.85E-05	0	1,200	162.29
435.50	455.50	5.53E-05	0	1,200	213.40
455.50	475.50	2.90E-05	0	1,200	181.59
475.50	495.50	3.47E-06	0	1,200	106.80
493.00	513.00	3.53E-06	0	1,200	107.26
507.00	527.00	9.13E-07	0	1,200	76.49
527.00	547.00	9.46E-07	0	1,200	77.17
547.00	567.00	1.08E-06	0	1,200	79.77
562.50	582.50	3.67E-08	-1	1,101	32.81

The Figures 6-1 to 6-3 present the transmissivity, conductivity and hydraulic freshwater head profiles.




Figure 6-1. Results summary – profiles of transmissivity and equivalent freshwater head extrapolated.





Figure 6-2. Results summary – profile of transmissivity.



**Figure 6-3.** Results summary – profile of hydraulic conductivity.

## 6.2 Correlation analysis

A correlation analysis was used with the aim of examining the consistency of results and deriving general conclusion regarding the testing and analysis methods used.

### 6.2.1 Comparison of steady state and transient analysis results

The steady state derived transmissivities ( $T_M$ ) and specific capacities ( $Q/s$ ) were compared in a cross-plot with the recommended transmissivity values derived from the transient analysis (see following figure).

The correlation analysis shows that the transmissivities derived from the steady state analysis differ by less than one order of magnitude from the transmissivities derived from the transient analysis.




Figure 6-4. Correlation analysis of transmissivities derived by steady state and transient methods.

## 6.2.2 Comparison between the matched and theoretical wellbore storage coefficient

The wellbore storage coefficient describes the capacity of the test interval to store fluid as result to an unit pressure change in the interval. For a closed system (i.e. closed downhole valve) the theoretical value of the wellbore storage coefficient is given by the product between the interval volume and the test zone compressibility. The interval volume is calculated from the borehole radius and interval length. There are uncertainties concerning the interval volume calculation. Cavities or high transmissivity fractures intersecting the interval may enlarge the effective volume of the interval.

The test zone compressibility is given by the sum of compressibilities of the individual components present in the interval (water, packer elements, other test tool components, and the borehole wall). The water compressibility depends on the temperature and salinity. However, for temperature and salinity values as encountered at the Oskarshamn site the water compressibility varies only slightly between  $4.5 \cdot 10^{-10}$  and  $5.0 \cdot 10^{-10}$  1/Pa.

A water compressibility of  $5 \cdot 10^{-10}$  1/Pa and a rock compressibility of  $1 \cdot 10^{-10}$  1/Pa was assumed for the analysis. In addition, the test zone compressibility is influenced by the test tool (packer compliance). The test tool compressibility was calculated as follow:

$$c = \frac{\Delta V}{\Delta p} \times \frac{1}{V} \text{ [1/Pa]}$$

$\Delta V$  Volume change of 2 Packers (The volume change was estimated at  $7 \cdot 10^{-7}$  m<sup>3</sup>/100 kPa based on the results of laboratory tests conducted by GEOSIGMA) [m<sup>3</sup>].

$\Delta p$  Pressure change in test section (usually  $2 \cdot 10^5$  Pa) [Pa].

$V$  Volume in test section [m<sup>3</sup>].

The following table presents the calculated compressibilities for each relevant section length. The average value for the test tool compressibility based on different section length is  $1 \cdot 10^{-10}$  1/Pa.

**Table 6-4. Test tool compressibility values based on packer displacement.**

Length of test section [m]	Volume in test section [m <sup>3</sup> ]	Compressibility [1/Pa]
20	0.091	$8 \cdot 10^{-11}$
100	0.454	$2 \cdot 10^{-11}$
Average compressibility:		$5 \cdot 10^{-11}$

The sum of the compressibilities (water, rock, test tool) leads to a test zone compressibility with a value of  $7 \cdot 10^{-10}$  1/Pa. This value is used for the calculation of the theoretical wellbore storage coefficient.

The matched wellbore storage coefficient is derived from the transient type curve analysis by matching the unit slope early times derivative plotted in log-log coordinates.

The following figure presents a cross-plot of the matched and theoretical wellbore storage coefficients.

It can be seen that the matched wellbore storage coefficients differ up to three orders of magnitude from the theoretical. This phenomenon was already observed at the previous boreholes. A two or three orders of magnitude increase is difficult to explain by volume uncertainty. Even if large fractures are connected to the interval, a volume increase by two orders of magnitude does not seem probable. This discrepancy is not fully understood, but following hypotheses may be formulated:

- Increased compressibility of the packer system.
- As shown by previous work conducted at site, the phenomenon of increased wellbore storage coefficients can be explained by turbulent flow induced by the test in the vicinity of the borehole. Considering the fact that deviations concerning the wellbore storage rather occur in test sections with a higher transmissivity (which can lead to turbulent flow) seems to rest upon this hypothesis.




Figure 6-5. Correlation analysis of theoretical and matched wellbore storage coefficients.



## 7 Conclusions

### 7.1 Transmissivity

Figure 6-1 presents a profile of transmissivity, including the confidence ranges derived from the transient analysis. The method used for deriving the recommended transmissivity and its confidence range is described in Section 4.5.9.

Whenever possible, the transmissivities derived are representative for the “undisturbed formation” further away from the borehole. The borehole vicinity was typically described by using a skin effect.

If the conducted preliminary pulse injection (PI) showed a slow recovery the pulse test was prolonged and no further injection test was performed. The pulse test was used for a quantitative analysis. In one case the preliminary pulse was prolonged and the recommended transmissivity is  $2.9 \cdot 10^{-11} \text{ m}^2/\text{s}$  (Section 142.5–162.5 m).

The recommended transmissivities derived from the conducted injection tests (CHi and CHir) range from  $1.5 \cdot 10^{-6} \text{ m}^2/\text{s}$  to  $4.1 \cdot 10^{-4} \text{ m}^2/\text{s}$  for 100 m tests and  $1.0 \cdot 10^{-10} \text{ m}^2/\text{s}$  to  $4.4 \cdot 10^{-4} \text{ m}^2/\text{s}$  for the 20 m tests.

In two cases the 20 m sections show a higher transmissivity than the appropriate 100 m section. These differences are very small and are covered by the confidence range.

### 7.2 Equivalent freshwater head

Figure 6-1 presents a profile of the derived equivalent freshwater head expressed in meters above sea level. The method used for deriving the equivalent freshwater head is described in Section 4.5.8.

The head profile shows a freshwater head that ranges from 14.3 m to 16.7 m and that is slightly increasing with depth. This increase can be explained with a higher salinity down in the borehole.

In general, the uncertainty related to the derived freshwater heads is dependent on the test section transmissivity. Due to the relatively short pressure recovery phase, the static pressure extrapolation becomes increasingly uncertain at lower transmissivities.

### 7.3 Flow regimes encountered

The flow models used in analysis were derived from the shape of the pressure derivative calculated with respect to log time and plotted in log-log coordinates.

In several cases the pressure derivative suggests a change of transmissivity with the distance from the borehole. In such cases a composite flow model was used in the analysis.

If there were different flow models matching the data in comparable quality, the simplest model was preferred.

In some cases very large skins has been observed. This is unusual and should be further examined. There are several possible explanations to this behaviour:

- If the behaviour is to be completely attributed to changes of transmissivity in the formation, this indicates the presence of larger transmissivity zones in the borehole vicinity, which could be caused by steep fractures that do not intersect the test interval, but are connected to the interval by lower transmissivity fractures. The fact that in many cases the test derivatives of adjacent test sections converge at late times seems to support this hypothesis.
- A further possibility is that the large skins are caused by turbulent flow taking place in the tool or in fractures connected to the test interval. This hypothesis is more difficult to examine. However, considering the fact that some high skins were observed in sections with transmissivities as low as  $1 \cdot 10^{-8} \text{ m}^2/\text{s}$  (which imply low flow rates) seems to speak against this hypothesis.

The flow dimension displayed by the test can be diagnosed from the slope of the pressure derivative. A slope of 0.5 indicates linear flow, a slope of 0 (horizontal derivative) indicates radial flow and a slope of  $-0.5$  indicates spherical flow. The flow dimension diagnosis was commented for each of the tests. In all of the cases it was possible to get a good match quality by using radial flow geometry. In no cases an alternative analysis with a flow dimension unequal to two was performed. The analyses are presented in Appendix 2.

## 8 References

- Bourdet D, Ayoub J A, Pirard Y M, 1989.** Use of pressure derivative in well-test interpretation. *Coc. Of Petroleum Engineers, SPE Formation Evaluation.* pp. 293–302.
- Chakrabarty C, Enachescu C, 1997.** Using the Devolution Approach for Slug Test Analysis: Theory and Application. *Ground Water* Sept.–Oct. 1997. pp. 797–806.
- Gringarten A C, 1986.** Computer-aided well-test analysis. *SPE Paper* 14099.
- Horne R N, 1990.** *Modern well test analysis.* Petroway, Inc., Palo Alto, Calif.
- Horner D R, 1951.** Pressure build-up in wells. *Third World Pet. Congress, E.J. Brill, Leiden II,* pp. 503–521.
- Jacob C E, Lohman S W, 1952.** Nonsteady flow to a well of constant drawdown in an extensive aquifer. *Transactions, American Geophysical Union, Volume 33, No 4,* pp. 559–569.
- Moye D G, 1967.** Diamond drilling for foundation exploration. *Civil Eng. Trans., Inst. Eng. Australia,* Apr. 1967, pp. 95–100.
- Peres A M M, Onur M, Reynolds A C, 1989.** A new analysis procedure for determining aquifer properties from slug test data. *Water Resour. Res.* v. 25, no. 7, pp. 1591–1602.
- Rhen I, 2005.** Reporting influence radius – proposal (2005-02-09).
- Rhen I, Forsmark T, Forssman, I, Zetterlund M, 2006.** Evaluation of hydrogeo-logical properties for Hydraulic Conductor Domains (HCD) and Hydraulic Rock Domains (HRD). SKB R-06-22, Svensk Kärnbränslehantering AB.
- SKB 2001.** Platsundersökningar. Undersökningsmetoder och generellt genomförandeprogram. SKB R-01-10, Svensk Kärnbränslehantering AB.
- SKB 2002.** Execution programme for the initial site investigations at Simpevarp. SKB P-02-06, Svensk Kärnbränslehantering AB.
- SKB 2006.** Programme for further investigations of bedrock, soil, water and environment in Laxemar subarea. SKB R-06-29, Svensk Kärnbränslehantering AB.
- THEIS C V, 1935.** The relation between the lowering of the piezometric surface and the rate and duration of discharge of a well using ground-water storage. *Trans. Am. Geophys. Union* 16:519–524.

Borehole: KLX13 A

## **APPENDIX 1**

File Description Table

<b>HYDROTESTING WITH PSS</b>				<b>DRILLHOLE IDENTIFICATION NO.: KLX13A</b>					
<b>TEST- AND FILEPROTOCOL</b>				<b>Testorder dated : 2007-02-14</b>					
Teststart		Interval boundaries		Name of Datafiles		Testtype	Copied to disk/CD	Plotted (date)	Sign.
Date	Time	Upper	Lower	(*HT2-file)	(*CSV-file)				
2007-02-15	09:48	102.50	202.50	__KLX13A_0102.50_200702150948.ht2	KLX13A_102.50-202.50_070215_1_CHir_Q_r.csv	Chir		2007-02-15	
2007-02-15	15:34	202.50	302.50	__KLX13A_0202.50_200702151534.ht2	KLX13A_202.50-302.50_070215_1_CHir_Q_r.csv	Chir		2007-02-15	
2007-02-16	07:58	302.50	402.50	__KLX13A_0302.50_200702160758.ht2	KLX13A_302.50-402.50_070216_1_CHir_Q_r.csv	Chir		2007-02-16	
2007-02-16	11:52	395.50	495.50	__KLX13A_0395.50_200702161152.ht2	KLX13A_395.50-495.50_070216_1_CHir_Q_r.csv	Chir		2007-02-16	
2007-02-16	15:44	482.50	582.50	__KLX13A_0482.50_200702161544.ht2	KLX13A_482.50-582.50_070216_1_CHir_Q_r.csv	Chir		2007-02-17	
2007-02-17	18:25	102.50	122.50	__KLX13A_0102.50_200702171825.ht2	KLX13A_102.50-122.50_070217_1_CHir_Q_r.csv	Chir		2007-02-18	
2007-02-18	08:25	122.50	142.50	__KLX13A_0122.50_200702180825.ht2	KLX13A_122.50-142.50_070218_1_CHir_Q_r.csv	Chir		2007-02-18	
2007-02-18	11:07	142.50	162.50	__KLX13A_0142.50_200702181107.ht2	KLX13A_142.50-162.50_070218_1_Pi_Q_r.csv	Pi		2007-02-18	
2007-02-18	13:24	162.50	182.50	__KLX13A_0162.50_200702181324.ht2	KLX13A_162.50-182.50_070218_1_CHir_Q_r.csv	Chir		2007-02-18	
2007-02-18	16:10	182.50	202.50	__KLX13A_0182.50_200702181610.ht2	KLX13A_182.50-202.50_070218_1_CHir_Q_r.csv	Chir		2007-02-18	
2007-02-18	18:12	202.50	222.50	__KLX13A_0202.50_200702181812.ht2	KLX13A_202.50-222.50_070218_1_CHir_Q_r.csv	Chir		2007-02-18	
2007-02-19	09:02	222.50	242.50	__KLX13A_0222.50_200702190902.ht2	KLX13A_222.50-242.50_070219_1_CHir_Q_r.csv	Chir		2007-02-19	
2007-02-19	11:04	242.50	262.50	__KLX13A_0242.50_200702191104.ht2	KLX13A_242.50-262.50_070219_1_CHir_Q_r.csv	Chir		2007-02-19	
2007-02-20	17:06	395.50	415.50	__KLX13A_0395.50_200702201706.ht2	KLX13A_395.50-415.50_070220_1_CHir_Q_r.csv	Chir		2007-02-21	
2007-02-21	08:38	415.50	435.50	__KLX13A_0415.50_200702210838.ht2	KLX13A_415.50-435.50_070221_1_CHir_Q_r.csv	Chir		2007-02-21	

<b>HYDROTESTING WITH PSS</b>					<b>DRILLHOLE IDENTIFICATION NO.: KLX13A</b>				
<b>TEST- AND FILEPROTOCOL</b>					<b>Testorder dated : 2007-02-14</b>				
Teststart		Interval boundaries		Name of Datafiles		Testtype	Copied to disk/CD	Plotted (date)	Sign.
Date	Time	Upper	Lower	(*HT2-file)	(*CSV-file)				
2007-02-21	10:41	435.50	455.50	__KLX13A_0435.50_200702211041.ht2	KLX13A_435.50-455.50_070221_1_CHir_Q_r.csv	Chir		2007-02-21	
2007-02-21	13:02	455.50	475.50	__KLX13A_0455.50_200702211302.ht2	KLX13A_455.50-475.50_070221_1_CHir_Q_r.csv	Chir		2007-02-21	
2007-02-21	15:28	475.50	495.50	__KLX13A_0475.50_200702211528.ht2	KLX13A_475.50-495.50_070221_1_CHir_Q_r.csv	Chir		2007-02-21	
2007-02-21	17:33	493.00	513.00	__KLX13A_0493.00_200702211733.ht2	KLX13A_493.00-513.00_070221_1_CHir_Q_r.csv	Chir		2007-02-22	
2007-02-22	08:14	507.00	527.00	__KLX13A_0507.00_200702220814.ht2	KLX13A_507.00-527.00_070222_1_CHir_Q_r.csv	Chir		2007-02-22	
2007-02-22	10:14	527.00	547.00	__KLX13A_0527.00_200702221014.ht2	KLX13A_527.00-547.00_070222_1_CHir_Q_r.csv	Chir		2007-02-22	
2007-02-22	13:02	547.00	567.00	__KLX13A_0547.00_200702221302.ht2	KLX13A_547.00-567.00_070222_1_CHir_Q_r.csv	Chir		2007-02-22	
2007-02-22	15:00	562.50	582.50	__KLX13A_0562.50_200702221500.ht2	KLX13A_562.50-582.50_070222_1_CHir_Q_r.csv	Chir		2007-02-22	

Borehole: KLX13A

## **APPENDIX 2**


Analysis diagrams

## **APPENDIX 2-1**


Test 102.50 – 202.50 m

Analysis diagrams







Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-2**

Test 202.50 – 302.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match

## **APPENDIX 2-3**


Test 302.50 – 402.50 m

Analysis diagrams






Pressure and flow rate vs. time; cartesian plot



Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match

Borehole: KLX13A  
Test: 302.50 – 402.50 m

Page 2-3/4

**Not analysable**

CHIR phase; log-log match


**Not analysable**

CHIR phase; HORNER match


## **APPENDIX 2-4**

Test 395.50 – 495.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match

## **APPENDIX 2-5**


Test 482.50 – 582.50 m

Analysis diagrams







Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-6**

Test 102.50 – 122.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match

## **APPENDIX 2-7**


Test 122.50 – 142.50 m

Analysis diagrams







Pressure and flow rate vs. time; cartesian plot



Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match


**Not analysable**

CHIR phase; HORNER match


## **APPENDIX 2-8**

Test 142.50 – 162.50 m


Analysis diagrams



Pressure and flow rate vs. time; cartesian plot



Interval pressure and temperature vs. time; cartesian plot




Pulse injection; deconvolution plot


## **APPENDIX 2-9**

Test 162.50 – 182.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-10**

Test 182.50 – 202.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-11**

Test 202.50 – 222.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-12**

Test 222.50 – 242.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-13**

Test 242.50 – 262.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-14**

Test 262.50 – 282.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-15**

Test 282.50 – 302.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-16**

Test 302.50 – 322.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-17**

Test 322.50 – 342.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-18**

Test 342.50 – 362.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-19**

Test 355.50 – 375.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-20**

Test 375.50 – 395.50 m


Analysis diagrams



Pressure and flow rate vs. time; cartesian plot



Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match

Borehole: KLX13A  
Test: 375.50 – 395.50 m

Page 2-20/4

**Not analysable**

CHIR phase; log-log match


**Not analysable**

CHIR phase; HORNER match


## **APPENDIX 2-21**

Test 395.50 – 415.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-22**

Test 415.50 – 435.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-23**

Test 435.50 – 455.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-24**

Test 455.50 – 475.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-25**

Test 475.50 – 495.50 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-26**

Test 493.00 – 513.00 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-27**

Test 507.00 – 527.00 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-28**

Test 527.00 – 547.00 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-29**

Test 547.00 – 567.00 m

Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot






CHI phase; log-log match



CHIR phase; log-log match




CHIR phase; HORNER match


## **APPENDIX 2-30**

Test 562.50 – 582.50 m


Analysis diagrams




Pressure and flow rate vs. time; cartesian plot




Interval pressure and temperature vs. time; cartesian plot



CHI phase; log-log match



CHIR phase; log-log match



CHIR phase; HORNER match


## **APPENDIX 2-31**

Observation section 583.50 – 595.85 m  
(Bottom Zone)

Analysis diagrams


See Appendix 2-30

Pressure and flow rate vs. time; cartesian plot




Bottom zone pressure; cartesian plot





CHI phase; log-log match; Bottom zone response



CHIR phase; log-log match; Bottom zone response

## **APPENDIX 3**

### Test Summary Sheets

<b>Test Summary Sheet</b>			
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070215 09:48
Test section from - to (m):	102.50-202.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>2300 2100 1900 1700 1500 1300 1100 900</p> <p>0.00 0.50 1.00 1.50 2.00 2.50 3.00 3.50 4.00 4.50</p> <p style="text-align: center;">Elapsed Time [h]</p> <p style="text-align: center;">KLX13A_102.50-202.50_070215_1_CHir_Q_r</p> <p style="text-align: right;">             • P section              • P above              • P below              - Q         </p>		<p><b>Indata</b></p> <p>p<sub>0</sub> (kPa) = 1971</p> <p>p<sub>i</sub> (kPa) = 1978</p> <p>p<sub>p</sub> (kPa) = 2176</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 6.50E-05</p> <p>tp (s) = 1800</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 9.1</p> <p>Derivative fact. = 0.08</p>	
		<p>p<sub>F</sub> (kPa) = 1981</p> <p>t<sub>F</sub> (s) = 1800</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.05</p>	
		<p><b>Results</b></p> <p>Q/s (m<sup>2</sup>/s) = 3.2E-06</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 4.2E-06</p>	
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.43</p> <p>dt<sub>2</sub> (min) = 19.28</p> <p>T (m<sup>2</sup>/s) = 4.5E-06</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 4.5E-08</p> <p>S<sub>s</sub> (1/m) = 1.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = 0.54</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.07</p> <p>dt<sub>2</sub> (min) = 0.98</p> <p>T (m<sup>2</sup>/s) = 2.6E-06</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 2.6E-08</p> <p>S<sub>s</sub> (1/m) = 1.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 1.1E-10</p> <p>C<sub>D</sub> (-) = 1.2E-02</p> <p>ξ (-) = -2.39</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>	
		<p>dt<sub>1</sub> (min) = 0.07</p> <p>dt<sub>2</sub> (min) = 0.98</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 2.6E-06</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 2.6E-08</p> <p>S<sub>s</sub> (1/m) = 1.0E-08</p>	
		<p>C (m<sup>3</sup>/Pa) = 1.1E-10</p> <p>C<sub>D</sub> (-) = 1.2E-02</p> <p>ξ (-) = -2.39</p>	
		<p><b>Comments:</b></p> <p>The recommended transmissivity of 2.6E-6 m<sup>2</sup>/s was derived from the analysis of the CHir phase (inner zone), which shows the best data and derivative quality and a clear horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be 1.0E-6 m<sup>2</sup>/s to 8.0E-6 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 1,978.7 kPa.</p>	

Test Summary Sheet					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070215 15:34		
Test section from - to (m):	202.50-302.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	2946		
		p <sub>i</sub> (kPa) =	2947		
		p <sub>p</sub> (kPa) =	3147	p <sub>F</sub> (kPa) =	2954
		Q <sub>p</sub> (m <sup>3</sup> /s) =	3.67E-05		
		t <sub>p</sub> (s) =	1800	t <sub>F</sub> (s) =	1800
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	10.5		
Derivative fact. =	0.02	Derivative fact. =	0.02		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	1.8E-06				
T <sub>M</sub> (m <sup>2</sup> /s) =	2.3E-06				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		Flow regime:	transient		
		dt <sub>1</sub> (min) =	2.06	dt <sub>1</sub> (min) =	#NV
		dt <sub>2</sub> (min) =	26.88	dt <sub>2</sub> (min) =	#NV
		T (m <sup>2</sup> /s) =	1.5E-06	T (m <sup>2</sup> /s) =	3.7E-06
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	1.5E-08	K <sub>s</sub> (m/s) =	3.7E-08
		S <sub>s</sub> (1/m) =	1.0E-08	S <sub>s</sub> (1/m) =	1.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	4.4E-10
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	4.9E-02
		ξ (-) =	-2.39	ξ (-) =	1.52
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	2.06	C (m <sup>3</sup> /Pa) =	4.4E-10
		dt <sub>2</sub> (min) =	26.88	C <sub>D</sub> (-) =	4.9E-02
		T <sub>T</sub> (m <sup>2</sup> /s) =	1.5E-06	ξ (-) =	-2.39
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	1.5E-08		
		S <sub>s</sub> (1/m) =	1.0E-08		
<b>Comments:</b>		<p>The recommended transmissivity of 1.5E-06 m<sup>2</sup>/s was derived from the analysis of the CHi phase, which shows the clearest horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be 8.0E-07 m<sup>2</sup>/s to 6.0E-06 m<sup>2</sup>/s. The flow dimension during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,941.2 kPa.</p>			

<b>Test Summary Sheet</b>																																																															
Project:	Oskarshamn site investigation	<a href="#">Test type: f1</a>	CHir																																																												
Area:	Laxemar	Test no:	1																																																												
Borehole ID:	KLX13A	Test start:	070216 07:58																																																												
Test section from - to (m):	302.50-402.50 m	Responsible for test execution:	Stephan Rohs																																																												
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu																																																												
<b>Linear plot Q and p</b>		<b>Flow period</b>																																																													
		<b>Recovery period</b>																																																													
		<b>Indata</b>																																																													
		<table border="1"> <tr> <td>p<sub>0</sub> (kPa) =</td> <td>3922</td> <td></td> <td></td> </tr> <tr> <td>p<sub>i</sub> (kPa) =</td> <td>3923</td> <td></td> <td></td> </tr> <tr> <td>p<sub>p</sub> (kPa) =</td> <td>3934</td> <td>p<sub>F</sub> (kPa) =</td> <td>3927</td> </tr> <tr> <td>Q<sub>p</sub> (m<sup>3</sup>/s) =</td> <td>2.63E-04</td> <td></td> <td></td> </tr> <tr> <td>t<sub>p</sub> (s) =</td> <td>1800</td> <td>t<sub>F</sub> (s) =</td> <td>1800</td> </tr> <tr> <td>S e l S' (-) =</td> <td>1.00E-06</td> <td>S e l S' (-) =</td> <td>1.00E-06</td> </tr> <tr> <td>EC<sub>w</sub> (mS/m) =</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Temp<sub>w</sub> (gr C) =</td> <td>12.4</td> <td></td> <td></td> </tr> <tr> <td>Derivative fact. =</td> <td>0.02</td> <td>Derivative fact. =</td> <td>0.02</td> </tr> </table>		p <sub>0</sub> (kPa) =	3922			p <sub>i</sub> (kPa) =	3923			p <sub>p</sub> (kPa) =	3934	p <sub>F</sub> (kPa) =	3927	Q <sub>p</sub> (m <sup>3</sup> /s) =	2.63E-04			t <sub>p</sub> (s) =	1800	t <sub>F</sub> (s) =	1800	S e l S' (-) =	1.00E-06	S e l S' (-) =	1.00E-06	EC <sub>w</sub> (mS/m) =				Temp <sub>w</sub> (gr C) =	12.4			Derivative fact. =	0.02	Derivative fact. =	0.02																								
p <sub>0</sub> (kPa) =	3922																																																														
p <sub>i</sub> (kPa) =	3923																																																														
p <sub>p</sub> (kPa) =	3934	p <sub>F</sub> (kPa) =	3927																																																												
Q <sub>p</sub> (m <sup>3</sup> /s) =	2.63E-04																																																														
t <sub>p</sub> (s) =	1800	t <sub>F</sub> (s) =	1800																																																												
S e l S' (-) =	1.00E-06	S e l S' (-) =	1.00E-06																																																												
EC <sub>w</sub> (mS/m) =																																																															
Temp <sub>w</sub> (gr C) =	12.4																																																														
Derivative fact. =	0.02	Derivative fact. =	0.02																																																												
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>																																																													
		<table border="1"> <tr> <td>Q/s (m<sup>2</sup>/s) =</td> <td>2.3E-04</td> <td></td> <td></td> </tr> <tr> <td>T<sub>M</sub> (m<sup>2</sup>/s) =</td> <td>3.1E-04</td> <td></td> <td></td> </tr> <tr> <td>Flow regime:</td> <td>transient</td> <td>Flow regime:</td> <td>transient</td> </tr> <tr> <td>dt<sub>1</sub> (min) =</td> <td>#NV</td> <td>dt<sub>1</sub> (min) =</td> <td>#NV</td> </tr> <tr> <td>dt<sub>2</sub> (min) =</td> <td>#NV</td> <td>dt<sub>2</sub> (min) =</td> <td>#NV</td> </tr> <tr> <td>T (m<sup>2</sup>/s) =</td> <td>4.1E-04</td> <td>T (m<sup>2</sup>/s) =</td> <td>NA</td> </tr> <tr> <td>S (-) =</td> <td>1.0E-06</td> <td>S (-) =</td> <td>NA</td> </tr> <tr> <td>K<sub>s</sub> (m/s) =</td> <td>4.1E-06</td> <td>K<sub>s</sub> (m/s) =</td> <td>NA</td> </tr> <tr> <td>S<sub>s</sub> (1/m) =</td> <td>1.0E-08</td> <td>S<sub>s</sub> (1/m) =</td> <td>NA</td> </tr> <tr> <td>C (m<sup>3</sup>/Pa) =</td> <td>NA</td> <td>C (m<sup>3</sup>/Pa) =</td> <td>NA</td> </tr> <tr> <td>C<sub>D</sub> (-) =</td> <td>NA</td> <td>C<sub>D</sub> (-) =</td> <td>NA</td> </tr> <tr> <td>ξ (-) =</td> <td>-0.67</td> <td>ξ (-) =</td> <td>NA</td> </tr> <tr> <td>T<sub>GRF</sub> (m<sup>2</sup>/s) =</td> <td>NA</td> <td>T<sub>GRF</sub> (m<sup>2</sup>/s) =</td> <td>NA</td> </tr> <tr> <td>S<sub>GRF</sub> (-) =</td> <td>NA</td> <td>S<sub>GRF</sub> (-) =</td> <td>NA</td> </tr> <tr> <td>D<sub>GRF</sub> (-) =</td> <td>NA</td> <td>D<sub>GRF</sub> (-) =</td> <td>NA</td> </tr> </table>		Q/s (m <sup>2</sup> /s) =	2.3E-04			T <sub>M</sub> (m <sup>2</sup> /s) =	3.1E-04			Flow regime:	transient	Flow regime:	transient	dt <sub>1</sub> (min) =	#NV	dt <sub>1</sub> (min) =	#NV	dt <sub>2</sub> (min) =	#NV	dt <sub>2</sub> (min) =	#NV	T (m <sup>2</sup> /s) =	4.1E-04	T (m <sup>2</sup> /s) =	NA	S (-) =	1.0E-06	S (-) =	NA	K <sub>s</sub> (m/s) =	4.1E-06	K <sub>s</sub> (m/s) =	NA	S <sub>s</sub> (1/m) =	1.0E-08	S <sub>s</sub> (1/m) =	NA	C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	NA	C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	NA	ξ (-) =	-0.67	ξ (-) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA
		Q/s (m <sup>2</sup> /s) =	2.3E-04																																																												
T <sub>M</sub> (m <sup>2</sup> /s) =	3.1E-04																																																														
Flow regime:	transient	Flow regime:	transient																																																												
dt <sub>1</sub> (min) =	#NV	dt <sub>1</sub> (min) =	#NV																																																												
dt <sub>2</sub> (min) =	#NV	dt <sub>2</sub> (min) =	#NV																																																												
T (m <sup>2</sup> /s) =	4.1E-04	T (m <sup>2</sup> /s) =	NA																																																												
S (-) =	1.0E-06	S (-) =	NA																																																												
K <sub>s</sub> (m/s) =	4.1E-06	K <sub>s</sub> (m/s) =	NA																																																												
S <sub>s</sub> (1/m) =	1.0E-08	S <sub>s</sub> (1/m) =	NA																																																												
C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	NA																																																												
C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	NA																																																												
ξ (-) =	-0.67	ξ (-) =	NA																																																												
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA																																																												
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA																																																												
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA																																																												
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>																																																													
<p style="text-align: center;">Not analysed</p>		<table border="1"> <tr> <td>dt<sub>1</sub> (min) =</td> <td>#NV</td> <td>C (m<sup>3</sup>/Pa) =</td> <td>NA</td> </tr> <tr> <td>dt<sub>2</sub> (min) =</td> <td>#NV</td> <td>C<sub>D</sub> (-) =</td> <td>NA</td> </tr> <tr> <td>T<sub>T</sub> (m<sup>2</sup>/s) =</td> <td>4.1E-04</td> <td>ξ (-) =</td> <td>-0.67</td> </tr> <tr> <td>S (-) =</td> <td>1.0E-06</td> <td></td> <td></td> </tr> <tr> <td>K<sub>s</sub> (m/s) =</td> <td>4.1E-06</td> <td></td> <td></td> </tr> <tr> <td>S<sub>s</sub> (1/m) =</td> <td>1.0E-08</td> <td></td> <td></td> </tr> </table>		dt <sub>1</sub> (min) =	#NV	C (m <sup>3</sup> /Pa) =	NA	dt <sub>2</sub> (min) =	#NV	C <sub>D</sub> (-) =	NA	T <sub>T</sub> (m <sup>2</sup> /s) =	4.1E-04	ξ (-) =	-0.67	S (-) =	1.0E-06			K <sub>s</sub> (m/s) =	4.1E-06			S <sub>s</sub> (1/m) =	1.0E-08																																						
		dt <sub>1</sub> (min) =	#NV	C (m <sup>3</sup> /Pa) =	NA																																																										
		dt <sub>2</sub> (min) =	#NV	C <sub>D</sub> (-) =	NA																																																										
		T <sub>T</sub> (m <sup>2</sup> /s) =	4.1E-04	ξ (-) =	-0.67																																																										
		S (-) =	1.0E-06																																																												
		K <sub>s</sub> (m/s) =	4.1E-06																																																												
S <sub>s</sub> (1/m) =	1.0E-08																																																														
<b>Comments:</b>																																																															
		<p>The recommended transmissivity of 4.1E-04 m<sup>2</sup>/s was derived from the analysis of the CHi phase (inner zone). The confidence range for the interval transmissivity is estimated to be 7.0E-05 m<sup>2</sup>/s to 8.0E-04 m<sup>2</sup>/s (this range encompasses the outer zone transmissivity). The flow dimension during the test is assumed to be 2. The static pressure could not be analysed based on solely the CHi phase.</p>																																																													

<b>Test Summary Sheet</b>			
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070216 11:52
Test section from - to (m):	395.50-495.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>5000 4800 4600 4400 4200 4000 3800</p> <p>0.00 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00</p> <p>Elapsed Time [h]</p> <p>40 35 30 25 20 15 10 5 0</p> <p>Injection Rate [l/min]</p> <p>KLX13A_395.50-495.50_070216_1_CHir_Q_r</p> <p>• P section • P above • P below • Q</p>		<p><b>Indata</b></p> <p>p<sub>0</sub> (kPa) = 4834</p> <p>p<sub>i</sub> (kPa) = 4834</p> <p>p<sub>p</sub> (kPa) = 4875</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 4.05E-04</p> <p>tp (s) = 1800</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub>(gr C) = 14.4</p> <p>Derivative fact. = 0.02</p>	<p><b>Indata</b></p> <p>p<sub>F</sub> (kPa) = 4838</p> <p>t<sub>F</sub> (s) = 1800</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.08</p>
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<b>Results</b>	
		<p>Q/s (m<sup>2</sup>/s) = 9.7E-05</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 1.3E-04</p> <p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 5.61</p> <p>dt<sub>2</sub> (min) = 25.90</p> <p>T (m<sup>2</sup>/s) = 9.2E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 9.2E-07</p> <p>S<sub>s</sub> (1/m) = 1.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = -3.86</p> <p>T<sub>GRF</sub>(m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub>(-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Results</b>	
		<b>Results</b>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.67</p> <p>dt<sub>2</sub> (min) = 23.99</p> <p>T (m<sup>2</sup>/s) = 2.8E-04</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 2.8E-06</p> <p>S<sub>s</sub> (1/m) = 1.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 2.0E-08</p> <p>C<sub>D</sub> (-) = 2.2E+00</p> <p>ξ (-) = 4.57</p> <p>T<sub>GRF</sub>(m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub>(-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>	
		<p>dt<sub>1</sub> (min) = 5.61</p> <p>dt<sub>2</sub> (min) = 25.90</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 9.2E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 9.2E-07</p> <p>S<sub>s</sub> (1/m) = 1.0E-08</p>	
		<p>C (m<sup>3</sup>/Pa) = 2.0E-08</p> <p>C<sub>D</sub> (-) = 2.2E+00</p> <p>ξ (-) = -3.86</p>	
<b>Comments:</b>			
<p>The recommended transmissivity of 9.2E-5 m<sup>2</sup>/s was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. Due to the hydraulic connection to the bottom zone, the derived transmissivity should be regarded to be at the upper limit of the confidence range. The confidence range for the interval transmissivity is estimated to be 1.0E-5 m<sup>2</sup>/s to 2.0E-4 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,837.2 kPa.</p>			

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070216 15:44		
Test section from - to (m):	482.50-582.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	5687	p <sub>F</sub> (kPa) =	5687
		p <sub>i</sub> (kPa) =	5686	t <sub>F</sub> (s) =	1800
		p <sub>p</sub> (kPa) =	5884	S <sub>el</sub> S <sub>’</sub> (-) =	1.00E-06
		Q <sub>p</sub> (m <sup>3</sup> /s) =	1.05E-04	EC <sub>w</sub> (mS/m) =	
		t <sub>p</sub> (s) =	1800	Temp <sub>w</sub> (gr C) =	15.8
		S <sub>el</sub> S <sub>’</sub> (-) =	1.00E-06	Derivative fact. =	0.09
		Derivative fact. =	0.06		
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>			
		Q/s (m <sup>2</sup> /s) =	5.2E-06		
		T <sub>M</sub> (m <sup>2</sup> /s) =	6.8E-06		
		Flow regime:	transient	Flow regime:	transient
		dt <sub>1</sub> (min) =	0.28	dt <sub>1</sub> (min) =	0.62
		dt <sub>2</sub> (min) =	3.06	dt <sub>2</sub> (min) =	23.93
		T (m <sup>2</sup> /s) =	5.7E-06	T (m <sup>2</sup> /s) =	2.1E-05
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	5.7E-08	K <sub>s</sub> (m/s) =	2.1E-07
		S <sub>s</sub> (1/m) =	1.0E-08	S <sub>s</sub> (1/m) =	1.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	1.1E-09
C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	1.2E-01		
ξ (-) =	0.43	ξ (-) =	13.70		
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	0.28		
		dt <sub>2</sub> (min) =	3.06		
		T <sub>T</sub> (m <sup>2</sup> /s) =	5.7E-06		
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	5.7E-08		
		S <sub>s</sub> (1/m) =	1.0E-08		
<b>Comments:</b>		C (m <sup>3</sup> /Pa) =	1.1E-09		
<p>The recommended transmissivity of 5.7E-6 m<sup>2</sup>/s was derived from the analysis of the CHi phase (inner zone), which shows a good derivative stabilisation. The confidence range for the interval transmissivity is estimated to be 1.0E-6 m<sup>2</sup>/s to 7.0E-6 m<sup>2</sup>/s due to the hydraulic connection. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,684.4 kPa.</p>		C <sub>D</sub> (-) =	1.2E-01		
		ξ (-) =	0.43		

<b>Test Summary Sheet</b>			
Project:	Oskarshamn site investigation	<a href="#">Test type: f11</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070217 18:25
Test section from - to (m):	102.50-122.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>p<sub>0</sub> (kPa) = 1194</p> <p>p<sub>i</sub> (kPa) = 1197</p> <p>p<sub>p</sub> (kPa) = 1396</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 5.67E-05</p> <p>tp (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 9.1</p> <p>Derivative fact. = 0.08</p>		<p>p<sub>F</sub> (kPa) = 1201</p> <p>t<sub>F</sub> (s) = 3600</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.02</p>	
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<p>Q/s (m<sup>2</sup>/s) = 2.8E-06</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 2.9E-06</p>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.37</p> <p>dt<sub>2</sub> (min) = 1.05</p> <p>T (m<sup>2</sup>/s) = 2.5E-06</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 1.3E-07</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = -1.53</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Results</b>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.22</p> <p>dt<sub>2</sub> (min) = 1.84</p> <p>T (m<sup>2</sup>/s) = 2.3E-06</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 1.2E-07</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 2.3E-10</p> <p>C<sub>D</sub> (-) = 2.6E-02</p> <p>ξ (-) = -2.22</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
		<p><b>Selected representative parameters.</b></p> <p>C (m<sup>3</sup>/Pa) = 2.3E-10</p> <p>C<sub>D</sub> (-) = 2.6E-02</p> <p>ξ (-) = -2.22</p>	
		<p><b>Comments:</b></p> <p>The recommended transmissivity of 2.3E-06 m<sup>2</sup>/s was derived from the analysis of the CHir phase (inner zone), which shows the best horizontal stabilisation of the derivative and best data and derivative quality. The confidence range for the interval transmissivity is estimated to be 1.0E-06 m<sup>2</sup>/s to 7.0E-06 m<sup>2</sup>/s. The analysis was conducted using a flow dimension of 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 1,198.9 kPa.</p>	



<b>Test Summary Sheet</b>			
Project:	Oskarshamn site investigation	<a href="#">Test type: f1</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070218 08:25
Test section from - to (m):	122.50-142.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>KLX13A_122.50-142.50_070218_1_CHir_Q_r</p> <p>Legend: • P section, • P above, • P below, • Q</p>		<p>p<sub>0</sub> (kPa) = 1387</p> <p>p<sub>i</sub> (kPa) = 1401</p> <p>p<sub>p</sub> (kPa) = 1627</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 1.67E-08</p> <p>tp (s) = 600</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 8.3</p> <p>Derivative fact. = 0.07</p>	<p>Indata</p> <p>p<sub>F</sub> (kPa) = 1435</p> <p>t<sub>F</sub> (s) = 2400</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.02</p>
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<p>Q/s (m<sup>2</sup>/s) = 7.2E-10</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 7.6E-10</p> <p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = #NV</p> <p>dt<sub>2</sub> (min) = #NV</p> <p>T (m<sup>2</sup>/s) = 1.3E-10</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 6.5E-12</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = -1.13</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	<p>Results</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 7.6E-10</p> <p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = #NV</p> <p>dt<sub>2</sub> (min) = #NV</p> <p>T (m<sup>2</sup>/s) = 1.0E-10</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 5.0E-12</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 3.3E-11</p> <p>C<sub>D</sub> (-) = 3.6E-03</p> <p>ξ (-) = -1.23</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>
		<b>Log-Log plot incl. derivatives- recovery period</b>	
		<p>dt<sub>1</sub> (min) = #NV</p> <p>dt<sub>2</sub> (min) = #NV</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 1.0E-10</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 5.0E-12</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p>	<p>C (m<sup>3</sup>/Pa) = 3.3E-11</p> <p>C<sub>D</sub> (-) = 3.6E-03</p> <p>ξ (-) = -1.23</p>
		<b>Comments:</b>	
		<p>The recommended transmissivity of 1.0E-10 m<sup>2</sup>/s was derived from the analysis of the CHir phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be 7.0E-11 m<sup>2</sup>/s to 4.0E-10 m<sup>2</sup>/s. The analysis was conducted using a flow dimension of 2 (radial flow). Due to the low transmissivity no fresh water head was calculated.</p>	

Test Summary Sheet					
Project:	Oskarshamn site investigation	<a href="#">Test type:</a> f1	Pi		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070218 11:07		
Test section from - to (m):	142.50-162.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
Linear plot Q and p		Flow period		Recovery period	
		<b>Indata</b> p <sub>0</sub> (kPa) = 1581 p <sub>i</sub> (kPa) = 1599 p <sub>p</sub> (kPa) = 1833 Q <sub>p</sub> (m <sup>3</sup> /s) = #NV t <sub>p</sub> (s) = 10 S el S' (-) = 1.00E-06 EC <sub>w</sub> (mS/m) = Temp <sub>w</sub> (gr C) = 8.5 Derivative fact. = 		<b>Indata</b> p <sub>F</sub> (kPa) = 1674 t <sub>F</sub> (s) = 3600 S el S' (-) = 1.00E-06 Derivative fact. = 0.05 	
		<b>Results</b> Q/s (m <sup>2</sup> /s) = #NV T <sub>M</sub> (m <sup>2</sup> /s) = #NV Flow regime: transient dt <sub>1</sub> (min) = #NV dt <sub>2</sub> (min) = #NV T (m <sup>2</sup> /s) = NA S (-) = NA K <sub>s</sub> (m/s) = NA S <sub>s</sub> (1/m) = NA C (m <sup>3</sup> /Pa) = NA C <sub>D</sub> (-) = NA ξ (-) = NA T <sub>GRF</sub> (m <sup>2</sup> /s) = NA S <sub>GRF</sub> (-) = NA D <sub>GRF</sub> (-) = NA 		<b>Results</b> T (m <sup>2</sup> /s) = 2.9E-11 S (-) = 1.0E-06 K <sub>s</sub> (m/s) = 1.5E-12 S <sub>s</sub> (1/m) = 5.0E-08 C (m <sup>3</sup> /Pa) = 2.4E-11 C <sub>D</sub> (-) = 2.6E-03 ξ (-) = -0.28 T <sub>GRF</sub> (m <sup>2</sup> /s) = NA S <sub>GRF</sub> (-) = NA D <sub>GRF</sub> (-) = NA 	
Log-Log plot incl. derivatives- flow period		Selected representative parameters.			
		dt <sub>1</sub> (min) = #NV		C (m <sup>3</sup> /Pa) = 2.4E-11	
		dt <sub>2</sub> (min) = #NV		C <sub>D</sub> (-) = 2.6E-03	
		T <sub>T</sub> (m <sup>2</sup> /s) = 2.9E-11		ξ (-) = -0.28	
		S (-) = 1.0E-06			
		K <sub>s</sub> (m/s) = 5.8E-12			
		S <sub>s</sub> (1/m) = 5.0E-08			
		<b>Comments:</b>			
		The recommended transmissivity of 2.9E-11 m <sup>2</sup> /s was derived from the analysis of the Pi phase. The confidence range for the interval transmissivity is estimated to be 9.0E-12 to 7.0E-11 m <sup>2</sup> /s. The analysis was conducted using a flow dimension of 2. The static pressure could not be extrapolated due to the very low transmissivity.			

Test Summary Sheet			
Project:	Oskarshamn site investigation	Test type: f1	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070218 13:24
Test section from - to (m):	162.50-182.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>2100 2000 1900 1800 1700 1600 1500</p> <p>KLX13A_162.50-182.50_070218_1_CHir_Q_r</p> <p>0.00 0.20 0.40 0.60 0.80 1.00 1.20 1.40</p> <p>Elapsed Time [h]</p>		<p><b>Indata</b></p> <p>p<sub>0</sub> (kPa) = 1776</p> <p>p<sub>i</sub> (kPa) = 1782</p> <p>p<sub>p</sub> (kPa) = 1981</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 2.18E-06</p> <p>tp (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 8.8</p> <p>Derivative fact. = 0.02</p>	
		<p>p<sub>F</sub> (kPa) = 1783</p> <p>t<sub>F</sub> (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.03</p>	
		<p><b>Results</b></p> <p>Q/s (m<sup>2</sup>/s) = 1.1E-07</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 1.1E-07</p>	
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<p><b>Results</b></p> <p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 1.52</p> <p>dt<sub>2</sub> (min) = 16.68</p> <p>T (m<sup>2</sup>/s) = 1.9E-07</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 9.5E-09</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = 4.20</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = #NV</p> <p>dt<sub>2</sub> (min) = #NV</p> <p>T (m<sup>2</sup>/s) = 1.1E-07</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 5.5E-09</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 6.3E-11</p> <p>C<sub>D</sub> (-) = 6.9E-03</p> <p>ξ (-) = 1.35</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>	
		<p>dt<sub>1</sub> (min) = 1.52</p> <p>dt<sub>2</sub> (min) = 16.68</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 1.9E-07</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 9.5E-09</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p>	
		<p>C (m<sup>3</sup>/Pa) = 6.3E-11</p> <p>C<sub>D</sub> (-) = 6.9E-03</p> <p>ξ (-) = 4.20</p>	
		<p><b>Comments:</b></p> <p>The recommended transmissivity of 1.9E-7 m<sup>2</sup>/s was derived from the analysis of the CHi phase, which shows the clearest horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be 9.0E-8 m<sup>2</sup>/s to 6.0E-7 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 1,782.2 kPa.</p>	

Test Summary Sheet					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070218 16:10		
Test section from - to (m):	182.50-202.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>			
		p <sub>0</sub> (kPa) =	1971		
		p <sub>i</sub> (kPa) =	1973		
		p <sub>p</sub> (kPa) =	2172	p <sub>F</sub> (kPa) =	1971
		Q <sub>p</sub> (m <sup>3</sup> /s) =	5.18E-06		
		tp (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	9		
Derivative fact. =	0.05	Derivative fact. =	0.05		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	2.6E-07				
T <sub>M</sub> (m <sup>2</sup> /s) =	2.7E-07				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		Flow regime:	transient		
		dt <sub>1</sub> (min) =	0.22	dt <sub>1</sub> (min) =	0.31
		dt <sub>2</sub> (min) =	15.47	dt <sub>2</sub> (min) =	1.23
		T (m <sup>2</sup> /s) =	3.2E-07	T (m <sup>2</sup> /s) =	2.5E-07
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	1.6E-08	K <sub>s</sub> (m/s) =	1.3E-08
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	5.6E-11
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	6.2E-03
		ξ (-) =	1.34	ξ (-) =	0.25
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	0.31	C (m <sup>3</sup> /Pa) =	5.6E-11
		dt <sub>2</sub> (min) =	1.23	C <sub>D</sub> (-) =	6.2E-03
		T <sub>T</sub> (m <sup>2</sup> /s) =	2.5E-07	ξ (-) =	0.25
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	1.3E-08		
		S <sub>s</sub> (1/m) =	5.0E-08		
<b>Comments:</b>		<p>The recommended transmissivity of 2.5E-7 m<sup>2</sup>/s was derived from the analysis of the CHir phase (inner zone), which shows the best data and derivative quality. The confidence range for the interval transmissivity is estimated to be 1.0E-7 m<sup>2</sup>/s to 8.0E-7 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 1,965.1 kPa.</p>			

Test Summary Sheet			
Project:	Oskarshamn site investigation	<a href="#">Test type: f1</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070218 18:12
Test section from - to (m):	202.50-222.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>p<sub>0</sub> (kPa) = 2166</p> <p>p<sub>i</sub> (kPa) = 2168</p> <p>p<sub>p</sub> (kPa) = 2382</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 8.00E-06</p> <p>tp (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 9.3</p> <p>Derivative fact. = 0.07</p>		<p>p<sub>F</sub> (kPa) = 2168</p> <p>t<sub>F</sub> (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.04</p>	
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<p>Q/s (m<sup>3</sup>/s) = 3.7E-07</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 3.8E-07</p>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.19</p> <p>dt<sub>2</sub> (min) = 13.32</p> <p>T (m<sup>2</sup>/s) = 6.4E-07</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 3.2E-08</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = 3.64</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Results</b>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.64</p> <p>dt<sub>2</sub> (min) = 10.52</p> <p>T (m<sup>2</sup>/s) = 2.4E-06</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 1.2E-07</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 6.7E-11</p> <p>C<sub>D</sub> (-) = 7.4E-03</p> <p>ξ (-) = 32.40</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
		<p><b>Selected representative parameters.</b></p> <p>dt<sub>1</sub> (min) = 0.19</p> <p>dt<sub>2</sub> (min) = 13.32</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 6.4E-07</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 3.2E-08</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = #NV</p> <p>C<sub>D</sub> (-) = #NV</p> <p>ξ (-) = 3.64</p>	
<b>Comments:</b>			
<p>The recommended transmissivity of 6.4E-7 m<sup>2</sup>/s was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be 4.0E-7 m<sup>2</sup>/s to 3.0E-6 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,166.3 kPa.</p>			

Test Summary Sheet																																																																																																												
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir																																																																																																									
Area:	Laxemar	Test no:	1																																																																																																									
Borehole ID:	KLX13A	Test start:	070219 09:02																																																																																																									
Test section from - to (m):	222.50-242.50 m	Responsible for test execution:	Stephan Rohs																																																																																																									
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu																																																																																																									
Linear plot Q and p		Flow period																																																																																																										
	<table border="1"> <thead> <tr> <th colspan="2">Indata</th> <th colspan="2">Indata</th> </tr> </thead> <tbody> <tr> <td>p<sub>0</sub> (kPa) =</td> <td>2362</td> <td></td> <td></td> </tr> <tr> <td>p<sub>i</sub> (kPa) =</td> <td>2367</td> <td></td> <td></td> </tr> <tr> <td>p<sub>p</sub> (kPa) =</td> <td>2567</td> <td>p<sub>F</sub> (kPa) =</td> <td>2377</td> </tr> <tr> <td>Q<sub>p</sub> (m<sup>3</sup>/s) =</td> <td>1.72E-05</td> <td></td> <td></td> </tr> <tr> <td>tp (s) =</td> <td>1200</td> <td>t<sub>F</sub> (s) =</td> <td>1200</td> </tr> <tr> <td>S el S' (-) =</td> <td>1.00E-06</td> <td>S el S' (-) =</td> <td>1.00E-06</td> </tr> <tr> <td>EC<sub>w</sub> (mS/m) =</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Temp<sub>w</sub> (gr C) =</td> <td>9.6</td> <td></td> <td></td> </tr> <tr> <td>Derivative fact. =</td> <td>0.05</td> <td>Derivative fact. =</td> <td>0.04</td> </tr> </tbody> </table>		Indata		Indata		p <sub>0</sub> (kPa) =	2362			p <sub>i</sub> (kPa) =	2367			p <sub>p</sub> (kPa) =	2567	p <sub>F</sub> (kPa) =	2377	Q <sub>p</sub> (m <sup>3</sup> /s) =	1.72E-05			tp (s) =	1200	t <sub>F</sub> (s) =	1200	S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06	EC <sub>w</sub> (mS/m) =				Temp <sub>w</sub> (gr C) =	9.6			Derivative fact. =	0.05	Derivative fact. =	0.04	<table border="1"> <thead> <tr> <th colspan="2">Results</th> <th colspan="2">Results</th> </tr> </thead> <tbody> <tr> <td>Q/s (m<sup>2</sup>/s) =</td> <td>8.4E-07</td> <td></td> <td></td> </tr> <tr> <td>T<sub>M</sub> (m<sup>2</sup>/s) =</td> <td>8.8E-07</td> <td></td> <td></td> </tr> <tr> <td>Flow regime:</td> <td>transient</td> <td>Flow regime:</td> <td>transient</td> </tr> <tr> <td>dt<sub>1</sub> (min) =</td> <td>4.82</td> <td>dt<sub>1</sub> (min) =</td> <td>7.17</td> </tr> <tr> <td>dt<sub>2</sub> (min) =</td> <td>18.25</td> <td>dt<sub>2</sub> (min) =</td> <td>16.30</td> </tr> <tr> <td>T (m<sup>2</sup>/s) =</td> <td>5.7E-07</td> <td>T (m<sup>2</sup>/s) =</td> <td>6.3E-07</td> </tr> <tr> <td>S (-) =</td> <td>1.0E-06</td> <td>S (-) =</td> <td>1.0E-06</td> </tr> <tr> <td>K<sub>s</sub> (m/s) =</td> <td>2.9E-08</td> <td>K<sub>s</sub> (m/s) =</td> <td>5.0E-08</td> </tr> <tr> <td>S<sub>s</sub> (1/m) =</td> <td>5.0E-08</td> <td>S<sub>s</sub> (1/m) =</td> <td>5.0E-08</td> </tr> <tr> <td>C (m<sup>3</sup>/Pa) =</td> <td>NA</td> <td>C (m<sup>3</sup>/Pa) =</td> <td>1.5E-10</td> </tr> <tr> <td>C<sub>D</sub> (-) =</td> <td>NA</td> <td>C<sub>D</sub> (-) =</td> <td>1.7E-02</td> </tr> <tr> <td>ξ (-) =</td> <td>0.15</td> <td>ξ (-) =</td> <td>4.36</td> </tr> <tr> <td>T<sub>GRF</sub> (m<sup>2</sup>/s) =</td> <td>NA</td> <td>T<sub>GRF</sub> (m<sup>2</sup>/s) =</td> <td>NA</td> </tr> <tr> <td>S<sub>GRF</sub> (-) =</td> <td>NA</td> <td>S<sub>GRF</sub> (-) =</td> <td>NA</td> </tr> <tr> <td>D<sub>GRF</sub> (-) =</td> <td>NA</td> <td>D<sub>GRF</sub> (-) =</td> <td>NA</td> </tr> </tbody> </table>		Results		Results		Q/s (m <sup>2</sup> /s) =	8.4E-07			T <sub>M</sub> (m <sup>2</sup> /s) =	8.8E-07			Flow regime:	transient	Flow regime:	transient	dt <sub>1</sub> (min) =	4.82	dt <sub>1</sub> (min) =	7.17	dt <sub>2</sub> (min) =	18.25	dt <sub>2</sub> (min) =	16.30	T (m <sup>2</sup> /s) =	5.7E-07	T (m <sup>2</sup> /s) =	6.3E-07	S (-) =	1.0E-06	S (-) =	1.0E-06	K <sub>s</sub> (m/s) =	2.9E-08	K <sub>s</sub> (m/s) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08	C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	1.5E-10	C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	1.7E-02	ξ (-) =	0.15	ξ (-) =	4.36	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA
	Indata		Indata																																																																																																									
	p <sub>0</sub> (kPa) =	2362																																																																																																										
	p <sub>i</sub> (kPa) =	2367																																																																																																										
	p <sub>p</sub> (kPa) =	2567	p <sub>F</sub> (kPa) =	2377																																																																																																								
	Q <sub>p</sub> (m <sup>3</sup> /s) =	1.72E-05																																																																																																										
	tp (s) =	1200	t <sub>F</sub> (s) =	1200																																																																																																								
	S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06																																																																																																								
	EC <sub>w</sub> (mS/m) =																																																																																																											
	Temp <sub>w</sub> (gr C) =	9.6																																																																																																										
Derivative fact. =	0.05	Derivative fact. =	0.04																																																																																																									
Results		Results																																																																																																										
Q/s (m <sup>2</sup> /s) =	8.4E-07																																																																																																											
T <sub>M</sub> (m <sup>2</sup> /s) =	8.8E-07																																																																																																											
Flow regime:	transient	Flow regime:	transient																																																																																																									
dt <sub>1</sub> (min) =	4.82	dt <sub>1</sub> (min) =	7.17																																																																																																									
dt <sub>2</sub> (min) =	18.25	dt <sub>2</sub> (min) =	16.30																																																																																																									
T (m <sup>2</sup> /s) =	5.7E-07	T (m <sup>2</sup> /s) =	6.3E-07																																																																																																									
S (-) =	1.0E-06	S (-) =	1.0E-06																																																																																																									
K <sub>s</sub> (m/s) =	2.9E-08	K <sub>s</sub> (m/s) =	5.0E-08																																																																																																									
S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08																																																																																																									
C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	1.5E-10																																																																																																									
C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	1.7E-02																																																																																																									
ξ (-) =	0.15	ξ (-) =	4.36																																																																																																									
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA																																																																																																									
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA																																																																																																									
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA																																																																																																									
Log-Log plot incl. derivatives- flow period		Recovery period																																																																																																										
	<table border="1"> <thead> <tr> <th colspan="4">Selected representative parameters.</th> </tr> </thead> <tbody> <tr> <td>dt<sub>1</sub> (min) =</td> <td>4.82</td> <td>C (m<sup>3</sup>/Pa) =</td> <td>1.5E-10</td> </tr> <tr> <td>dt<sub>2</sub> (min) =</td> <td>18.25</td> <td>C<sub>D</sub> (-) =</td> <td>1.7E-02</td> </tr> <tr> <td>T<sub>T</sub> (m<sup>2</sup>/s) =</td> <td>5.7E-07</td> <td>ξ (-) =</td> <td>0.15</td> </tr> <tr> <td>S (-) =</td> <td>1.0E-06</td> <td></td> <td></td> </tr> <tr> <td>K<sub>s</sub> (m/s) =</td> <td>2.9E-08</td> <td></td> <td></td> </tr> <tr> <td>S<sub>s</sub> (1/m) =</td> <td>5.0E-08</td> <td></td> <td></td> </tr> </tbody> </table>		Selected representative parameters.				dt <sub>1</sub> (min) =	4.82	C (m <sup>3</sup> /Pa) =	1.5E-10	dt <sub>2</sub> (min) =	18.25	C <sub>D</sub> (-) =	1.7E-02	T <sub>T</sub> (m <sup>2</sup> /s) =	5.7E-07	ξ (-) =	0.15	S (-) =	1.0E-06			K <sub>s</sub> (m/s) =	2.9E-08			S <sub>s</sub> (1/m) =	5.0E-08			<p><b>Comments:</b></p> <p>The recommended transmissivity of 5.7E-7 m<sup>2</sup>/s was derived from the analysis of the CHi phase (outer zone), which shows the best horizontal stabilisation of the derivative and best data and derivative quality. The confidence range for the interval transmissivity is estimated to be 2.0E-7 m<sup>2</sup>/s to 1.0E-06 m<sup>2</sup>/s. The analysis displayed during the test a flow dimension of 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,360.1 kPa.</p>																																																																													
	Selected representative parameters.																																																																																																											
	dt <sub>1</sub> (min) =	4.82	C (m <sup>3</sup> /Pa) =	1.5E-10																																																																																																								
	dt <sub>2</sub> (min) =	18.25	C <sub>D</sub> (-) =	1.7E-02																																																																																																								
	T <sub>T</sub> (m <sup>2</sup> /s) =	5.7E-07	ξ (-) =	0.15																																																																																																								
	S (-) =	1.0E-06																																																																																																										
	K <sub>s</sub> (m/s) =	2.9E-08																																																																																																										
	S <sub>s</sub> (1/m) =	5.0E-08																																																																																																										
	Log-Log plot incl. derivatives- recovery period																																																																																																											

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070219 11:04		
Test section from - to (m):	242.50-262.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Indata</b>			
		p <sub>0</sub> (kPa) = 2556			
		p <sub>i</sub> (kPa) = 2565			
		p <sub>p</sub> (kPa) = 2764			
		Q <sub>p</sub> (m <sup>3</sup> /s) = 3.67E-07			
		t <sub>p</sub> (s) = 1200			
		S e l S' (-) = 1.00E-06			
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) = 10			
		Derivative fact. = 0.02			
<b>Recovery period</b>		<b>Indata</b>			
		p <sub>F</sub> (kPa) = 2565			
		t <sub>F</sub> (s) = 2400			
		S e l S' (-) = 1.00E-06			
		Derivative fact. = 0.02			
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>			
		Q/s (m <sup>2</sup> /s) = 1.8E-08			
		T <sub>M</sub> (m <sup>2</sup> /s) = 1.9E-08			
		Flow regime: transient		Flow regime: transient	
		dt <sub>1</sub> (min) = 2.68		dt <sub>1</sub> (min) = 7.97	
		dt <sub>2</sub> (min) = 15.86		dt <sub>2</sub> (min) = 36.71	
		T (m <sup>2</sup> /s) = 2.5E-08		T (m <sup>2</sup> /s) = 8.7E-08	
		S (-) = 1.0E-06		S (-) = 1.0E-06	
		K <sub>s</sub> (m/s) = 1.3E-09		K <sub>s</sub> (m/s) = 4.4E-09	
		S <sub>s</sub> (1/m) = 5.0E-08		S <sub>s</sub> (1/m) = 5.0E-08	
		C (m <sup>3</sup> /Pa) = NA		C (m <sup>3</sup> /Pa) = 1.0E-10	
C <sub>D</sub> (-) = NA		C <sub>D</sub> (-) = 1.1E-02			
ξ (-) = 2.75		ξ (-) = 20.70			
T <sub>GRF</sub> (m <sup>2</sup> /s) = NA		T <sub>GRF</sub> (m <sup>2</sup> /s) = NA			
S <sub>GRF</sub> (-) = NA		S <sub>GRF</sub> (-) = NA			
D <sub>GRF</sub> (-) = NA		D <sub>GRF</sub> (-) = NA			
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) = 2.68			
		dt <sub>2</sub> (min) = 15.86			
		T <sub>T</sub> (m <sup>2</sup> /s) = 2.5E-08			
		S (-) = 1.0E-06			
		K <sub>s</sub> (m/s) = 1.3E-09			
		S <sub>s</sub> (1/m) = 5.0E-08			
C (m <sup>3</sup> /Pa) = 1.0E-10					
C <sub>D</sub> (-) = 1.1E-02					
ξ (-) = 2.75					
<b>Comments:</b>					
The recommended transmissivity of 2.5E-08 m <sup>2</sup> /s was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be 1.0E-08 m <sup>2</sup> /s to 9.0E-08 m <sup>2</sup> /s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,563.2 kPa.					

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070219 14:13		
Test section from - to (m):	262.50-282.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	2751		
		p <sub>i</sub> (kPa) =	2751		
		p <sub>p</sub> (kPa) =	2963	p <sub>F</sub> (kPa) =	2752
		Q <sub>p</sub> (m <sup>3</sup> /s) =	1.37E-06		
		t <sub>p</sub> (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	10.3		
Derivative fact. =	0.02	Derivative fact. =	0.02		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	6.3E-08				
T <sub>M</sub> (m <sup>2</sup> /s) =	6.6E-08				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		Flow regime:	transient		
		dt <sub>1</sub> (min) =	2.70	dt <sub>1</sub> (min) =	4.65
		dt <sub>2</sub> (min) =	17.74	dt <sub>2</sub> (min) =	17.08
		T (m <sup>2</sup> /s) =	1.2E-07	T (m <sup>2</sup> /s) =	7.5E-08
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	6.0E-09	K <sub>s</sub> (m/s) =	3.8E-09
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	2.4E-11
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	2.6E-03
		ξ (-) =	-2.23	ξ (-) =	5.84
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	2.70	C (m <sup>3</sup> /Pa) =	2.4E-11
		dt <sub>2</sub> (min) =	17.74	C <sub>D</sub> (-) =	2.6E-03
		T <sub>T</sub> (m <sup>2</sup> /s) =	1.2E-07	ξ (-) =	-2.23
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	6.0E-09		
		S <sub>s</sub> (1/m) =	5.0E-08		
<b>Comments:</b>		<p>The recommended transmissivity of 1.2E-07 m<sup>2</sup>/s was derived from the analysis of the CHi phase, which is very noisy but shows a horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be 3.0E-08 m<sup>2</sup>/s to 3.0E-07 m<sup>2</sup>/s. The analysis was conducted using a flow dimension of 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,743.6 kPa.</p>			



<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070219 16:17		
Test section from - to (m):	282.50-302.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Indata</b>			
		p <sub>0</sub> (kPa) = 2949		Indata	
		p <sub>i</sub> (kPa) = 2943			
		p <sub>p</sub> (kPa) = 3143		p <sub>F</sub> (kPa) = 2943	
		Q <sub>p</sub> (m <sup>3</sup> /s) = 1.80E-05			
		t <sub>p</sub> (s) = 1200		t <sub>F</sub> (s) = 1200	
		S <sub>el</sub> S' (-) = 1.00E-06		S <sub>el</sub> S' (-) = 1.00E-06	
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) = 10.6			
		Derivative fact. = 0.02		Derivative fact. = 0.04	
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) = 8.8E-07					
T <sub>M</sub> (m <sup>2</sup> /s) = 9.2E-07					
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		Flow regime: transient			
		dt <sub>1</sub> (min) = 0.47		dt <sub>1</sub> (min) = 0.53	
		dt <sub>2</sub> (min) = 17.90		dt <sub>2</sub> (min) = 13.15	
		T (m <sup>2</sup> /s) = 1.4E-06		T (m <sup>2</sup> /s) = 2.0E-06	
		S (-) = 1.0E-06		S (-) = 1.0E-06	
		K <sub>s</sub> (m/s) = 7.0E-08		K <sub>s</sub> (m/s) = 1.0E-07	
		S <sub>s</sub> (1/m) = 5.0E-08		S <sub>s</sub> (1/m) = 5.0E-08	
		C (m <sup>3</sup> /Pa) = NA		C (m <sup>3</sup> /Pa) = 2.0E-10	
		C <sub>D</sub> (-) = NA		C <sub>D</sub> (-) = 2.2E-02	
		ξ (-) = 3.04		ξ (-) = 6.87	
T <sub>GRF</sub> (m <sup>2</sup> /s) = NA		T <sub>GRF</sub> (m <sup>2</sup> /s) = NA			
S <sub>GRF</sub> (-) = NA		S <sub>GRF</sub> (-) = NA			
D <sub>GRF</sub> (-) = NA		D <sub>GRF</sub> (-) = NA			
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) = 0.53			
		dt <sub>2</sub> (min) = 13.15		C (m <sup>3</sup> /Pa) = 2.0E-10	
		T <sub>T</sub> (m <sup>2</sup> /s) = 2.0E-06		C <sub>D</sub> (-) = 2.2E-02	
		S (-) = 1.0E-06		ξ (-) = 6.87	
		K <sub>s</sub> (m/s) = 1.0E-07			
		S <sub>s</sub> (1/m) = 5.0E-08			
<b>Comments:</b>					
The recommended transmissivity of 2.0E-06 m <sup>2</sup> /s was derived from the analysis of the CHir phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be 9.0E-07 m <sup>2</sup> /s to 5.0E-06 m <sup>2</sup> /s. The flow dimension during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 2,939.1 kPa.					

Test Summary Sheet					
Project:	Oskarshamn site investigation	<a href="#">Test type: f11</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070219 18:12		
Test section from - to (m):	302.50-322.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	3141		
		p <sub>i</sub> (kPa) =	3138		
		p <sub>p</sub> (kPa) =	3336	p <sub>F</sub> (kPa) =	3138
		Q <sub>p</sub> (m <sup>3</sup> /s) =	8.00E-05		
		tp (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	10.9		
Derivative fact. =	0.04	Derivative fact. =	0.03		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	4.0E-06				
T <sub>M</sub> (m <sup>2</sup> /s) =	4.1E-06				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		Flow regime:	transient		
		dt <sub>1</sub> (min) =	0.55	dt <sub>1</sub> (min) =	0.34
		dt <sub>2</sub> (min) =	4.37	dt <sub>2</sub> (min) =	7.99
		T (m <sup>2</sup> /s) =	6.8E-06	T (m <sup>2</sup> /s) =	2.1E-05
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	3.4E-07	K <sub>s</sub> (m/s) =	1.1E-06
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	2.1E-10
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	2.3E-02
		ξ (-) =	1.26	ξ (-) =	20.30
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	0.34	C (m <sup>3</sup> /Pa) =	2.1E-10
		dt <sub>2</sub> (min) =	7.99	C <sub>D</sub> (-) =	2.3E-02
		T <sub>T</sub> (m <sup>2</sup> /s) =	2.1E-05	ξ (-) =	20.30
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	1.1E-06		
		S <sub>s</sub> (1/m) =	5.0E-08		
<b>Comments:</b>		<p>The recommended transmissivity of 2.1E-05 m<sup>2</sup>/s was derived from the analysis of the CHir phase, which shows the better derivative quality. The confidence range for the interval transmissivity is estimated to be 1.0E-06 m<sup>2</sup>/s to 4.0E-05 m<sup>2</sup>/s. The flow dimension displayed during the test is 2. The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 3,137.7 kPa.</p>			

<b>Test Summary Sheet</b>			
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070220 08:18
Test section from - to (m):	322.50-342.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>3700 3600 3500 3400 3300 3200 3100</p> <p>Downhole Pressure [kPa]</p> <p>0.15 0.10 0.05 0.00</p> <p>Injection Rate [l/min]</p> <p>0.00 0.20 0.40 0.60 0.80 1.00 1.20 1.40</p> <p>Elapsed Time [h]</p> <p>KLX13A_322.50-342.50_070220_1_CHir_Q_r</p> <p>• P section • P above • P below • Q</p>		<p><b>Indata</b></p> <p>p<sub>0</sub> (kPa) = 3338</p> <p>p<sub>i</sub> (kPa) = 3336</p> <p>p<sub>p</sub> (kPa) = 3534</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 1.60E-06</p> <p>tp (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 11.1</p> <p>Derivative fact. = 0.05</p>	<p><b>Indata</b></p> <p>p<sub>F</sub> (kPa) = 3335</p> <p>t<sub>F</sub> (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.02</p>
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<p><b>Results</b></p> <p>Q/s (m<sup>2</sup>/s) = 7.9E-08</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 8.3E-08</p> <p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 1.30</p> <p>dt<sub>2</sub> (min) = 16.65</p> <p>T (m<sup>2</sup>/s) = 1.6E-07</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 7.9E-09</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = 6.70</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	<p><b>Results</b></p> <p>Q/s (m<sup>2</sup>/s) =</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) =</p> <p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = #NV</p> <p>dt<sub>2</sub> (min) = #NV</p> <p>T (m<sup>2</sup>/s) = 5.9E-08</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 3.0E-09</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 8.3E-11</p> <p>C<sub>D</sub> (-) = 9.2E-03</p> <p>ξ (-) = 0.05</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>
		<b>Log-Log plot incl. derivatives- recovery period</b>	
		<p>dt<sub>1</sub> (min) = 1.30</p> <p>dt<sub>2</sub> (min) = 16.65</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 1.6E-07</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 7.9E-09</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p>	
		<p>C (m<sup>3</sup>/Pa) = 8.3E-11</p> <p>C<sub>D</sub> (-) = 9.2E-03</p> <p>ξ (-) = 6.70</p>	
<b>Comments:</b>			
<p>The recommended transmissivity of 1.6E-7 m<sup>2</sup>/s was derived from the analysis of the CHi phase (inner zone), which shows a horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be 8.0E-8 m<sup>2</sup>/s to 5.0E-7 m<sup>2</sup>/s. The analysis was conducted using a flow dimension of 2 (radial flow). The static pressure measured at transducer depth, was derived from the Chir phase using straight line extrapolation in the Horner plot to a value of 3,334.2 kPa.</p>			

<b>Test Summary Sheet</b>			
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070220 10:20
Test section from - to (m):	342.50-362.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>3700 3650 3600 3550 3500 3450 3400 3350 3300 3250 3200</p> <p>0.00 0.20 0.40 0.60 0.80 1.00 1.20 1.40</p> <p>Elapsed Time [h]</p> <p>KLX13A_342.50-362.50_070220_1_CHir_Q_r</p> <p>• P section • P above • P below • Q</p>		<p>Indata</p> <p>p<sub>0</sub> (kPa) = 3531</p> <p>p<sub>i</sub> (kPa) = 3529</p> <p>p<sub>p</sub> (kPa) = 3647</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 2.52E-04</p> <p>tp (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 11</p> <p>Derivative fact. = 0.04</p>	
		<p>Indata</p> <p>p<sub>F</sub> (kPa) = 3531</p> <p>t<sub>F</sub> (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.02</p>	
		<b>Results</b>	
		<p>Q/s (m<sup>2</sup>/s) = 2.1E-05</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 2.2E-05</p>	
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.37</p> <p>dt<sub>2</sub> (min) = 14.95</p> <p>T (m<sup>2</sup>/s) = 4.6E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 2.3E-06</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = 4.46</p>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.91</p> <p>dt<sub>2</sub> (min) = 13.78</p> <p>T (m<sup>2</sup>/s) = 4.8E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 9.6E-06</p> <p>S<sub>s</sub> (1/m) = 2.0E-07</p> <p>C (m<sup>3</sup>/Pa) = 5.1E-09</p> <p>C<sub>D</sub> (-) = 5.6E-01</p> <p>ξ (-) = 5.25</p>	
		<p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>	
		<p>dt<sub>1</sub> (min) = 0.91</p> <p>dt<sub>2</sub> (min) = 13.78</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 4.8E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 9.6E-06</p> <p>S<sub>s</sub> (1/m) = 2.0E-07</p>	
		<p>C (m<sup>3</sup>/Pa) = 5.1E-09</p> <p>C<sub>D</sub> (-) = 5.6E-01</p> <p>ξ (-) = 5.25</p>	
		<b>Comments:</b>	
		<p>The recommended transmissivity of 4.8E-05 m<sup>2</sup>/s was derived from the analysis of the CHir phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be 2.0E-05 m<sup>2</sup>/s to 7.0E-05 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 3,529.9 kPa.</p>	

<b>Test Summary Sheet</b>			
Project:	Oskarshamn site investigation	<a href="#">Test type: f1</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070220 12:56
Test section from - to (m):	355.50-375.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>p<sub>0</sub> (kPa) = 3658</p> <p>p<sub>i</sub> (kPa) = 3657</p> <p>p<sub>p</sub> (kPa) = 3817</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 2.79E-04</p> <p>tp (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 11.2</p> <p>Derivative fact. = 0.02</p>		<p>p<sub>F</sub> (kPa) = 3659</p> <p>t<sub>F</sub> (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.02</p>	
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<p>Q/s (m<sup>2</sup>/s) = 1.7E-05</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 1.8E-05</p>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.38</p> <p>dt<sub>2</sub> (min) = 19.17</p> <p>T (m<sup>2</sup>/s) = 4.1E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 2.1E-06</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = 6.02</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Results</b>	
		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 0.38</p> <p>dt<sub>2</sub> (min) = 9.19</p> <p>T (m<sup>2</sup>/s) = 6.1E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 3.1E-06</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 1.9E-09</p> <p>C<sub>D</sub> (-) = 2.1E-01</p> <p>ξ (-) = 13.40</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
		<p><b>Selected representative parameters.</b></p> <p>dt<sub>1</sub> (min) = 0.38</p> <p>dt<sub>2</sub> (min) = 19.17</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 4.1E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 2.1E-06</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = 1.9E-09</p> <p>C<sub>D</sub> (-) = 2.1E-01</p> <p>ξ (-) = 6.02</p>	
<b>Comments:</b>			
<p>The recommended transmissivity of 4.1E-05 m<sup>2</sup>/s was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be 2.0E-05 m<sup>2</sup>/s to 8.0E-05 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 3,658.5 kPa.</p>			

Test Summary Sheet			
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070220 15:00
Test section from - to (m):	375.50-395.50 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>Downhole Pressure [kPa]</p> <p>Elapsed Time [h]</p> <p>KLX13A_375.50-395.50_070220_1_CHir_Q_r</p> <p>• P section • P above • P below • Q</p>		<p><b>Indata</b></p> <p>p<sub>0</sub> (kPa) = 3854</p> <p>p<sub>i</sub> (kPa) = 3853</p> <p>p<sub>p</sub> (kPa) = 3861</p> <p>Q<sub>p</sub> (m<sup>3</sup>/s) = 2.37E-04</p> <p>tp (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 12.3</p> <p>Derivative fact. = 0.02</p>	<p><b>Indata</b></p> <p>p<sub>F</sub> (kPa) = 3857</p> <p>t<sub>F</sub> (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p>
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>	
		<b>Results</b>	
		<p>Q/s (m<sup>2</sup>/s) = 2.9E-04</p> <p>T<sub>M</sub> (m<sup>2</sup>/s) = 3.0E-04</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = #NV</p> <p>dt<sub>2</sub> (min) = #NV</p> <p>T (m<sup>2</sup>/s) = 4.4E-04</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 2.2E-05</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = -2.83</p> <p>T<sub>GRF</sub> (m<sup>2</sup>/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>	
<p>Not analysed</p>		<p>dt<sub>1</sub> (min) = #NV</p> <p>dt<sub>2</sub> (min) = #NV</p> <p>T<sub>T</sub> (m<sup>2</sup>/s) = 4.4E-04</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 2.2E-05</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p>	
		<p>C (m<sup>3</sup>/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = -2.83</p>	
		<b>Comments:</b>	
		<p>The recommended transmissivity of 4.4E-4 m<sup>2</sup>/s was derived from the analysis of the CHi phase (inner zone), which shows the best horizontal stabilisation of the derivative and best data and derivative quality. The confidence range for the interval transmissivity is estimated to be 7.0E-5 m<sup>2</sup>/s to 8.0E-4 m<sup>2</sup>/s. The analysis was conducted using a flow dimension of 2 (radial flow). The static pressure could not be analysed based on solely the CHi phase.</p>	

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: f1</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070220 17:06		
Test section from - to (m):	395.50-415.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	4052		
		p <sub>i</sub> (kPa) =	4052		
		p <sub>p</sub> (kPa) =	4160	p <sub>F</sub> (kPa) =	4053
		Q <sub>p</sub> (m <sup>3</sup> /s) =	2.41E-04		
		tp (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	13		
Derivative fact. =	0.02	Derivative fact. =	0.03		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	2.2E-05				
T <sub>M</sub> (m <sup>2</sup> /s) =	2.3E-05				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		Flow regime:	transient		
		dt <sub>1</sub> (min) =	0.22	dt <sub>1</sub> (min) =	0.36
		dt <sub>2</sub> (min) =	16.10	dt <sub>2</sub> (min) =	9.19
		T (m <sup>2</sup> /s) =	4.8E-05	T (m <sup>2</sup> /s) =	5.6E-05
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	2.4E-06	K <sub>s</sub> (m/s) =	2.8E-06
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	1.6E-09
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	1.8E-01
		ξ (-) =	4.42	ξ (-) =	7.77
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Flow regime: transient</b>			
		dt <sub>1</sub> (min) =	0.22	C (m <sup>3</sup> /Pa) =	#NV
		dt <sub>2</sub> (min) =	16.10	C <sub>D</sub> (-) =	#NV
		T <sub>T</sub> (m <sup>2</sup> /s) =	4.8E-05	ξ (-) =	4.42
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	2.4E-06		
		S <sub>s</sub> (1/m) =	5.0E-08		
		<b>Comments:</b>			
The recommended transmissivity of 4.8E-05 m <sup>2</sup> /s was derived from the analysis of the CHi phase, which shows the better derivative stabilisation. The confidence range for the interval transmissivity is estimated to be 3.0E-05 m <sup>2</sup> /s to 7.0E-05 m <sup>2</sup> /s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,053.1 kPa.					

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: f1</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070221 08:38		
Test section from - to (m):	415.50-435.40 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	4247		
		p <sub>i</sub> (kPa) =	4246		
		p <sub>p</sub> (kPa) =	4442	p <sub>F</sub> (kPa) =	4247
		Q <sub>p</sub> (m <sup>3</sup> /s) =	1.55E-04		
		tp (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	13.5		
Derivative fact. =	0.02	Derivative fact. =	0.02		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	7.7E-06				
T <sub>M</sub> (m <sup>2</sup> /s) =	8.1E-06				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		<b>Flow regime: transient</b>			
		dt <sub>1</sub> (min) =	0.78	dt <sub>1</sub> (min) =	0.41
		dt <sub>2</sub> (min) =	13.44	dt <sub>2</sub> (min) =	9.19
		T (m <sup>2</sup> /s) =	1.9E-05	T (m <sup>2</sup> /s) =	3.4E-05
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	9.5E-07	K <sub>s</sub> (m/s) =	1.7E-06
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	1.1E-09
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	1.2E-01
		ξ (-) =	6.02	ξ (-) =	19.50
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	0.78	C (m <sup>3</sup> /Pa) =	#NV
		dt <sub>2</sub> (min) =	13.44	C <sub>D</sub> (-) =	#NV
		T <sub>T</sub> (m <sup>2</sup> /s) =	1.9E-05	ξ (-) =	6.02
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	3.8E-06		
		S <sub>s</sub> (1/m) =	2.0E-07		
<b>Comments:</b>		<p>The recommended transmissivity of 1.9E-05 m<sup>2</sup>/s was derived from the analysis of the CHi phase due to the fast recovery during the CHir phase. The confidence range for the interval transmissivity is estimated to be 9.0E-06 m<sup>2</sup>/s to 5.0E-05 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,246.6 kPa.</p>			



<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070221 10:41		
Test section from - to (m):	435.50-455.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	4443		
		p <sub>i</sub> (kPa) =	4444		
		p <sub>p</sub> (kPa) =	4534	p <sub>F</sub> (kPa) =	4444
		Q <sub>p</sub> (m <sup>3</sup> /s) =	2.43E-04		
		t <sub>p</sub> (s) =	1200	t <sub>F</sub> (s) =	1200
		S e l S' (-) =	1.00E-06	S e l S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	13.8		
Derivative fact. =	0.02	Derivative fact. =	0.03		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	2.6E-05				
T <sub>M</sub> (m <sup>2</sup> /s) =	2.8E-05				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime:</b> transient			
		Flow regime:	transient		
		dt <sub>1</sub> (min) =	0.18	dt <sub>1</sub> (min) =	0.26
		dt <sub>2</sub> (min) =	16.50	dt <sub>2</sub> (min) =	8.82
		T (m <sup>2</sup> /s) =	5.5E-05	T (m <sup>2</sup> /s) =	5.9E-05
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	2.8E-06	K <sub>s</sub> (m/s) =	3.0E-06
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	3.3E-09
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	3.6E-01
		ξ (-) =	5.47	ξ (-) =	3.71
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	0.18	C (m <sup>3</sup> /Pa) =	3.3E-09
		dt <sub>2</sub> (min) =	16.50	C <sub>D</sub> (-) =	3.6E-01
		T <sub>T</sub> (m <sup>2</sup> /s) =	5.5E-05	ξ (-) =	5.47
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	2.8E-06		
		S <sub>s</sub> (1/m) =	5.0E-08		
<b>Comments:</b>		<p>The recommended transmissivity of 5.5E-05 m<sup>2</sup>/s was derived from the analysis of the CHi phase which is more reliable due to the fast recovery during the CHir phase. The confidence range for the interval transmissivity is estimated to be 3.0E-05 m<sup>2</sup>/s to 8.0E-05 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,442.8 kPa.</p>			

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070221 13:02		
Test section from - to (m):	455.50-475.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	4639		
		p <sub>i</sub> (kPa) =	4638		
		p <sub>p</sub> (kPa) =	4758	p <sub>F</sub> (kPa) =	4639
		Q <sub>p</sub> (m <sup>3</sup> /s) =	1.87E-04		
		t <sub>p</sub> (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	14.1		
Derivative fact. =	0.03	Derivative fact. =	0.03		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	1.5E-05				
T <sub>M</sub> (m <sup>2</sup> /s) =	1.6E-05				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		<b>Flow regime: transient</b>			
		dt <sub>1</sub> (min) =	0.91	dt <sub>1</sub> (min) =	0.26
		dt <sub>2</sub> (min) =	12.31	dt <sub>2</sub> (min) =	8.96
		T (m <sup>2</sup> /s) =	2.9E-05	T (m <sup>2</sup> /s) =	5.4E-05
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	1.5E-06	K <sub>s</sub> (m/s) =	2.7E-06
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	1.5E-09
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	1.6E-01
		ξ (-) =	2.94	ξ (-) =	13.60
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	0.91	C (m <sup>3</sup> /Pa) =	1.5E-09
		dt <sub>2</sub> (min) =	12.31	C <sub>D</sub> (-) =	1.6E-01
		T <sub>T</sub> (m <sup>2</sup> /s) =	2.9E-05	ξ (-) =	2.94
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	1.5E-06		
		S <sub>s</sub> (1/m) =	5.0E-08		
<b>Comments:</b>		<p>The recommended transmissivity of 2.9E-05 m<sup>2</sup>/s was derived from the analysis of the CHi phase due to the fast recovery during the CHir phase. The confidence range for the interval transmissivity is estimated to be 1.0E-05 m<sup>2</sup>/s to 7.0E-05 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,638.9 kPa.</p>			

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: f1</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070131 00:00		
Test section from - to (m):	475.50-495.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	9999		
		p <sub>i</sub> (kPa) =	9999		
		p <sub>p</sub> (kPa) =	9999	p <sub>F</sub> (kPa) =	9999
		Q <sub>p</sub> (m <sup>3</sup> /s) =	1.67E-04		
		tp (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	14.4		
Derivative fact. =	0.04	Derivative fact. =	0.02		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	3.0E-06				
T <sub>M</sub> (m <sup>2</sup> /s) =	3.1E-06				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime:</b> transient			
		Flow regime:	transient		
		dt <sub>1</sub> (min) =	0.61	dt <sub>1</sub> (min) =	0.50
		dt <sub>2</sub> (min) =	18.65	dt <sub>2</sub> (min) =	9.13
		T (m <sup>2</sup> /s) =	3.5E-06	T (m <sup>2</sup> /s) =	1.4E-05
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	1.8E-07	K <sub>s</sub> (m/s) =	7.0E-07
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	3.5E-10
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	3.8E-02
		ξ (-) =	-0.81	ξ (-) =	20.10
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	0.61	C (m <sup>3</sup> /Pa) =	3.5E-10
		dt <sub>2</sub> (min) =	18.65	C <sub>D</sub> (-) =	3.8E-02
		T <sub>T</sub> (m <sup>2</sup> /s) =	3.5E-06	ξ (-) =	-0.81
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	1.8E-07		
		S <sub>s</sub> (1/m) =	5.0E-08		
<b>Comments:</b>		<p>The recommended transmissivity of 3.5E-06 m<sup>2</sup>/s was derived from the analysis of the CHi phase, which shows a clear horizontal stabilisation and good data quality. The confidence range for the interval transmissivity is estimated to be 1.0E-06 m<sup>2</sup>/s to 8.0E-06 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 4,833.3 kPa.</p>			

Test Summary Sheet			
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir
Area:	Laxemar	Test no:	1
Borehole ID:	KLX13A	Test start:	070221 17:33
Test section from - to (m):	493.00-513.00 m	Responsible for test execution:	Stephan Rohs
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu
<b>Linear plot Q and p</b>		<b>Flow period</b>	
		<b>Recovery period</b>	
		<b>Indata</b>	
<p>KLX13A_493.00-513.00_070221_1_CHir_Q_r</p> <p>Y-axis: Borehole Pressure [kPa] (4700 to 5300)</p> <p>X-axis: Elapsed Time [h] (0.00 to 1.40)</p> <p>Legend: P section, P above, P below, Q</p>		<p><b>Indata</b></p> <p>p<sub>0</sub> (kPa) = 5005</p> <p>p<sub>i</sub> (kPa) = 5005</p> <p>p<sub>p</sub> (kPa) = 5203</p> <p>Q<sub>p</sub> (m³/s) = 5.92E-05</p> <p>tp (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>EC<sub>w</sub> (mS/m) =</p> <p>Temp<sub>w</sub> (gr C) = 14.7</p> <p>Derivative fact. = 0.02</p>	<p><b>Indata</b></p> <p>p<sub>F</sub> (kPa) = 5005</p> <p>t<sub>F</sub> (s) = 1200</p> <p>S el S' (-) = 1.00E-06</p> <p>Derivative fact. = 0.02</p>
<b>Log-Log plot incl. derivates- flow period</b>		<b>Results</b>	
		<p><b>Results</b></p> <p>Q/s (m²/s) = 2.9E-06</p> <p>T<sub>M</sub> (m²/s) = 3.1E-06</p> <p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 8.50</p> <p>dt<sub>2</sub> (min) = 26.27</p> <p>T (m²/s) = 3.5E-06</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 1.8E-07</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m³/Pa) = NA</p> <p>C<sub>D</sub> (-) = NA</p> <p>ξ (-) = -0.41</p> <p>T<sub>GRF</sub> (m²/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>	<p><b>Results</b></p> <p>Q/s (m²/s) =</p> <p>T<sub>M</sub> (m²/s) =</p> <p>Flow regime: transient</p> <p>dt<sub>1</sub> (min) = 10.02</p> <p>dt<sub>2</sub> (min) = 14.04</p> <p>T (m²/s) = 1.4E-05</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 7.0E-07</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p> <p>C (m³/Pa) = 1.7E-10</p> <p>C<sub>D</sub> (-) = 1.9E-02</p> <p>ξ (-) = 20.40</p> <p>T<sub>GRF</sub> (m²/s) = NA</p> <p>S<sub>GRF</sub> (-) = NA</p> <p>D<sub>GRF</sub> (-) = NA</p>
		<b>Log-Log plot incl. derivatives- recovery period</b>	
		<p>dt<sub>1</sub> (min) = 8.50</p> <p>dt<sub>2</sub> (min) = 26.27</p> <p>T<sub>T</sub> (m²/s) = 3.5E-06</p> <p>S (-) = 1.0E-06</p> <p>K<sub>s</sub> (m/s) = 1.8E-07</p> <p>S<sub>s</sub> (1/m) = 5.0E-08</p>	<p>C (m³/Pa) = 1.7E-10</p> <p>C<sub>D</sub> (-) = 1.9E-02</p> <p>ξ (-) = -0.41</p>
		<p><b>Comments:</b></p> <p>The recommended transmissivity of 3.5E-06 m²/s was derived from the analysis of the CHi phase, which is of good quality and shows a clear horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be 1.0E-06 m²/s to 6.0E-06 m²/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,005.4 kPa.</p>	

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: f11</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070222 08:14		
Test section from - to (m):	507.00-527.00 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Indata</b>			
		p <sub>0</sub> (kPa) = 5142			
		p <sub>i</sub> (kPa) = 5140			
		p <sub>p</sub> (kPa) = 5339		p <sub>F</sub> (kPa) = 5141	
		Q <sub>p</sub> (m <sup>3</sup> /s) = 1.48E-05			
		tp (s) = 1200		t <sub>F</sub> (s) = 1200	
		S el S' (-) = 1.00E-06		S el S' (-) = 1.00E-06	
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) = 14.9			
		Derivative fact. = 0.04		Derivative fact. = 0.04	
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) = 7.3E-07					
T <sub>M</sub> (m <sup>2</sup> /s) = 7.6E-07					
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime:</b> transient			
		Flow regime: transient			
		dt <sub>1</sub> (min) = 0.17		dt <sub>1</sub> (min) = 0.97	
		dt <sub>2</sub> (min) = 17.90		dt <sub>2</sub> (min) = 15.20	
		T (m <sup>2</sup> /s) = 9.1E-07		T (m <sup>2</sup> /s) = 3.5E-06	
		S (-) = 1.0E-06		S (-) = 1.0E-06	
		K <sub>s</sub> (m/s) = 4.6E-08		K <sub>s</sub> (m/s) = 1.8E-07	
		S <sub>s</sub> (1/m) = 5.0E-08		S <sub>s</sub> (1/m) = 5.0E-08	
		C (m <sup>3</sup> /Pa) = NA		C (m <sup>3</sup> /Pa) = 2.9E-10	
		C <sub>D</sub> (-) = NA		C <sub>D</sub> (-) = 3.2E-02	
		ξ (-) = 0.84		ξ (-) = 20.20	
T <sub>GRF</sub> (m <sup>2</sup> /s) = NA		T <sub>GRF</sub> (m <sup>2</sup> /s) = NA			
S <sub>GRF</sub> (-) = NA		S <sub>GRF</sub> (-) = NA			
D <sub>GRF</sub> (-) = NA		D <sub>GRF</sub> (-) = NA			
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) = 0.17			
		dt <sub>2</sub> (min) = 17.90			
		T <sub>T</sub> (m <sup>2</sup> /s) = 9.1E-07			
		S (-) = 1.0E-06			
		K <sub>s</sub> (m/s) = 4.6E-08			
		S <sub>s</sub> (1/m) = 5.0E-08			
C (m <sup>3</sup> /Pa) = 2.9E-10					
C <sub>D</sub> (-) = 3.2E-02					
ξ (-) = 0.84					
<b>Comments:</b>					
The recommended transmissivity of 9.1E-07 m <sup>2</sup> /s was derived from the analysis of the CHi phase, which shows the better derivative quality. The confidence range for the interval transmissivity is estimated to be 7.0E-07 m <sup>2</sup> /s to 4.0E-06 m <sup>2</sup> /s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,140.4 kPa.					

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070222 10:14		
Test section from - to (m):	527.00-547.00 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	5338		
		p <sub>i</sub> (kPa) =	5336		
		p <sub>p</sub> (kPa) =	5536	p <sub>F</sub> (kPa) =	5339
		Q <sub>p</sub> (m <sup>3</sup> /s) =	1.67E-05		
		tp (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	15.2		
Derivative fact. =	0.03	Derivative fact. =	0.04		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	8.2E-07				
T <sub>M</sub> (m <sup>2</sup> /s) =	8.6E-07				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		<b>Flow regime: transient</b>			
		dt <sub>1</sub> (min) =	0.20	dt <sub>1</sub> (min) =	0.87
		dt <sub>2</sub> (min) =	18.25	dt <sub>2</sub> (min) =	18.02
		T (m <sup>2</sup> /s) =	9.5E-07	T (m <sup>2</sup> /s) =	3.1E-06
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	4.8E-08	K <sub>s</sub> (m/s) =	1.6E-07
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	1.8E-10
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	2.0E-02
		ξ (-) =	-0.02	ξ (-) =	14.60
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	0.20	C (m <sup>3</sup> /Pa) =	1.8E-10
		dt <sub>2</sub> (min) =	18.25	C <sub>D</sub> (-) =	2.0E-02
		T <sub>T</sub> (m <sup>2</sup> /s) =	9.5E-07	ξ (-) =	-0.02
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	4.8E-08		
		S <sub>s</sub> (1/m) =	5.0E-08		
		<b>Comments:</b>			
The recommended transmissivity of 9.5E-07 m <sup>2</sup> /s was derived from the analysis of the CHi phase, which shows the better derivative and horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be 7.0E-07 m <sup>2</sup> /s to 5.0E-06 m <sup>2</sup> /s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,335.5 kPa.					

Test Summary Sheet					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070222 13:02		
Test section from - to (m):	547.00-567.00 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
Linear plot Q and p		Flow period			
		Recovery period			
		Indata			
		p <sub>0</sub> (kPa) =	5533		
		p <sub>i</sub> (kPa) =	5532		
		p <sub>p</sub> (kPa) =	5731	p <sub>F</sub> (kPa) =	5533
		Q <sub>p</sub> (m <sup>3</sup> /s) =	1.63E-05		
		tp (s) =	1200	t <sub>F</sub> (s) =	1200
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	15.5		
Derivative fact. =	0.05	Derivative fact. =	0.03		
Log-Log plot incl. derivatives- flow period		Results			
		Q/s (m <sup>2</sup> /s) =	8.1E-07		
		T <sub>M</sub> (m <sup>2</sup> /s) =	8.4E-07		
		Flow regime:	transient	Flow regime:	transient
		dt <sub>1</sub> (min) =	0.28	dt <sub>1</sub> (min) =	0.33
		dt <sub>2</sub> (min) =	18.27	dt <sub>2</sub> (min) =	13.15
		T (m <sup>2</sup> /s) =	1.1E-06	T (m <sup>2</sup> /s) =	4.1E-06
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	5.5E-08	K <sub>s</sub> (m/s) =	2.1E-07
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	7.1E-11
C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	7.8E-03		
ξ (-) =	0.89	ξ (-) =	20.90		
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
Log-Log plot incl. derivatives- recovery period		Selected representative parameters.			
		dt <sub>1</sub> (min) =	0.28	C (m <sup>3</sup> /Pa) =	7.1E-11
		dt <sub>2</sub> (min) =	18.27	C <sub>D</sub> (-) =	7.8E-03
		T <sub>T</sub> (m <sup>2</sup> /s) =	1.1E-06	ξ (-) =	0.89
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	5.5E-08		
		S <sub>s</sub> (1/m) =	5.0E-08		
Comments:					
<p>The recommended transmissivity of 1.1E-06 m<sup>2</sup>/s was derived from the analysis of the CHi phase, which shows the better derivative quality and horizontal stabilisation. The confidence range for the interval transmissivity is estimated to be 8.0E-07 m<sup>2</sup>/s to 5.0E-06 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,530.2 kPa.</p>					

<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: [1]</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070222 15:00		
Test section from - to (m):	562.50-582.50 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	5686		
		p <sub>i</sub> (kPa) =	5685		
		p <sub>p</sub> (kPa) =	5883	p <sub>F</sub> (kPa) =	5691
		Q <sub>p</sub> (m <sup>3</sup> /s) =	1.45E-06		
		tp (s) =	1200	t <sub>F</sub> (s) =	3600
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	15.8		
Derivative fact. =	0.06	Derivative fact. =	0.02		
<b>Results</b>		<b>Results</b>			
Q/s (m <sup>2</sup> /s) =	7.2E-08				
T <sub>M</sub> (m <sup>2</sup> /s) =	7.5E-08				
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Flow regime: transient</b>			
		Flow regime:	transient		
		dt <sub>1</sub> (min) =	2.44	dt <sub>1</sub> (min) =	19.84
		dt <sub>2</sub> (min) =	18.35	dt <sub>2</sub> (min) =	52.24
		T (m <sup>2</sup> /s) =	3.7E-08	T (m <sup>2</sup> /s) =	3.7E-08
		S (-) =	1.0E-06	S (-) =	1.0E-06
		K <sub>s</sub> (m/s) =	1.9E-09	K <sub>s</sub> (m/s) =	1.9E-09
		S <sub>s</sub> (1/m) =	5.0E-08	S <sub>s</sub> (1/m) =	5.0E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	8.5E-12
		C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	9.4E-04
		ξ (-) =	-2.38	ξ (-) =	-2.86
T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA	T <sub>GRF</sub> (m <sup>2</sup> /s) =	NA		
S <sub>GRF</sub> (-) =	NA	S <sub>GRF</sub> (-) =	NA		
D <sub>GRF</sub> (-) =	NA	D <sub>GRF</sub> (-) =	NA		
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	19.84	C (m <sup>3</sup> /Pa) =	8.5E-12
		dt <sub>2</sub> (min) =	52.24	C <sub>D</sub> (-) =	9.4E-04
		T <sub>T</sub> (m <sup>2</sup> /s) =	3.7E-08	ξ (-) =	-2.86
		S (-) =	1.0E-06		
		K <sub>s</sub> (m/s) =	1.9E-09		
		S <sub>s</sub> (1/m) =	5.0E-08		
<b>Comments:</b>		<p>The recommended transmissivity of 3.7E-8 m<sup>2</sup>/s was derived from the analysis of the CHir phase (inner zone), which shows the best data and derivative quality. The confidence range for the interval transmissivity is estimated to be 1.0E-8 m<sup>2</sup>/s to 5.0E-8 m<sup>2</sup>/s. The flow dimension displayed during the test is 2 (radial flow). The static pressure measured at transducer depth, was derived from the CHir phase using straight line extrapolation in the Horner plot to a value of 5,677.5 kPa.</p>			



<b>Test Summary Sheet</b>					
Project:	Oskarshamn site investigation	<a href="#">Test type: f11</a>	CHir		
Area:	Laxemar	Test no:	1		
Borehole ID:	KLX13A	Test start:	070222 15:00		
Test section from - to (m):	583.50-595.85 m	Responsible for test execution:	Stephan Rohs		
Section diameter, 2·r <sub>w</sub> (m):	0.076	Responsible for test evaluation:	Cristian Enachescu		
<b>Linear plot Q and p</b>		<b>Flow period</b>			
		<b>Recovery period</b>			
		<b>Indata</b>		<b>Indata</b>	
		p <sub>0</sub> (kPa) =	5711		
		p <sub>i</sub> (kPa) =	5712		
		p <sub>p</sub> (kPa) =	5798	p <sub>F</sub> (kPa) =	5717
		Q <sub>p</sub> (m <sup>3</sup> /s) =	NA		
		t <sub>p</sub> (s) =	1200	t <sub>F</sub> (s) =	3600
		S el S' (-) =	1.00E-06	S el S' (-) =	1.00E-06
		EC <sub>w</sub> (mS/m) =			
		Temp <sub>w</sub> (gr C) =	NA		
Derivative fact. =	0.04	Derivative fact. =	0.04		
<b>Log-Log plot incl. derivatives- flow period</b>		<b>Results</b>			
		Q/s (m <sup>2</sup> /s) =	NA		
		T <sub>M</sub> (m <sup>2</sup> /s) =	NA		
		Flow regime:	transient	Flow regime:	transient
		dt <sub>1</sub> (min) =	0.70	dt <sub>1</sub> (min) =	1.80
		dt <sub>2</sub> (min) =	1.55	dt <sub>2</sub> (min) =	8.62
		T (m <sup>2</sup> /s) =	4.0E-08	T (m <sup>2</sup> /s) =	6.4E-08
		S (-) =	8.4E-08	S (-) =	2.2E-07
		K <sub>s</sub> (m/s) =	3.3E-09	K <sub>s</sub> (m/s) =	5.1E-09
		S <sub>s</sub> (1/m) =	6.8E-09	S <sub>s</sub> (1/m) =	1.7E-08
		C (m <sup>3</sup> /Pa) =	NA	C (m <sup>3</sup> /Pa) =	NA
C <sub>D</sub> (-) =	NA	C <sub>D</sub> (-) =	NA		
ξ (-) =	NA	ξ (-) =	NA		
T <sub>GRF</sub> (m <sup>2</sup> /s) =		T <sub>GRF</sub> (m <sup>2</sup> /s) =			
S <sub>GRF</sub> (-) =		S <sub>GRF</sub> (-) =			
D <sub>GRF</sub> (-) =		D <sub>GRF</sub> (-) =			
<b>Log-Log plot incl. derivatives- recovery period</b>		<b>Selected representative parameters.</b>			
		dt <sub>1</sub> (min) =	1.80	C (m <sup>3</sup> /Pa) =	NA
		dt <sub>2</sub> (min) =	8.62	C <sub>D</sub> (-) =	NA
		T <sub>T</sub> (m <sup>2</sup> /s) =	6.4E-08	ξ (-) =	NA
		S (-) =	2.2E-07		
		K <sub>s</sub> (m/s) =	5.1E-09		
		S <sub>s</sub> (1/m) =	1.7E-08		
<b>Comments:</b>					
		<p>The analysis of this test is based on the response of the bottom zone from the previous test.</p> <p>The recommended transmissivity of 6.4•10-8 m2/s was derived from the analysis of the CHir phase (inner zone), which shows the best data and derivative quality. The confidence range for the interval transmissivity is estimated to be 1.0•10-8 m2/s to 1.0•10-7 m2/s. The analysis was conducted using a flow dimension of 2 (radial flow).</p>			

Borehole: KLX13 A

## **APPENDIX 4**

Nomenclature

Character	SICADA designation	Explanation	Dimension	Unit
<b>Variables, constants</b>				
$A_w$		Horizontal area of water surface in open borehole, not including area of signal cables, etc.	$[L^2]$	$m^2$
$b$		Aquifer thickness (Thickness of 2D formation)	$[L]$	$m$
$B$		Width of channel	$[L]$	$m$
$L$		Corrected borehole length	$[L]$	$m$
$L_0$		Uncorrected borehole length	$[L]$	$m$
$L_p$		Point of application for a measuring section based on its centre point or centre of gravity for distribution of transmissivity in the measuring section.	$[L]$	$m$
$L_w$		Test section length.	$[L]$	$m$
$dL$		Step length, Positive Flow Log - overlapping flow logging. (step length, PFL)	$[L]$	$m$
$r$		Radius	$[L]$	$m$
$r_w$		Borehole, well or soil pipe radius in test section.	$[L]$	$m$
$r_{we}$		Effective borehole, well or soil pipe radius in test section. (Consideration taken to skin factor)	$[L]$	$m$
$r_s$		Distance from test section to observation section, the shortest distance.	$[L]$	$m$
$r_t$		Distance from test section to observation section, the <b>interpreted</b> shortest distance via conductive structures.	$[L]$	$m$
$r_D$		Dimensionless radius, $r_D=r/r_w$	-	-
$Z$		Level above reference point	$[L]$	$m$
$Z_r$		Level for reference point on borehole	$[L]$	$m$
$Z_{wu}$		Level for test section (section that is being flowed), upper limitation	$[L]$	$m$
$Z_{wl}$		Level for test section (section that is being flowed), lower limitation	$[L]$	$m$
$Z_{ws}$		Level for sensor that measures response in test section (section that is flowed)	$[L]$	$m$
$Z_{ou}$		Level for observation section, upper limitation	$[L]$	$m$
$Z_{ol}$		Level for observation section, lower limitation	$[L]$	$m$
$Z_{os}$		Level for sensor that measures response in observation section	$[L]$	$m$
$E$		Evaporation: hydrological budget:	$[L^3/(T L^2)]$ $[L^3/T]$	$mm/y,$ $mm/d,$ $m^3/s$
$ET$		Evapotranspiration hydrological budget:	$[L^3/(T L^2)]$ $[L^3/T]$	$mm/y,$ $mm/d,$ $m^3/s$
$P$		Precipitation hydrological budget:	$[L^3/(T L^2)]$ $[L^3/T]$	$mm/y,$ $mm/d,$ $m^3/s$
$R$		Groundwater recharge hydrological budget:	$[L^3/(T L^2)]$ $[L^3/T]$	$mm/y,$ $mm/d,$ $m^3/s$
$D$		Groundwater discharge hydrological budget:	$[L^3/(T L^2)]$ $[L^3/T]$	$mm/y,$ $mm/d,$ $m^3/s$
$Q_R$		Run-off rate	$[L^3/T]$	$m^3/s$
$Q_p$		Pumping rate	$[L^3/T]$	$m^3/s$
$Q_1$		Infiltration rate	$[L^3/T]$	$m^3/s$
$Q$		Volumetric flow. Corrected flow in flow logging ( $Q_1 - Q_0$ ) (Flow rate)	$[L^3/T]$	$m^3/s$
$Q_0$		Flow in test section during undisturbed conditions (flow logging).	$[L^3/T]$	$m^3/s$
$Q_p$		Flow in test section immediately before stop of flow. Stabilised pump flow in flow logging.	$[L^3/T]$	$m^3/s$

Character	SICADA designation	Explanation	Dimension	Unit
$Q_m$		Arithmetical mean flow during perturbation phase.	$[L^3/T]$	$m^3/s$
$Q_1$		Flow in test section during pumping with pump flow $Q_{p1}$ , (flow logging).	$[L^3/T]$	$m^3/s$
$Q_2$		Flow in test section during pumping with pump flow $Q_{p1}$ , (flow logging).	$[L^3/T]$	$m^3/s$
$\Sigma Q$	SumQ	Cumulative volumetric flow along borehole	$[L^3/T]$	$m^3/s$
$\Sigma Q_0$	SumQ0	Cumulative volumetric flow along borehole, undisturbed conditions (ie, not pumped)	$[L^3/T]$	$m^3/s$
$\Sigma Q_1$	SumQ1	Cumulative volumetric flow along borehole, with pump flow $Q_{p1}$	$[L^3/T]$	$m^3/s$
$\Sigma Q_2$	SumQ2	Cumulative volumetric flow along borehole, with pump flow $Q_{p2}$	$[L^3/T]$	$m^3/s$
$\Sigma Q_{C1}$	SumQC1	Corrected cumulative volumetric flow along borehole, $\Sigma Q_1 - \Sigma Q_0$	$[L^3/T]$	$m^3/s$
$\Sigma Q_{C2}$	SumQC2	Corrected cumulative volumetric flow along borehole, $\Sigma Q_2 - \Sigma Q_0$	$[L^3/T]$	$m^3/s$
$q$		Volumetric flow per flow passage area (Specific discharge (Darcy velocity, Darcy flux, Filtration velocity)).	$([L^3/T \cdot L^2])$	$m/s$
$V$		Volume	$[L^3]$	$m^3$
$V_w$		Water volume in test section.	$[L^3]$	$m^3$
$V_p$		Total water volume injected/pumped during perturbation phase.	$[L^3]$	$m^3$
$v$		Velocity	$([L^3/T \cdot L^2])$	$m/s$
$v_a$		Mean transport velocity (Average linear velocity (Average linear groundwater velocity, Mean microscopic velocity)); $v_a = q/n_e$	$([L^3/T \cdot L^2])$	$m/s$
$t$		Time	$[T]$	hour, min, s
$t_0$		Duration of rest phase before perturbation phase.	$[T]$	s
$t_p$		Duration of perturbation phase. (from flow start as far as $p_p$ ).	$[T]$	s
$t_F$		Duration of recovery phase (from $p_p$ to $p_F$ ).	$[T]$	s
$t_1, t_2$ etc		Times for various phases during a hydro test.	$[T]$	hour, min, s
$dt$		Running time from start of flow phase and recovery phase respectively.	$[T]$	s
$dt_e$		$dt_e = (dt \cdot t_p) / (dt + t_p)$ Agarwal equivalent time with $dt$ as running time for recovery phase.	$[T]$	s
$t_D$		$t_D = T \cdot t / (S \cdot r_w^2)$ . Dimensionless time	-	-
$p$		Static pressure; including non-dynamic pressure which depends on water velocity. Dynamic pressure is normally ignored in estimating the potential in groundwater flow relations.	$[M/(LT)^2]$	kPa
$p_a$		Atmospheric pressure	$[M/(LT)^2]$	kPa
$p_t$		Absolute pressure; $p_t = p_a + p_g$	$[M/(LT)^2]$	kPa
$p_g$		Gauge pressure; Difference between absolute pressure and atmospheric pressure.	$[M/(LT)^2]$	kPa
$p_0$		Initial pressure before test begins, prior to packer expansion.	$[M/(LT)^2]$	kPa
$p_i$		Pressure in measuring section before start of flow.	$[M/(LT)^2]$	kPa
$p_f$		Pressure during perturbation phase.	$[M/(LT)^2]$	kPa
$p_s$		Pressure during recovery.	$[M/(LT)^2]$	kPa
$p_p$		Pressure in measuring section before flow stop.	$[M/(LT)^2]$	kPa
$p_F$		Pressure in measuring section at end of recovery.	$[M/(LT)^2]$	kPa
$p_D$		$p_D = 2\pi \cdot T \cdot p / (Q \cdot \rho_w \cdot g)$ , Dimensionless pressure	-	-
$dp$		Pressure difference, drawdown of pressure surface between two points of time.	$[M/(LT)^2]$	kPa

Character	SICADA designation	Explanation	Dimension	Unit
$dp_f$		$dp_f = p_i - p_f$ or $= p_f - p_i$ , drawdown/pressure increase of pressure surface between two points of time during perturbation phase. $dp_f$ usually expressed positive.	$[M/(LT)^2]$	kPa
$dp_s$		$dp_s = p_s - p_p$ or $= p_p - p_s$ , pressure increase/drawdown of pressure surface between two points of time during recovery phase. $dp_s$ usually expressed positive.	$[M/(LT)^2]$	kPa
$dp_p$		$dp_p = p_i - p_p$ or $= p_p - p_i$ , <b>maximal</b> pressure increase/drawdown of pressure surface between two points of time during perturbation phase. $dp_p$ expressed positive.	$[M/(LT)^2]$	kPa
$dp_F$		$dp_F = p_p - p_F$ or $= p_F - p_p$ , <b>maximal</b> pressure increase/drawdown of pressure surface between two points of time during recovery phase. $dp_F$ expressed positive.	$[M/(LT)^2]$	kPa
H		Total head; (potential relative a reference level) (indication of h for phase as for p). $H=h_e+h_p+h_v$	[L]	m
h		Groundwater pressure level (hydraulic head (piezometric head; possible to use for level observations in boreholes, static head)); (indication of h for phase as for p). $h=h_e+h_p$	[L]	m
$h_e$		Height of measuring point (Elevation head); Level above reference level for measuring point.	[L]	m
$h_p$		Pressure head; Level above reference level for height of measuring point of stationary column of water giving corresponding static pressure at measuring point	[L]	m
$h_v$		Velocity head; height corresponding to the lifting for which the kinetic energy is capable (usually neglected in hydrogeology)	[L]	m
s		Drawdown; Drawdown from undisturbed level (same as $dh_p$ , positive)	[L]	m
$s_p$		Drawdown in measuring section before flow stop.	[L]	m
			[L]	
$h_0$		Initial above reference level before test begins, prior to packer expansion.	[L]	m
$h_i$		Level above reference level in measuring section before start of flow.	[L]	m
$h_f$		Level above reference level during perturbation phase.	[L]	m
$h_s$		Level above reference level during recovery phase.	[L]	m
$h_p$		Level above reference level in measuring section before flow stop.	[L]	m
$h_F$		Level above reference level in measuring section at end of recovery.	[L]	m
dh		Level difference, drawdown of water level between two points of time.	[L]	m
$dh_f$		$dh_f = h_i - h_f$ or $= h_f - h_i$ , drawdown/pressure increase of pressure surface between two points of time during perturbation phase. $dh_f$ usually expressed positive.	[L]	m
$dh_s$		$dh_s = h_s - h_p$ or $= h_p - h_s$ , pressure increase/drawdown of pressure surface between two points of time during recovery phase. $dh_s$ usually expressed positive.	[L]	m
$dh_p$		$dh_p = h_i - h_p$ or $= h_p - h_i$ , maximal pressure increase/drawdown of pressure surface between two points of time during perturbation phase. $dh_p$ expressed positive.	[L]	m
$dh_F$		$dh_F = h_p - h_F$ or $= h_F - h_p$ , maximal pressure increase/drawdown of pressure surface between two points of time during perturbation phase. $dh_F$ expressed positive.	[L]	m
$Te_w$		Temperature in the test section (taken from temperature logging). Temperature		°C
$Te_{w0}$		Temperature in the test section during undisturbed conditions (taken from temperature logging).		°C

Character	SICADA designation	Explanation	Dimension	Unit
Te <sub>o</sub>		Temperature in the observation section (taken from temperature logging). Temperature		°C
EC <sub>w</sub>		Electrical conductivity of water in test section.		mS/m
EC <sub>w0</sub>		Electrical conductivity of water in test section during undisturbed conditions.		mS/m
EC <sub>o</sub>		Electrical conductivity of water in observation section		mS/m
TDS <sub>w</sub>		Total salinity of water in the test section.	[M/L <sup>3</sup> ]	mg/L
TDS <sub>w0</sub>		Total salinity of water in the test section during undisturbed conditions.	[M/L <sup>3</sup> ]	mg/L
TDS <sub>o</sub>		Total salinity of water in the observation section.	[M/L <sup>3</sup> ]	mg/L
g		Constant of gravitation (9.81 m*s <sup>-2</sup> ) (Acceleration due to gravity)	[L/T <sup>2</sup> ]	m/s <sup>2</sup>
π	pi	Constant (approx 3.1416).	[-]	
r		Residual. r= p <sub>c</sub> -p <sub>m</sub> , r= h <sub>c</sub> -h <sub>m</sub> , etc. Difference between measured data (p <sub>m</sub> , h <sub>m</sub> , etc) and estimated data (p <sub>c</sub> , h <sub>c</sub> , etc)		
ME		Mean error in residuals. $ME = \frac{1}{n} \sum_{i=1}^n r_i$		
NME		Normalized ME. NME=ME/(x <sub>MAX</sub> -x <sub>MIN</sub> ), x: measured variable considered.		
MAE		Mean absolute error. $MAE = \frac{1}{n} \sum_{i=1}^n  r_i $		
NMAE		Normalized MAE. NMAE=MAE/(x <sub>MAX</sub> -x <sub>MIN</sub> ), x: measured variable considered.		
RMS		Root mean squared error. $RMS = \left( \frac{1}{n} \sum_{i=1}^n r_i^2 \right)^{0.5}$		
NRMS		Normalized RMR. NRMR=RMR/(x <sub>MAX</sub> -x <sub>MIN</sub> ), x: measured variable considered.		
SDR		Standard deviation of residual. $SDR = \left( \frac{1}{n-1} \sum_{i=1}^n (r_i - ME)^2 \right)^{0.5}$		
SEMR		Standard error of mean residual. $SEMR = \left( \frac{1}{n(n-1)} \sum_{i=1}^n (r_i - ME)^2 \right)^{0.5}$		
<b>Parameters</b>				
Q/s		Specific capacity s=dp <sub>p</sub> or s=s <sub>p</sub> =h <sub>o</sub> -h <sub>p</sub> (open borehole)	[L <sup>2</sup> /T]	m <sup>2</sup> /s
D		Interpreted flow dimension according to Barker, 1988.	[-]	-
dt <sub>1</sub>		Time of starting for semi-log or log-log evaluated characteristic counted from start of flow phase and recovery phase respectively.	[T]	s
dt <sub>2</sub>		End of time for semi-log or log-log evaluated characteristic counted from start of flow phase and recovery phase respectively.	[T]	s
dt <sub>L</sub>		Response time to obtain 0.1 m (or 1 kPa) drawdown in observation section counted from start of recovery phase.	[T]	s
TB		Flow capacity in a one-dimensional structure of width B and transmissivity T. Transient evaluation of one-dimensional structure	[L <sup>3</sup> /T]	m <sup>3</sup> /s
T		Transmissivity	[L <sup>2</sup> /T]	m <sup>2</sup> /s
T <sub>M</sub>		Transmissivity according to Moye (1967)	[L <sup>2</sup> /T]	m <sup>2</sup> /s
T <sub>Q</sub>		Evaluation based on Q/s and regression curve between Q/s and T, as example see Rhén et al (1997) p. 190.	[L <sup>2</sup> /T]	m <sup>2</sup> /s
T <sub>s</sub>		Transmissivity evaluated from slug test	[L <sup>2</sup> /T]	m <sup>2</sup> /s

Character	SICADA designation	Explanation	Dimension	Unit
$T_D$		Transmissivity evaluated from PFL-Difference Flow Meter	$[L^2/T]$	$m^2/s$
$T_I$		Transmissivity evaluated from Impeller flow log	$[L^2/T]$	$m^2/s$
$T_{Sf}, T_{Lf}$		Transient evaluation based on semi-log or log-log diagram for perturbation phase in injection or pumping.	$[L^2/T]$	$m^2/s$
$T_{Ss}, T_{Ls}$		Transient evaluation based on semi-log or log-log diagram for recovery phase in injection or pumping.	$[L^2/T]$	$m^2/s$
$T_T$		Transient evaluation (log-log or lin-log). Judged best evaluation of $T_{Sf}, T_{Lf}, T_{Ss}, T_{Ls}$	$[L^2/T]$	$m^2/s$
$T_{NLR}$		Evaluation based on non-linear regression.	$[L^2/T]$	$m^2/s$
$T_{Tot}$		Judged most representative transmissivity for particular test section and (in certain cases) evaluation time with respect to available data (made by SKB at a later stage).	$[L^2/T]$	$m^2/s$
K		Hydraulic conductivity	$[L/T]$	m/s
$K_s$		Hydraulic conductivity based on spherical flow model	$[L/T]$	m/s
$K_m$		Hydraulic conductivity matrix, intact rock	$[L/T]$	m/s
k		Intrinsic permeability	$[L^2]$	$m^2$
kb		Permeability-thickness product: $kb=k \cdot b$	$[L^3]$	$m^3$
SB		Storage capacity in a one-dimensional structure of width B and storage coefficient S. Transient evaluation of one-dimensional structure	[L]	m
SB*		Assumed storage capacity in a one-dimensional structure of width B and storage coefficient S. Transient evaluation of one-dimensional structure	[L]	m
S		Storage coefficient, (Storativity)	[-]	-
S*		Assumed storage coefficient	[-]	-
$S_y$		Theoretical specific yield of water (Specific yield; unconfined storage. Defined as total porosity (n) minus retention capacity ( $S_r$ ))	[-]	-
$S_{ya}$		Specific yield of water (Apparent specific yield); unconfined storage, field measuring. Corresponds to volume of water achieved on draining saturated soil or rock in free draining of a volumetric unit. $S_{ya}=S_y$ (often called $S_y$ in literature)	[-]	-
$S_r$		Specific retention capacity, (specific retention of water, field capacity) (Specific retention); unconfined storage. Corresponds to water volume that the soil or rock has left after free draining of saturated soil or rock.	[-]	-
$S_f$		Fracture storage coefficient	[-]	-
$S_m$		Matrix storage coefficient	[-]	-
$S_{NLR}$		Storage coefficient, evaluation based on non-linear regression	[-]	-
$S_{Tot}$		Judged most representative storage coefficient for particular test section and (in certain cases) evaluation time with respect to available data (made by SKB at a later stage).	[-]	-
$S_s$		Specific storage coefficient; confined storage.	$[1/L]$	1/m
$S_s^*$		Assumed specific storage coefficient; confined storage.	$[1/L]$	1/m
$c_f$		Hydraulic resistance: The hydraulic resistance is an aquitard with a flow vertical to a two-dimensional formation. The inverse of c is also called Leakage coefficient. $c_f=b'/K'$ where $b'$ is thickness of the aquitard and $K'$ its hydraulic conductivity across the aquitard.	[T]	s
$L_f$		Leakage factor: $L_f=(K \cdot b \cdot c_f)^{0.5}$ where K represents characteristics of the aquifer.	[L]	m
$\xi$	Skin	Skin factor	[-]	-

Character	SICADA designation	Explanation	Dimension	Unit
$\xi^*$	Skin	Assumed skin factor	[-]	-
C		Wellbore storage coefficient	$[(LT^2) \cdot M^2]$	$m^3/Pa$
$C_D$		$C_D = C \cdot \rho_w g / (2\pi \cdot S \cdot r_w^2)$ , Dimensionless wellbore storage coefficient	[-]	-
$\omega$	Stor-ratio	$\omega = S_f / (S_f + S_m)$ , storage ratio (Storativity ratio); the ratio of storage coefficient between that of the fracture and total storage.	[-]	-
$\lambda$	Interflow-coeff	$\lambda = \alpha \cdot (K_m / K_f) \cdot r_w^2$ interporosity flow coefficient.	[-]	-
$T_{GRF}$		Transmissivity interpreted using the GRF method	$[L^2/T]$	$m^2/s$
$S_{GRF}$		Storage coefficient interpreted using the GRF method	[ 1/L]	1/m
$D_{GRF}$		Flow dimension interpreted using the GRF method	[-]	-
$c_w$		Water compressibility; corresponding to $\beta$ in hydrogeological literature.	$[(LT^2)/M]$	1/Pa
$c_r$		Pore-volume compressibility, (rock compressibility); Corresponding to $\alpha/n$ in hydrogeological literature.	$[(LT^2)/M]$	1/Pa
$c_t$		$c_t = c_r + c_w$ , total compressibility; compressibility per volumetric unit of rock obtained through multiplying by the total porosity, n. (Presence of gas or other fluids can be included in $c_t$ if the degree of saturation (volume of respective fluid divided by n) of the pore system of respective fluid is also included)	$[(LT^2)/M]$	1/Pa
$nc_t$		Porosity-compressibility factor: $nc_t = n \cdot c_t$	$[(LT^2)/M]$	1/Pa
$nc_t b$		Porosity-compressibility-thickness product: $nc_t b = n \cdot c_t \cdot b$	$[(L^2 T^2)/M]$	m/Pa
n		Total porosity	-	-
$n_e$		Kinematic porosity, (Effective porosity)	-	-
e		Transport aperture. $e = n_e \cdot b$	[L]	m
$\rho$	Density	Density	$[M/L^3]$	$kg/(m^3)$
$\rho_w$	Density-w	Fluid density in measurement section during pumping/injection	$[M/L^3]$	$kg/(m^3)$
$\rho_o$	Density-o	Fluid density in observation section	$[M/L^3]$	$kg/(m^3)$
$\rho_{sp}$	Density-sp	Fluid density in standpipes from measurement section	$[M/L^3]$	$kg/(m^3)$
$\mu$	my	Dynamic viscosity	$[M/LT]$	Pa s
$\mu_w$	my	Dynamic viscosity (Fluid density in measurement section during pumping/injection)	$[M/LT]$	Pa s
$FC_T$		Fluid coefficient for intrinsic permeability, transference of k to K; $K = FC_T \cdot k$ ; $FC_T = \rho_w \cdot g / \mu_w$	[1/LT]	1/(ms)
$FC_S$		Fluid coefficient for porosity-compressibility, transference of $c_t$ to $S_s$ ; $S_s = FC_S \cdot n \cdot c_t$ ; $FC_S = \rho_w \cdot g$	$[M/T^2 L^2]$	Pa/m
<b>Index on K, T and S</b>				
S		S: semi-log		
L		L: log-log		
f		Pump phase or injection phase, designation following S or L (withdrawal)		
s		Recovery phase, designation following S or L (recovery)		
NLR		NLR: Non-linear regression. Performed on the entire test sequence, perturbation and recovery		
M		Moye		
GRF		Generalised Radial Flow according to Barker (1988)		
m		Matrix		
f		Fracture		
T		Judged best evaluation based on transient evaluation.		



Character	SICADA designation	Explanation	Dimension	Unit
Tot		Judged most representative parameter for particular test section and (in certain cases) evaluation time with respect to available data (made by SKB at a later stage).		
b		Bloch property in a numerical groundwater flow model		
e		Effective property (constant) within a domain in a numerical groundwater flow model.		
<b>Index on p and Q</b>				
0		Initial condition, undisturbed condition in open holes		
i		Natural, "undisturbed" condition of formation parameter		
f		Pump phase or injection phase (withdrawal, flowing phase)		
s		Recovery, shut-in phase		
p		Pressure or flow in measuring section at end of perturbation period		
F		Pressure in measuring section at end of recovery period.		
m		Arithmetical mean value		
c		Estimated value. The index is placed last if index for "where" and "what" are used. Simulated value		
m		Measured value. The index is placed last if index for "where" and "what" are used. Measured value		
<b>Some miscellaneous indexes on p and h</b>				
w		Test section (final difference pressure during flow phase in test section can be expressed $dp_{wp}$ ; First index shows "where" and second index shows "what")		
o		Observation section (final difference pressure during flow phase in observation section can be expressed $dp_{op}$ ; First index shows "where" and second index shows "what")		
f		Fresh-water head. Water is normally pumped up from section to measuring hoses where pressure and level are observed. Density of the water is therefore approximately the same as that of the measuring section. Measured groundwater level is therefore normally represented by what is defined as point-water head. If pressure at the measuring level is recalculated to a level for a column of water with density of fresh water above the measuring point it is referred to as fresh-water head and h is indicated last by an f. Observation section (final level during flow phase in observation section can be expressed $h_{opf}$ ; the first index shows "where" and the second index shows "what" and the last one "recalculation")		

## **APPENDIX 5**

SICADA data tables

Borehole: KLX13 A

## **APPENDIX 5-1**

SICADA data tables (Injection tests)



(Simplified version v1.4)

# SICADA/Data Import Template

SKB & Ergodata AB 2004

<b>File Identity</b>	
<b>Created By</b>	Stephan Rohs
<b>Created</b>	2007-05-18

<b>Compiled By</b>	
<b>Quality Check For Delivery</b>	
<b>Delivery Approval</b>	

<b>Activity Type</b>	KLX13A KLX 13A - Injection test
----------------------	------------------------------------

<b>Project</b>	AP PS 400-07-006
----------------	------------------

Activity Information						Additional Activity Data				
Idcode	Start Date	Stop Date	Secup (m)	Seclow (m)	Section No	C10	P20	P200	P220	R25

Idcode	Start Date	Stop Date	Secup (m)	Seclow (m)	Section No	Company	Field crew manager	Field crew	evaluating data	Report
KLX20A	2007-02-15 09:48	2007-02-22 17:15	102.50	582.50		Golder Associates	Stephan Rohs	Stephan Rohs, Mesgena Gebrezghi, Tomas Cronquist	Cristian Enacescu, Philipp Wolf, Stephan Rohs	Stephan Rohs

<b>Table</b>	<b>plu_s_hole_test_d</b> PLU Injection and pumping, General information
--------------	--

Column	Datatype	Unit	Column Description
site	CHAR		Investigation site name
activity_type	CHAR		Activity type code
start_date	DATE		Date (yymmdd hh:mm:ss)
stop_date	DATE		Date (yymmdd hh:mm:ss)
project	CHAR		project code
idcode	CHAR		Object or borehole identification code
secup	FLOAT	m	Upper section limit (m)
seclow	FLOAT	m	Lower section limit (m)
section_no	INTEGER	number	Section number
test_type	CHAR		Test type code (1-7), see table description
formation_type	CHAR		1: Rock, 2: Soil (superficial deposits)
start_flow_period	DATE	yyyymmdd	Date & time of pumping/injection start (YYYY-MM-DD hh:mm:ss)
stop_flow_period	DATE	yyyymmdd	Date & time of pumping/injection stop (YYYY-MM-DD hh:mm:ss)
flow_rate_end_qp	FLOAT	m**3/s	Flow rate at the end of the flowing period
value_type_qp	CHAR		0:true value,-1<lower meas.limit1:>upper meas.limit
mean_flow_rate_qm	FLOAT	m**3/s	Arithmetic mean flow rate during flow period
q_measl_l	FLOAT	m**3/s	Estimated lower measurement limit of flow rate
q_measl_u	FLOAT	m**3/s	Estimated upper measurement limit of flow rate
tot_volume_vp	FLOAT	m**3	Total volume of pumped or injected water
dur_flow_phase_tp	FLOAT	s	Duration of the flowing period of the test
dur_rec_phase_tf	FLOAT	s	Duration of the recovery period of the test
initial_head_hi	FLOAT	m	Hydraulic head in test section at start of the flow period
head_at_flow_end_hf	FLOAT	m	Hydraulic head in test section at stop of the flow period.
final_head_hf	FLOAT	m	Hydraulic head in test section at stop of recovery period.
initial_press_pi	FLOAT	kPa	Groundwater pressure in test section at start of flow period
press_at_flow_end_p	FLOAT	kPa	Groundwater pressure in test section at stop of flow period.
final_press_pf	FLOAT	kPa	Ground water pressure at the end of the recovery period.
fluid_temp_tew	FLOAT	oC	Measured section fluid temperature, see table description
fluid_elcond_ecw	FLOAT	mS/m	Measured section fluid el. conductivity,see table descr.
fluid_salinity_tds	FLOAT	mg/l	Total salinity of section fluid based on EC,see table descr.
fluid_salinity_tds	FLOAT	mg/l	Tot. section fluid salinity based on water sampling,see...
reference	CHAR		SKB report No for reports describing data and evaluation
comments	VARCHAR		Short comment to data
error_flag	CHAR		If error_flag = "*" then an error occurred and an error
in_use	CHAR		If in_use = "*" then the activity has been selected as
sign	CHAR		Signature for QA data acknowledgement (QA - OK)
lp	FLOAT	m	Hydraulic point of application

idcode	start_date	stop_date	secup	seclow	section_ no	test_type	formation_ type	start_flow_period	stop_flow_period	flow_rate_end_ qp	value_type_q p	mean_flow_ rate_qm	q_measl_ l	q_measl_ u	tot_volume_v p
KLX13A	2007-02-15 09:48:00	2007-02-15 14:06:00	102.50	202.50		3	1	2007-02-15 13:03:50	2007-02-15 13:34:00	6.50E-05	0	7.00E-05	1.67E-08	8.33E-04	1.26E-01
KLX13A	2007-02-15 15:34:00	2007-02-15 17:30:00	202.50	302.50		3	1	2007-02-15 16:28:11	2007-02-15 16:58:21	3.67E-05	0	4.05E-05	1.67E-08	8.33E-04	7.29E-02
KLX13A	2007-02-16 07:58:00	2007-02-16 10:27:00	302.50	402.50		3	1	2007-02-16 09:25:41	2007-02-16 09:55:51	2.63E-04	0	4.65E-04	1.67E-08	8.33E-04	8.37E-01
KLX13A	2007-02-16 11:52:00	2007-02-16 13:43:00	395.50	495.50		3	1	2007-02-16 12:41:02	2007-02-16 13:11:12	4.05E-04	0	4.52E-04	1.67E-08	8.33E-04	8.13E-01
KLX13A	2007-02-16 15:44:00	2007-02-16 17:35:00	482.50	582.50		3	1	2007-02-16 16:33:24	2007-02-16 17:03:34	1.05E-04	0	1.20E-04	1.67E-08	8.33E-04	2.16E-01
KLX13A	2007-02-17 18:25:00	2007-02-17 20:28:00	102.50	122.50		3	1	2007-02-17 19:06:03	2007-02-17 19:26:13	5.67E-05	0	6.17E-05	1.67E-08	8.33E-04	7.40E-02
KLX13A	2007-02-18 08:25:00	2007-02-18 10:31:00	122.50	142.50		3	1	2007-02-18 09:39:06	2007-02-18 09:49:16	1.67E-08	0	2.00E-08	1.67E-08	8.33E-04	1.20E-05
KLX13A	2007-02-18 13:24:00	2007-02-18 14:46:00	162.50	182.50		3	1	2007-02-18 14:04:13	2007-02-18 14:24:23	2.18E-06	0	2.35E-06	1.67E-08	8.33E-04	2.82E-03
KLX13A	2007-02-18 16:10:00	2007-02-18 17:42:00	182.50	202.50		3	1	2007-02-18 17:00:25	2007-02-18 17:20:35	5.18E-06	0	5.47E-06	1.67E-08	8.33E-04	6.56E-03
KLX13A	2007-02-18 18:12:00	2007-02-18 19:32:00	202.50	222.50		3	1	2007-02-18 18:50:25	2007-02-18 19:10:35	8.00E-06	0	8.50E-06	1.67E-08	8.33E-04	1.02E-02
KLX13A	2007-02-19 09:02:00	2007-02-19 10:27:00	222.50	242.50		3	1	2007-02-19 09:44:54	2007-02-19 10:05:04	1.72E-05	0	1.85E-05	1.67E-08	8.33E-04	2.22E-02
KLX13A	2007-02-19 11:04:00	2007-02-19 12:53:00	242.50	262.50		3	1	2007-02-19 11:50:34	2007-02-19 12:10:44	3.67E-07	-1	4.17E-07	1.67E-08	8.33E-04	5.00E-04
KLX13A	2007-02-19 14:13:00	2007-02-19 15:40:00	262.50	282.50		3	1	2007-02-19 14:58:31	2007-02-19 15:18:41	1.37E-06	0	1.49E-06	1.67E-08	8.33E-04	1.78E-03
KLX13A	2007-02-19 16:17:00	2007-02-19 17:40:00	282.50	302.50		3	1	2007-02-19 16:58:28	2007-02-19 17:18:38	1.80E-05	0	1.87E-05	1.67E-08	8.33E-04	2.24E-02
KLX13A	2007-02-19 18:12:00	2007-02-19 19:37:00	302.50	322.50		3	1	2007-02-19 18:55:41	2007-02-19 19:15:51	8.00E-05	0	9.17E-05	1.67E-08	8.33E-04	1.10E-01
KLX13A	2007-02-20 08:18:00	2007-02-20 09:42:00	322.50	342.50		3	1	2007-02-20 08:59:55	2007-02-20 09:20:05	1.60E-06	0	1.67E-06	1.67E-08	8.33E-04	2.00E-03
KLX13A	2007-02-20 10:20:00	2007-02-20 11:43:00	342.50	362.50		3	1	2007-02-20 11:01:32	2007-02-20 11:21:42	2.52E-04	0	2.62E-04	1.67E-08	8.33E-04	3.14E-01
KLX13A	2007-02-20 12:56:00	2007-02-20 14:18:00	355.50	375.50		3	1	2007-02-20 13:36:48	2007-02-20 13:56:58	2.79E-04	0	2.92E-04	1.67E-08	8.33E-04	3.51E-01
KLX13A	2007-02-20 15:00:00	2007-02-20 16:26:00	375.50	395.50		3	1	2007-02-20 15:44:09	2007-02-20 16:04:19	2.37E-04	0	4.68E-04	1.67E-08	8.33E-04	5.61E-01
KLX13A	2007-02-20 17:07:00	2007-02-20 18:30:00	395.50	415.50		3	1	2007-02-20 17:48:26	2007-02-20 18:08:36	2.41E-04	0	2.50E-04	1.67E-08	8.33E-04	3.00E-01
KLX13A	2007-02-21 08:38:00	2007-02-21 10:02:00	415.50	435.50		3	1	2007-02-21 09:20:29	2007-02-21 09:40:39	1.55E-04	0	1.60E-04	1.67E-08	8.33E-04	1.92E-01
KLX13A	2007-02-21 10:41:00	2007-02-21 12:03:00	435.50	455.50		3	1	2007-02-21 11:21:02	2007-02-21 11:41:12	2.43E-04	0	2.53E-04	1.67E-08	8.33E-04	3.04E-01
KLX13A	2007-02-21 13:02:00	2007-02-21 14:30:00	455.50	475.50		3	1	2007-02-21 13:48:14	2007-02-21 14:08:24	1.87E-04	0	1.99E-04	1.67E-08	8.33E-04	2.39E-01
KLX13A	2007-02-21 15:28:00	2007-02-21 16:54:00	475.50	495.50		3	1	2007-02-21 16:12:04	2007-02-21 16:32:14	6.07E-05	0	6.68E-05	1.67E-08	8.33E-04	8.02E-02
KLX13A	2007-02-21 17:33:00	2007-02-21 18:58:00	493.00	513.00		3	1	2007-02-21 18:16:28	2007-02-21 18:36:38	5.92E-05	0	6.40E-05	1.67E-08	8.33E-04	7.68E-02
KLX13A	2007-02-22 08:14:00	2007-02-22 09:36:00	507.00	527.00		3	1	2007-02-22 08:54:32	2007-02-22 09:14:42	1.48E-05	0	1.57E-05	1.67E-08	8.33E-04	1.88E-02
KLX13A	2007-02-22 10:14:00	2007-02-22 11:38:00	527.00	547.00		3	1	2007-02-22 10:56:22	2007-02-22 11:16:32	1.67E-05	0	1.80E-05	1.67E-08	8.33E-04	2.16E-02
KLX13A	2007-02-22 13:02:00	2007-02-22 14:22:00	547.00	567.00		3	1	2007-02-22 13:40:27	2007-02-22 14:00:37	1.63E-05	0	1.78E-05	1.67E-08	8.33E-04	2.14E-02
KLX13A	2007-02-22 15:00:00	2007-02-22 17:15:00	562.50	582.50		3	1	2007-02-22 15:53:03	2007-02-22 15:53:13	1.45E-06	0	1.77E-06	1.67E-08	8.33E-04	2.12E-03

idcode	secup	seclo	dur_flow_p hase_tp	dur_rec_ph ase_tf	initial_head_ hi	ow_end_h p	final_head_ hf	initial_press_ pi	press_at_flow_ end_pp	final_press_p f	fluid_temp_t ew	fluid_elcond_e cw	fluid_salinity_ tdsw	fluid_salinity_t dswm	reference	comments	lp
KLX13A	102.50	202.50	1800	1800			15.71	1978	2176	1981	9.1						152.50
KLX13A	202.50	302.50	1800	1800			14.75	2947	3147	2954	10.5						252.50
KLX13A	302.50	402.50	1800	1800			#NV	3923	3934	3927	12.4						352.50
KLX13A	395.50	495.50	1800	1800			16.67	4834	4875	4838	14.4						445.50
KLX13A	482.50	582.50	1800	1800			16.68	5686	5884	5687	15.8						532.50
KLX13A	102.50	122.50	1200	3600			15.73	1197	1396	1201	7.9						112.50
KLX13A	122.50	142.50	600	2400			#NV	1401	1627	1435	8.3						132.50
KLX13A	162.50	182.50	1200	1200			15.67	1782	1981	1783	8.8						172.50
KLX13A	182.50	202.50	1200	1200			14.32	1973	2172	1971	9.0						192.50
KLX13A	202.50	222.50	1200	1200			15.30	2168	2382	2168	9.3						212.50
KLX13A	222.50	242.50	1200	1200			15.05	2367	2567	2377	9.6						232.50
KLX13A	242.50	262.50	1200	2400			15.75	2565	2764	2565	10.0						252.50
KLX13A	262.50	282.50	1200	1200			14.61	2751	2963	2752	10.3						272.50
KLX13A	282.50	302.50	1200	1200			14.53	2943	3143	2943	10.6						292.50
KLX13A	302.50	322.50	1200	1200			14.77	3138	3336	3138	10.9						312.50
KLX13A	322.50	342.50	1200	1200			15.27	3336	3534	3335	11.1						332.50
KLX13A	342.50	362.50	1200	1200			15.22	3529	3647	3531	11.0						352.50
KLX13A	355.50	375.50	1200	1200			15.58	3657	3817	3659	11.2						365.50
KLX13A	375.50	395.50	1200	1200			#NV	3853	3861	3857	12.3						385.50
KLX13A	395.50	415.50	1200	1200			15.81	4052	4160	4053	13.0						405.50
KLX13A	415.50	435.50	1200	1200			16.00	4246	4442	4247	13.5						425.50
KLX13A	435.50	455.50	1200	1200			16.00	4444	4534	4444	13.8						445.50
KLX13A	455.50	475.50	1200	1200			15.99	4638	4758	4639	14.1						465.50
KLX13A	475.50	495.50	1200	1200			16.27	4833	5031	4833	14.4						485.50
KLX13A	493.00	513.00	1200	1200			16.37	5005	5203	5005	14.7						503.00
KLX13A	507.00	527.00	1200	1200			16.08	5140	5339	5141	14.9						517.00
KLX13A	527.00	547.00	1200	1200			15.96	5336	5536	5339	15.2						537.00
KLX13A	547.00	567.00	1200	1200			16.27	5532	5731	5533	15.5						557.00
KLX13A	562.50	582.50	1200	3600			15.98	5685	5883	5691	15.8						572.50

<b>Table</b>	<b>plu_s_hole_test_ed1</b> PLU Single hole tests, pumping/injection. Basic evaluation
--------------	--

Column	Datatype	Unit	Column Description
site	CHAR		Investigation site name
activity_type	CHAR		Activity type code
start_date	DATE		Date (yymmdd hh:mm:ss)
stop_date	DATE		Date (yymmdd hh:mm:ss)
project	CHAR		project code
idcode	CHAR		Object or borehole identification code
secup	FLOAT	m	Upper section limit (m)
seclow	FLOAT	m	Lower section limit (m)
section_no	INTEGER	number	Section number
test_type	CHAR		Test type code (1-7), see table description!
formation_type	CHAR		Formation type code. 1: Rock, 2: Soil (superficial deposits)
lp	FLOAT	m	Hydraulic point of application for test section, see descr.
seclen_class	FLOAT	m	Planned ordinary test interval during test campaign.
spec_capacity_q_s	FLOAT	m**2/s	Specific capacity (Q/s) of test section, see table descrpt.
value_type_q_s	CHAR		0:true value,-1:Q/s<lower meas.limit,1:Q/s>upper meas.limit
transmissivity_tq	FLOAT	m**2/s	Transmissivity based on Q/s, see table description
value_type_tq	CHAR		0:true value,-1:TQ<lower meas.limit,1:TQ>upper meas.limit.
bc_tq	CHAR		Best choice code. 1 means TQ is best choice of T, else 0
transmissivity_moye	FLOAT	m**2/s	Transmissivity, TM, based on Moye (1967)
bc_tm	CHAR		Best choice code. 1 means Tmoye is best choice of T, else 0
value_type_tm	CHAR		0:true value,-1:TM<lower meas.limit,1:TM>upper meas.limit.
hydr_cond_moye	FLOAT	m/s	K_M: Hydraulic conductivity based on Moye (1967)
formation_width_b	FLOAT	m	b:Aquifer thickness repr. for T(generally b=Lw) ,see descr.
width_of_channel_b	FLOAT	m	B:Inferred width of formation for evaluated TB
tb	FLOAT	m**3/s	TB:Flow capacity in 1D formation of T & width B, see descr.
l_measl_tb	FLOAT	m**3/s	Estimated lower meas. limit for evaluated TB,see description
u_measl_tb	FLOAT	m**3/s	Estimated upper meas. limit of evaluated TB,see description
sb	FLOAT	m	SB:S=storativity,B=width of formation,1D model,see descrpt.
assumed_sb	FLOAT	m	SB* : Assumed SB,S=storativity,B=width of formation,see...
leakage_factor_lf	FLOAT	m	Lf:1D model for evaluation of Leakage factor
transmissivity_tt	FLOAT	m**2/s	TT:Transmissivity of formation, 2D radial flow model,see...
value_type_tt	CHAR		0:true value,-1:TT<lower meas.limit,1:TT>upper meas.limit,
bc_tt	CHAR		Best choice code. 1 means TT is best choice of T, else 0
l_measl_q_s	FLOAT	m**2/s	Estimated lower meas. limit for evaluated TT,see table descr
u_measl_q_s	FLOAT	m**2/s	Estimated upper meas. limit for evaluated TT,see description
storativity_s	FLOAT		S:Storativity of formation based on 2D rad flow,see descr.
assumed_s	FLOAT		Assumed Storativity,2D model evaluation,see table descr.
bc_s	FLOAT		Best choice of S (Storativity) ,see descr.
ri	FLOAT	m	Radius of influence
ri_index	CHAR		ri index=index of radius of influence :-1,0 or 1, see descr.
leakage_coeff	FLOAT	1/s	K'/b':2D rad flow model evaluation of leakage coeff,see desc
hydr_cond_ksf	FLOAT	m/s	Ksf:3D model evaluation of hydraulic conductivity,see desc.
value_type_ksf	CHAR		0:true value,-1:Ksf<lower meas.limit,1:Ksf>upper meas.limit,
l_measl_ksf	FLOAT	m/s	Estimated lower meas.limit for evaluated Ksf,see table desc.
u_measl_ksf	FLOAT	m/s	Estimated upper meas.limit for evaluated Ksf,see table descr
spec_storage_ssf	FLOAT	1/m	Ssf:Specific storage,3D model evaluation,see table descr.
assumed_ssf	FLOAT	1/m	Ssf*:Assumed Spec.storage,3D model evaluation,see table des.
c	FLOAT	m**3/pa	C: Wellbore storage coefficient; flow or recovery period
cd	FLOAT		CD: Dimensionless wellbore storage coefficient
skin	FLOAT		Skin factor;best estimate of flow/recovery period,see descr.
dt1	FLOAT	s	Estimated start time of evaluation, see table description
dt2	FLOAT	s	Estimated stop time of evaluation. see table description
t1	FLOAT	s	Start time for evaluated parameter from start flow period
t2	FLOAT	s	Stop time for evaluated parameter from start of flow period
dte1	FLOAT	s	Start time for evaluated parameter from start of recovery
dte2	FLOAT	s	Stop time for evaluated parameter from start of recovery
p_horner	FLOAT	kPa	p*:Horner extrapolated pressure, see table description
transmissivity_t_nlr	FLOAT	m**2/s	T_NLR Transmissivity based on None Linear Regression...
storativity_s_nlr	FLOAT		S_NLR=storativity based on None Linear Regression,see..
value_type_t_nlr	CHAR		0:true value,-1:T_NLR<lower meas.limit,1:>upper meas.limit
bc_t_nlr	CHAR		Best choice code. 1 means T_NLR is best choice of T, else 0
c_nlr	FLOAT	m**3/pa	Wellbore storage coefficient, based on NLR, see descr.
cd_nlr	FLOAT		Dimensionless wellbore storage constant, see table descrip.
skin_nlr	FLOAT		Skin factor based on Non Linear Regression,see desc.
transmissivity_t_grf	FLOAT	m**2/s	T_GRF:Transmissivity based on Genelized Radial Flow,see...
value_type_t_grf	CHAR		0:true value,-1:T_GRF<lower meas.limit,1:>upper meas.limit
bc_t_grf	CHAR		Best choice code. 1 means T_GRF is best choice of T, else 0
storativity_s_grf	FLOAT		S_GRF:Storativity based on Generalized Radial Flow, see des.
flow_dim_grf	FLOAT		Inferred flow dimeision based on Generalized Rad. Flow model
comment	VARCHAR	no_unit	Short comment to the evaluated parameters
error_flag	CHAR		If error_flag = "" then an error occurred and an error
in_use	CHAR		If in_use = "" then the activity has been selected as
sign	CHAR		Signature for QA data ackcknowledge (QA - OK)



idcode	start_date	stop_date	secup	seclow	section_no	test_type	formation_t pe	lp	seclen_class	spec_capacity_q_s	value_type_q_ s	transmissivity_tq	value_type_tq	bc_tq	transmissivity_moy e
KLX13A	2007-02-15 09:48:00	2007-02-15 14:06:00	102.50	202.50		3	1	152.50	100	3.22E-06	0				4.19E-06
KLX13A	2007-02-15 15:34:00	2007-02-15 17:30:00	202.50	302.50		3	1	252.50	100	1.80E-06	0				2.34E-06
KLX13A	2007-02-16 07:58:00	2007-02-16 10:27:00	302.50	402.50		3	1	352.50	100	2.35E-04	0				3.06E-04
KLX13A	2007-02-16 11:52:00	2007-02-16 13:43:00	395.50	495.50		3	1	445.50	100	9.69E-05	0				1.26E-04
KLX13A	2007-02-16 15:44:00	2007-02-16 17:35:00	482.50	582.50		3	1	532.50	100	5.20E-06	0				6.77E-06
KLX13A	2007-02-17 18:25:00	2007-02-17 20:28:00	102.50	122.50		3	1	112.50	20	2.79E-06	0				2.92E-06
KLX13A	2007-02-18 08:25:00	2007-02-18 10:31:00	122.50	142.50		3	1	132.50	20	7.23E-10	0				7.57E-10
KLX13A	2007-02-18 13:24:00	2007-02-18 14:46:00	162.50	182.50		3	1	172.50	20	1.08E-07	0				1.13E-07
KLX13A	2007-02-18 16:10:00	2007-02-18 17:42:00	182.50	202.50		3	1	192.50	20	2.56E-07	0				2.67E-07
KLX13A	2007-02-18 18:12:00	2007-02-18 19:32:00	202.50	222.50		3	1	212.50	20	3.67E-07	0				3.84E-07
KLX13A	2007-02-19 09:02:00	2007-02-19 10:27:00	222.50	242.50		3	1	232.50	20	8.42E-07	0				8.81E-07
KLX13A	2007-02-19 11:04:00	2007-02-19 12:53:00	242.50	262.50		3	1	252.50	20	1.81E-08	0				1.89E-08
KLX13A	2007-02-19 14:13:00	2007-02-19 15:40:00	262.50	282.50		3	1	272.50	20	6.32E-08	0				6.62E-08
KLX13A	2007-02-19 16:17:00	2007-02-19 17:40:00	282.50	302.50		3	1	292.50	20	8.83E-07	0				9.24E-07
KLX13A	2007-02-19 18:12:00	2007-02-19 19:37:00	302.50	322.50		3	1	312.50	20	3.96E-06	0				4.15E-06
KLX13A	2007-02-20 08:18:00	2007-02-20 09:42:00	322.50	342.50		3	1	332.50	20	7.93E-08	0				8.29E-08
KLX13A	2007-02-20 10:20:00	2007-02-20 11:43:00	342.50	362.50		3	1	352.50	20	2.09E-05	0				2.19E-05
KLX13A	2007-02-20 12:56:00	2007-02-20 14:18:00	355.50	375.50		3	1	365.50	20	1.71E-05	0				1.79E-05
KLX13A	2007-02-20 15:00:00	2007-02-20 16:26:00	375.50	395.50		3	1	385.50	20	2.91E-04	0				3.04E-04
KLX13A	2007-02-20 17:07:00	2007-02-20 18:30:00	395.50	415.50		3	1	405.50	20	2.18E-05	0				2.29E-05
KLX13A	2007-02-21 08:38:00	2007-02-21 10:02:00	415.50	435.50		3	1	425.50	20	7.73E-06	0				8.09E-06
KLX13A	2007-02-21 10:41:00	2007-02-21 12:03:00	435.50	455.50		3	1	445.50	20	2.65E-05	0				2.77E-05
KLX13A	2007-02-21 13:02:00	2007-02-21 14:30:00	455.50	475.50		3	1	465.50	20	1.53E-05	0				1.60E-05
KLX13A	2007-02-21 15:28:00	2007-02-21 16:54:00	475.50	495.50		3	1	485.50	20	3.01E-06	0				3.14E-06
KLX13A	2007-02-21 17:33:00	2007-02-21 18:58:00	493.00	513.00		3	1	503.00	20	2.93E-06	0				3.07E-06
KLX13A	2007-02-22 08:14:00	2007-02-22 09:36:00	507.00	527.00		3	1	517.00	20	7.31E-07	0				7.65E-07
KLX13A	2007-02-22 10:14:00	2007-02-22 11:38:00	527.00	547.00		3	1	537.00	20	8.18E-07	0				8.55E-07
KLX13A	2007-02-22 13:02:00	2007-02-22 14:22:00	547.00	567.00		3	1	557.00	20	8.05E-07	0				8.42E-07
KLX13A	2007-02-22 15:00:00	2007-02-22 17:15:00	562.50	582.50		3	1	572.50	20	7.18E-08	0				7.52E-08

idcode	secup	seclow	bc_tm	value_type_tm	hydr_cond_m_oye	formation_wi_dth_b	width_of_channel_b	l_measl_tb	u_measl_tb	sb	assumed_sb	leakage_fact_or_lf	transmissivity_tt	value_type_tt	bc_tt	l_measl_q_s	u_measl_q_s
KLX13A	102.50	202.50	0	0	4.19E-08								2.56E-06	0	1	1.00E-06	8.00E-06
KLX13A	202.50	302.50	0	0	2.34E-08								1.50E-06	0	1	8.00E-07	6.00E-06
KLX13A	302.50	402.50	0	0	3.06E-06								4.12E-04	0	1	7.00E-05	8.00E-04
KLX13A	395.50	495.50	0	0	1.26E-06								9.16E-05	0	1	1.00E-05	2.00E-04
KLX13A	482.50	582.50	0	0	6.77E-08								5.74E-06	0	1	1.00E-06	7.00E-06
KLX13A	102.50	122.50	0	0	1.46E-07								2.33E-06	0	1	1.00E-06	7.00E-06
KLX13A	122.50	142.50	0	0	3.79E-11								1.03E-10	0	1	7.00E-11	4.00E-10
KLX13A	162.50	182.50	0	0	5.65E-09								1.87E-07	0	1	9.00E-08	6.00E-07
KLX13A	182.50	202.50	0	0	1.34E-08								2.54E-07	0	1	1.00E-07	8.00E-07
KLX13A	202.50	222.50	0	0	1.92E-08								6.41E-07	0	1	4.00E-07	3.00E-06
KLX13A	222.50	242.50	0	0	4.41E-08								5.69E-07	0	1	2.00E-07	1.00E-06
KLX13A	242.50	262.50	0	0	9.45E-10								2.49E-08	0	1	1.00E-08	9.00E-08
KLX13A	262.50	282.50	0	0	3.31E-09								1.16E-07	0	1	3.00E-08	3.00E-07
KLX13A	282.50	302.50	0	0	4.62E-08								2.04E-06	0	1	9.00E-07	5.00E-06
KLX13A	302.50	322.50	0	0	2.08E-07								2.05E-05	0	1	1.00E-06	4.00E-05
KLX13A	322.50	342.50	0	0	4.15E-09								1.58E-07	0	1	8.00E-08	5.00E-07
KLX13A	342.50	362.50	0	0	1.10E-06								4.83E-05	0	1	2.00E-05	7.00E-05
KLX13A	355.50	375.50	0	0	8.95E-07								4.10E-05	0	1	2.00E-05	8.00E-05
KLX13A	375.50	395.50	0	0	1.52E-05								4.38E-04	0	1	7.00E-05	8.00E-04
KLX13A	395.50	415.50	0	0	1.15E-06								4.82E-05	0	1	3.00E-05	7.00E-05
KLX13A	415.50	435.50	0	0	4.05E-07								1.85E-05	0	1	9.00E-06	5.00E-05
KLX13A	435.50	455.50	0	0	1.39E-06								5.53E-05	0	1	3.00E-05	8.00E-05
KLX13A	455.50	475.50	0	0	8.00E-07								2.90E-05	0	1	1.00E-05	7.00E-05
KLX13A	475.50	495.50	0	0	1.57E-07								3.47E-06	0	1	1.00E-06	8.00E-06
KLX13A	493.00	513.00	0	0	1.54E-07								3.53E-06	0	1	1.00E-06	6.00E-06
KLX13A	507.00	527.00	0	0	3.83E-08								9.13E-07	0	1	7.00E-07	4.00E-06
KLX13A	527.00	547.00	0	0	4.28E-08								9.46E-07	0	1	7.00E-07	5.00E-06
KLX13A	547.00	567.00	0	0	4.21E-08								1.08E-06	0	1	8.00E-07	5.00E-06
KLX13A	562.50	582.50	0	0	3.76E-09								3.67E-08	0	1	1.00E-08	5.00E-08

idcode	secup	seclow	storativity_s	assumed_s	bc_s	ri	ri_index	leakage_c oeff	hydr_cond_ksf	value_type_ksf	l_measl_k sf	u_measl_ks f	spec_storage_ssf	assumed_ss f	c	cd	skin	dt1	dt2
KLX13A	102.50	202.50	1.00E-06	1.00E-06		21.91	-1								1.11E-10	1.22E-02	-2.39	4.2	58.8
KLX13A	202.50	302.50	1.00E-06	1.00E-06		106.06	0								4.41E-10	4.86E-02	-2.39	123.6	1612.8
KLX13A	302.50	402.50	1.00E-06	1.00E-06		#NV	1				#NV	#NV			#NV	#NV	-0.67	#NV	#NV
KLX13A	395.50	495.50	1.00E-06	1.00E-06		296.50	0								2.00E-08	2.20E+00	-3.86	336.6	1554.0
KLX13A	482.50	582.50	1.00E-06	1.00E-06		47.38	1								1.13E-09	1.25E-01	0.43	16.8	183.6
KLX13A	102.50	122.50	1.00E-06	1.00E-06		29.32	-1								2.33E-10	2.57E-02	-2.22	13.2	110.4
KLX13A	122.50	142.50	1.00E-06	1.00E-06		11.15	1								3.28E-11	3.62E-03	-1.23	#NV	#NV
KLX13A	162.50	182.50	1.00E-06	1.00E-06		51.46	0								6.25E-11	6.89E-03	4.20	91.2	1000.8
KLX13A	182.50	202.50	1.00E-06	1.00E-06		13.78	-1								5.60E-11	6.17E-03	0.25	18.6	73.8
KLX13A	202.50	222.50	1.00E-06	1.00E-06		70.02	0								6.74E-11	7.43E-03	3.64	11.4	799.2
KLX13A	222.50	242.50	1.00E-06	1.00E-06		49.26	1								1.52E-10	1.68E-02	0.15	289.2	1095.0
KLX13A	242.50	262.50	1.00E-06	1.00E-06		31.09	0								1.01E-10	1.11E-02	2.75	160.8	951.6
KLX13A	262.50	282.50	1.00E-06	1.00E-06		45.67	0								2.40E-11	2.65E-03	-2.23	162.0	1064.4
KLX13A	282.50	302.50	1.00E-06	1.00E-06		93.52	0								1.98E-10	2.18E-02	6.87	31.8	789.0
KLX13A	302.50	322.50	1.00E-06	1.00E-06		166.51	0								2.09E-10	2.30E-02	20.30	20.4	479.4
KLX13A	322.50	342.50	1.00E-06	1.00E-06		45.02	1								8.31E-11	9.16E-03	6.70	78.0	999.0
KLX13A	342.50	362.50	1.00E-06	1.00E-06		206.30	0								5.10E-09	5.62E-01	5.25	54.6	826.8
KLX13A	355.50	375.50	1.00E-06	1.00E-06		198.02	0								1.94E-09	2.14E-01	6.02	22.8	1150.2
KLX13A	375.50	395.50	1.00E-06	1.00E-06		#NV	1				#NV	#NV			#NV	#NV	-2.83	#NV	#NV
KLX13A	395.50	415.50	1.00E-06	1.00E-06		206.19	0								1.64E-09	1.81E-01	4.42	13.2	966.0
KLX13A	415.50	435.50	1.00E-06	1.00E-06		162.29	0								1.05E-09	1.16E-01	6.02	46.8	806.4
KLX13A	435.50	455.50	1.00E-06	1.00E-06		213.40	0								3.30E-09	3.64E-01	5.47	10.8	990.0
KLX13A	455.50	475.50	1.00E-06	1.00E-06		181.59	0								1.47E-09	1.62E-01	2.94	54.6	738.6
KLX13A	475.50	495.50	1.00E-06	1.00E-06		106.80	0								3.45E-10	3.80E-02	-0.81	36.6	1119.0
KLX13A	493.00	513.00	1.00E-06	1.00E-06		107.26	0								1.70E-10	1.87E-02	-0.41	510.0	1576.2
KLX13A	507.00	527.00	1.00E-06	1.00E-06		76.49	0								2.91E-10	3.21E-02	0.84	10.2	1074.0
KLX13A	527.00	547.00	1.00E-06	1.00E-06		77.17	0								1.78E-10	1.96E-02	-0.02	12.0	1095.0
KLX13A	547.00	567.00	1.00E-06	1.00E-06		79.77	0								7.06E-11	7.78E-03	0.89	16.8	1096.2
KLX13A	562.50	582.50	1.00E-06	1.00E-06		32.81	-1								8.50E-12	9.37E-04	-2.86	146.4	1101.0



Table	<b>plu_s_hole_test_obs</b> Data of observation sections of single hole test		
Column	Datatype	Unit	Column Description
site	CHAR		Investigation site name
activity_type	CHAR		Activity type code
idcode	CHAR		Object or borehole identification code
start_date	DATE		Date (yymmdd hh:mm:ss)
secup	FLOAT	m	Upper section limit (m)
seclow	FLOAT	m	Lower section limit (m)
obs_secup	FLOAT	m	Upper limit of observation section
obs_seclow	FLOAT	m	Lower limit of observation section
pi_above	FLOAT	kPa	Groundwater pressure above test section, start of flow period
pp_above	FLOAT	kPa	Groundwater pressure above test section, at stop flow period
pf_above	FLOAT	kPa	Groundwater pressure above test section at stop recovery per
pi_below	FLOAT	kPa	Groundwater pressure below test section at start flow period
pp_below	FLOAT	kPa	Groundwater pressure below test section at stop flow period
pf_below	FLOAT	kPa	Groundwater pressure below test section at stop recovery per
comments	VARCHAR		Comment text row (unformatted text)

idcode	start_date	stop_date	secup	seclow	section_no	obs_secup	obs_seclow	pi_above	pp_above	pf_above	pi_below	pp_below	pf_below	comments
KLX13A	2007-02-15 09:48:00	2007-02-15 14:06:00	102.50	202.50		203.50	595.85	958	960	930	1992	1992	1992	
KLX13A	2007-02-15 15:34:00	2007-02-15 17:30:00	202.50	302.50		303.50	595.85	1935	1936	1937	2969	2969	2968	
KLX13A	2007-02-16 07:58:00	2007-02-16 10:27:00	302.50	402.50		403.50	595.85	2916	2916	2918	3950	3958	3953	
KLX13A	2007-02-16 11:52:00	2007-02-16 13:43:00	395.50	495.50		496.50	595.85	3827	3830	3829	4861	4868	4864	
KLX13A	2007-02-16 15:44:00	2007-02-16 17:35:00	482.50	582.50		583.50	595.85	4684	4683	4684	5714	5800	5716	
KLX13A	2007-02-17 18:25:00	2007-02-17 20:28:00	102.50	122.50		123.50	595.85	954	955	958	1215	1215	1214	
KLX13A	2007-02-18 08:25:00	2007-02-18 10:31:00	122.50	142.50		143.50	595.85	1150	1151	1151	1408	1407	1407	
KLX13A	2007-02-18 13:24:00	2007-02-18 14:46:00	162.50	182.50		183.50	595.85	1542	1543	1544	1798	1797	1797	
KLX13A	2007-02-18 16:10:00	2007-02-18 17:42:00	182.50	202.50		203.50	595.85	1738	1739	1740	1992	1992	1992	
KLX13A	2007-02-18 18:12:00	2007-02-18 19:32:00	202.50	222.50		223.50	595.85	1934	1935	1936	2187	2187	2187	
KLX13A	2007-02-19 09:02:00	2007-02-19 10:27:00	222.50	242.50		243.50	595.85	2129	2130	2131	2283	2283	2282	
KLX13A	2007-02-19 11:04:00	2007-02-19 12:53:00	242.50	262.50		263.50	595.85	2326	2327	2329	2578	2577	2576	
KLX13A	2007-02-19 14:13:00	2007-02-19 15:40:00	262.50	282.50		283.50	595.85	2522	2523	2524	2772	2772	2772	
KLX13A	2007-02-19 16:17:00	2007-02-19 17:40:00	282.50	302.50		303.50	595.85	2719	2720	2721	2968	2968	2967	
KLX13A	2007-02-19 18:12:00	2007-02-19 19:37:00	302.50	322.50		323.50	595.85	2916	2917	2917	3163	3164	3163	
KLX13A	2007-02-20 08:18:00	2007-02-20 09:42:00	322.50	342.50		343.50	595.85	3110	3110	3111	3360	3359	3359	
KLX13A	2007-02-20 10:20:00	2007-02-20 11:43:00	342.50	362.50		363.50	595.85	3305	3305	3307	3554	3359	3359	
KLX13A	2007-02-20 12:56:00	2007-02-20 14:18:00	355.50	375.50		376.50	595.85	3433	3434	3434	3682	3687	3684	
KLX13A	2007-02-20 15:00:00	2007-02-20 16:26:00	375.50	395.50		396.50	595.85	3629	3630	3631	3853	3861	3857	
KLX13A	2007-02-20 17:07:00	2007-02-20 18:30:00	395.50	415.50		416.50	595.85	3826	3827	3826	4077	4080	4078	
KLX13A	2007-02-21 08:38:00	2007-02-21 10:02:00	415.50	435.50		436.50	595.85	4022	4022	4022	4271	4273	4272	
KLX13A	2007-02-21 10:41:00	2007-02-21 12:03:00	435.50	455.50		456.50	595.85	4219	4220	4219	4467	4471	4468	
KLX13A	2007-02-21 13:02:00	2007-02-21 14:30:00	455.50	475.50		476.50	595.85	4416	4416	4416	4663	4667	4664	
KLX13A	2007-02-21 15:28:00	2007-02-21 16:54:00	475.50	495.50		496.50	595.85	4613	4613	4613	4858	4859	4858	
KLX13A	2007-02-21 17:33:00	2007-02-21 18:58:00	493.00	513.00		514.00	595.85	4785	4785	4785	5030	5030	5029	
KLX13A	2007-02-22 08:14:00	2007-02-22 09:36:00	507.00	527.00		528.00	595.85	4922	4922	4922	5166	5174	5167	
KLX13A	2007-02-22 10:14:00	2007-02-22 11:38:00	527.00	547.00		548.00	595.85	5119	5119	5119	5362	5371	5363	
KLX13A	2007-02-22 13:02:00	2007-02-22 14:22:00	547.00	567.00		568.00	595.85	5315	5315	5315	5558	5557	5556	
KLX13A	2007-02-22 15:00:00	2007-02-22 17:15:00	562.50	582.50		583.50	595.85	5467	5467	5467	5710	5798	5717	

## **APPENDIX 5-2**

SICADA data tables (Pulse injection tests)



# SICADA/Data Import Template

(Simplified version v1.8)

SKB & Ergodata AB 2006

<b>File Identity</b>	
<b>Created By</b>	
<b>Created</b>	

<b>File Time</b>
<b>Zone</b>

<b>Compiled By</b>	
<b>Quality Check For Delivery</b>	
<b>Delivery Approval</b>	

<b>Activity Type</b>	KLX13A KLX 13A - Pulse test
----------------------	--------------------------------

<b>Project</b>	AP PS 400-07-006
----------------	------------------

**Activity Information**

**Additional Activity Data**

Idcode	Start Date	Stop Date	Secup (m)	Seclow (m)	Section No	Additional Activity Data				
						C30	C40	I160	P20	P200
						Company evaluating data	Company performing field work	Instrument	Field crew manager	Field crew
KLX13A	2007-02-18 11:07:00	2007-02-18 12:53:00	142.50	162.50		Golder Associates	Golder Associates	PSS 2	Stephan Rohs	Stephan Rohs, Mesgena Gebrezghi, Tomas Cronquist



<b>Table</b>	<b>plu_slug_test_ed</b> Slug- & pulse test, calculated and evaluated results
--------------	---

Column	Datatype	Unit	Column Description
site	CHAR		Investigation site name
idcode	CHAR		Object or borehole identification code
secup	FLOAT	m	
seclow	FLOAT	m	Lower section limit (m)
start_date	DATE		Date (yymmdd hh:mm:ss)
stop_date	DATE		Date (yymmdd hh:mm:ss)
activity_type	CHAR		Activity type code
sign	CHAR		Activity QA signature
error_flag	CHAR		*: Data for the activity is erroneous and should not be used
test_type	CHAR		Type of test, one of 7, see table description
formation_type	CHAR		1: Rock, 2: Soil (superficial deposits)
start_flow_period	DATE		Date and time of flow phase start (YYYYMMDD hhmmss)
dur_flow_phase_tp	FLOAT	s	Time for the flowing phase of the test (tp)
dur_rec_phase_tf	FLOAT	s	Time for the recovery phase of the test (tf)
initial_head_h0	FLOAT	m	Initial formation hydraulic head, see table description
initial_displacem_d	FLOAT	m	Initial displacement of hydraulic head,see table description
displacem_dh0_p	FLOAT	m	Initial displacement of slugtest,see table description
displacem_dh0_f	FLOAT	m	Initial displacement of bailtest,see table description
head_at_flow_end	FLOAT	m	Hydraulic head at end of flow phase,see table description
final_head_hf	FLOAT	m	Hydraulic head at the end of the recovery,see table descr.
initial_press_pi	FLOAT	kPa	Initial formation pressure
initial_press_diff_d	FLOAT	kPa	Initial pressure change from pi at time dt=0,pulse test
press_change_dpC	FLOAT	kPa	Initial pressure change;pulse test-measured
press_at_flow_end	FLOAT	kPa	Final pressure at the end of the flowing period
final_press_pf	FLOAT	kPa	Final pressure at the end of the recovery period
formation_width_b	FLOAT	m	b:Interpreted formation thickness repr. for evaluated T,see
transmissivity_ts	FLOAT	m**2/s	Ts: Transmissivity based on slugtest, see table description
value_type_ts	CHAR		0:true value,-1:Ts<lower meas.limit,1:Ts>upper meas.limit
bc_ts	CHAR		Best choice code.1 means Ts is best choice of transm.,else 0
transmissivity_tp	FLOAT	m**2/s	TP: Transmissivity based on pulse test, see table descript.
value_type_tp	CHAR		0:true value,-1:Tp<lower meas.limit,1:Tp>upper meas.limit
bc_tp	CHAR		Best choice code.1 means Tp is best choice of transm.,else 0
l_meas_limit_t	FLOAT	m**2	Estimated lower measurement limit for Ts orTp,see descript.
u_meas_limit_t	FLOAT	m**2	Estimated upper measurement limit for Ts & Tp, see descript.
storativity_s	FLOAT		S= Storativity, see table description
assumed_s	FLOAT		S*=assumed storativity, see table description
skin	FLOAT		Skin factor
assumed_skin	FLOAT		Asumed skin factor
c	FLOAT	m**3/pa	Well bore storage coefficient
fluid_temp_tew	FLOAT	oC	Fluid temperature in the test section, see table description
fluid_elcond_ecw	FLOAT	mS/m	Fluid electric conductivity in test section,see table descri
fluid_salinity_tds	FLOAT	mg/l	Total salinity of the test section fluid (EC), see descr.
fluid_salinity_tdsr	FLOAT	mg/l	Total salinity of the test section fluid (samples),see descr
dt1	FLOAT	s	Estimated start time of evaluation, see table description
dt2	FLOAT	s	Estimated stop time of evaluation, see table description
reference	CHAR		SKB report No for reports describing data and evaluation
comments	CHAR		Short comment to evaluated parameters

idcode	start_date	stop_date	secup (m)	seclow (m)	section_no	test_type	formation_type	start_flow_period	dur_flow_phase_tp (s)	dur_rec_phase_tf (s)	initial_head_h0 (m)	initial_displacement_dh0 (m)	displacement_dh0_p (m)	displacement_dh0_f (m)	head_at_flow_end_hp (m)	final_head_hf (m)
KLX13A	2007-02-18 11:07:00	2007-02-18 12:53:00	142.50	162.50		4B	1	2007-02-18 11:51:33	10	3600						

idcode	secup (m)	seclow (m)	initial_pressure_pi (kPa)	initial_pressure_diff_dp0 (kPa)	pressure_change_dp0_p (kPa)	pressure_at_flow_end_pp (kPa)	final_pressure_pf (kPa)	formation_width_b (m)	transmissivity_ts (m**2/s)	value_type_e_ts	bc_ts	transmissivity_tp (m**2/s)	value_type_e_tp	bc_tp	l_meas_limit_t (m**2)	u_meas_limit_t (m**2)
KLX13A	142.50	162.50	1599	234		1833	1674					2.86E-11	0	1	9.00E-12	7.00E-11

idcode	secup (m)	seclow (m)	storativity_s	assumed_s	skin	assumed_skin	c (m**3/pa)	fluid_temp_tew (oC)	fluid_elcnd_ecw (mS/m)	fluid_salinity_tdswn (mg/l)	fluid_salinity_tdswn (mg/l)	dt1 (s)	dt2 (s)	reference	comments
KLX13A	142.50	162.50	1.00E-06	1.00E-06	-0.3		2.37E-11	8.5				#NV	#NV		

<b>Table</b>	<b>plu_s_hole_test_obs</b> Data of observation sections of single hole test
--------------	--

<b>Column</b>	<b>Datatype</b>	<b>Unit</b>	<b>Column Description</b>
site	CHAR		Investigation site name
activity_type	CHAR		Activity type code
idcode	CHAR		Object or borehole identification code
start_date	DATE		Date (yymmdd hh:mm:ss)
secup	FLOAT	m	Upper section limit (m)
seclow	FLOAT	m	Lower section limit (m)
sign	CHAR		Activity QA signature
error_flag	CHAR		*: Data for the activity is erroneous and should not be used
obs_secup	FLOAT	m	Upper limit of observation section
obs_seclow	FLOAT	m	Lower limit of observation section
pi_above	FLOAT	kPa	Groundwater pressure above test section, start of flow period
pp_above	FLOAT	kPa	Groundwater pressure above test section, at stop flow period
pf_above	FLOAT	kPa	Groundwater pressure above test section at stop recovery per
pi_below	FLOAT	kPa	Groundwater pressure below test section at start flow period
pp_below	FLOAT	kPa	Groundwater pressure below test section at stop flow period
pf_below	FLOAT	kPa	Groundwater pressure below test section at stop recovery per
comments	VARCHAR		Comment text row (unformatted text)

			(m)	(m)		(m)	(m)	(kPa)	(kPa)	(kPa)	(kPa)	(kPa)	(kPa)	
idcode	start_date	stop_date	secup	seclow	section_no	obs_secup	obs_seclow	pi_above	pp_above	pf_above	pi_below	pp_below	pf_below	comments
KLX13A	2007-02-18 11:07:00	2007-02-18 12:53:00	142.50	162.50		163.50	595.85	1.35E+03	1.35E+03	1.35E+03	1603	1602	1602	

## **APPENDIX 5-3**

SICADA data tables (Interference tests)

	SICADA/Data Import Template	(Simplified version v1.7)
SKB & Ergodata AB 2005		

<b>File Identity</b>	
<b>Created By</b>	
<b>Created</b>	

<b>File Time</b>
<b>Zone</b>

<b>Compiled By</b>	
<b>Quality Check For Delivery</b>	
<b>Delivery Approval</b>	

<b>Activity Type</b>	KLX13A KLX13A Interference test bottom zone
----------------------	--

<b>Project</b>	AP PS 400-07-006
----------------	------------------

Activity Information						Additional Activity Data								
Idcode	Start Date	Stop Date	Secup (m)	Seclow (m)	Section No	C30	C40	I160	P20	P200	P220	R240	R25	R85
						Company evaluating data	performing field work	Instrument	Field crew manager	Field crew	evaluating data	calibration type	Report	Pumped/injected borehole
KLX13A	2007.02.22 15:00	2007.02.22 17:15	583.50	595.85	Pb	Golder	Golder	PSS2	Stephan Rohs		Stephan Rohs			KLX13A

Table	<b>plu_inf_test_obs_d</b> PLU interference test, Observation section data		
Column	Datatype	Unit	Column Description
site	CHAR		Investigation site name
activity_type	CHAR		
start_date	DATE		
stop_date	DATE		
project	CHAR		project code
idcode	CHAR		Object or borehole identification code
secup	FLOAT	m	Upper section limit (m)
seclow	FLOAT	m	Lower section limit (m)
section_no	INTEGER	number	Section number
test_type	CHAR		Test type code, one of 7, see table description
formation_type	CHAR		1: Rock, 2: Soil (superficial deposits)
start_flow_period	DATE	yyyymmdd	Date and time start of pumping/injection(YMMDDhhmmss)
stop_flow_period	DATE	yyyymmdd	Date and time stop of pumping/injection(YMMDDhhmmss)
test_borehole	CHAR		Idcode of pumped/injected borehole
test_secup	FLOAT	m	Upper limit of pumped/injected section
test_seclow	FLOAT	m	Lower limit of pumped/injected section
lp	FLOAT	m	Hydraulic point of application, see table description
radial_distance_rs	FLOAT	m	Radial distance: test sec.-obs.sec., see table description
shortest_distance_rt	FLOAT	m	Shortest distance: test sec.-obs.sec., see table description
time_lag_press_dtl	FLOAT	s	Time lag, pressure response obs. hole. See table description
initial_head_hi	FLOAT	m	Hydraulic head in observationsection,at start of flow period
head_at_flow_end_h	FLOAT	m	Hydraulic head in observation section at stop of flow period
final_head_hf	FLOAT	m	Hydraulic head in obs. section at end of recovery period.
initial_press_pi	FLOAT	kPa	Groundwater pressure in obs.section at start of flow period
press_at_flow_end_f	FLOAT	kPa	Groundwater pressure in obs. section at stop of flow period
final_press_pf	FLOAT	kPa	Groundwater pressure in obs.section at stop of the recovery
fluid_temp_teo	FLOAT	oC	Measured fluid temperature in obs.section,see descr.
fluid_elcond_eco	FLOAT	mS/m	Measured fluid el. conductivity in obs.section,see descr.
fluid_salinity_tdso	FLOAT	mg/l	Total dissolved solids of section fluid,based on EC see desc
fluid_salinity_tdsom	FLOAT	mg/l	Tot disolved solids of section fluid based on analysis,see..
reference	CHAR		SKB report No for reports describing data and evaluation
comment	CHAR		Short comment to evaluated data.
error_flag	CHAR		If error_flag = "*" then an error ocured and an error
in_use	CHAR		If in_use = "*" then the activity has been selected as
sign	CHAR		Activity QA signature

idcode	start_date	stop_date	secup (m)	seclow (m)	section_no	test_type	formation_type	start_flow_period (yyyymmdd)	stop_flow_period (yyyymmdd)	test_borehole	test_section (m)	test_section_low (m)	lp (m)	radial_distance (m)
KLX13A	2007-02-22 15:00:00	2007-02-22 17:15:00	583.50	595.85	Pb	2	1	2007-02-22 15:53:03	2007-02-22 16:13:13	KLX13A	562.50	582.50		5.00

idcode	secup (m)	seclow (m)	shortest_distance (m)	time_lag_pressure (s)	initial_head_high (m)	head_at_flow_low_end (m)	final_head_high (m)	initial_pressure (kPa)	press_at_flow_end (kPa)	final_pressure (kPa)	fluid_temperature (oC)	fluid_electrical conductivity (mS/m)	fluid_salinity (mg/l)	fluid_salinity (mg/l)	reference	comment
KLX13A	583.50	595.85						5712.00	5798.00	5717.00	#NV					



